

Site Development Policies and Procedures

Closed Circuit Inspection of Storm Sewer Systems Effective Date: July 1, 2021

Supersedes policy dated: July 1, 2020

Issued by:

Thomas J. Smith

Director of Public Works & 1.5

Prince William County Closed Circuit (CC) Inspection Process

- 1. A Closed Circuit (CC) Inspection of the entire storm sewer system documenting no deficiencies shall occur prior to obtaining final bond release for all residential and commercial projects per County policy.
- 2. Prior to application for CC Inspection, the project site must conform to conditions listed below; failure to have site ready for inspection will result in cancellation of the scheduled CC inspection. Minimum conditions include:
 - Base asphalt is laid down.
 - Storm drainage systems flushed, cleaned, and free of debris.
 - All storm structures are set to their final grades- inverts, steps, tops, and grates installed.
 - All structures to be inspected must be marked in field (per approved plan) prior to inspection.
 - All stormwater management facilities are accessible via camera van vehicle and to County staff.
- 3. Once confirmation of the site's readiness for CC inspection has occurred, remit the items listed below to the Watershed Management Branch at the address below in item #5:
 - Unmarked, full-size (24" x36") copies of the approved site plan to include the most current unit price list (UPL), most current cover sheet and <u>all</u> revisions related to storm drainage systems.
 - Storm sewer profiles
 - Storm water management plan (if applicable)
 - Application for CC inspection
 - Applicable fees
- 4. For the most current fees, please refer to the PWC Land Development Fee Schedule at the following URL: http://www.pwcgov.org/LDDFeeSchedule.
 - The current fee is \$2.44 per linear foot for all areas to be inspected by County staff.
 - A separate CCTV Inspection Request Form and fee is required for each section and phase of a project, especially for large subdivision developments.
 - A minimum fee of \$292.60 will be assessed for inspection of storm easements totaling less than 250 linear feet.
 - Camera Van Re-inspection / Not Ready fee of \$292.60 (per request) will apply to any site
 requesting an inspection whose punch list items have not been corrected or the storm drainage
 system cannot be inspected / re-inspected due to inaccessibility, trash, debris, or standing water

in the system. The re-inspection / not ready fee must be paid in advance of any additional inspections.

5. Fees can be paid by cash, credit card, or check. Credit card payments can be made over the phone (we **do not accept American Express**) once we have received the application and applicable site plan sets. Cash payments must be made in person; checks shall be made payable to "Prince William County" and can be remitted by mail or in person along with the items listed in item #3 for submission to the address below:

PWC Department of Public Works Watershed Management Branch 5 County Complex Court, Suite 170 Prince William, VA 22192

- 6. Upon payment of all fees and receipt of all applicable items listed in item #3, County staff will add the project to the active Camera Van job list. County staff will strive to schedule and conduct an inspection within a timely manner; punch lists shall be generated based on the most current approved set of plans provided.
- 7. Punch lists are valid for eighteen (18) months from date of first inspection. Within this time frame, the developer shall correct all deficiencies noted on the punch list and schedule a re-inspection of all punch list items in order to obtain final approval. All deficiencies should be corrected as soon as possible; waiting too long may add new items to the punch list upon re-inspection. This initial re-inspection is included in the original fee.
- 8. The developer shall obtain final bond release within **eighteen (18) months** from <u>initial</u> punch list date (not punch list <u>completion date</u>). Failure to correct punch list deficiencies within the eighteen (18) month period will require the developer to begin the CC TV inspection process of the entire system **again**, including payment of all fees assessed.



COUNTY OF PRINCE WILLIAM DEPARTMENT OF PUBLIC WORKS

5 County Complex Court, Suite 170, DS-930 Prince William, Virginia 22192-5308 Main (703) 792-7070 Facsimile: (703) 792-6297

FY22 Closed Circuit Storm Sewer Inspection Request Application (Effective July 1, 2021- June 30, 2022)

Staff Use Only	
ILP # Amount received (@ \$2.44/linear foot):	
	RCPT
Emailed to CCTV Inspector Date:	Site Inspection Area:
(Complete Checklist Below) Most current cover sheet. One (1) set of full size (24"x36") Storm Plan/Grading Plan Sheets All applicable revisions involving storm drainage systems One (1) copy of Storm Profile Sheet One (1) copy of most current Unit Price List One (1) copy of the Storm Water Management Plan and Profile Payment amount listed in TOTAL AMOUNT DUE box	Before requesting an inspection, please make sure your site meets the minimum requirements listed on page 1, item #2. Please use checklist below for your reference: Base asphalt is laid down Storm drainage systems flushed, cleaned, and free of debris. All storm structures are set to their final grades- inverts, steps, tops, and grates installed. All structures to be inspected must be marked in field (per approved plan) prior to inspection. All storm water management facilities are accessible via camera van vehicle and to County staff
LND Number:	
(Site Permit Number) Approved Site Plan Number: Approved Site Plan Name:	Section: Phase:
Site Address:	
Contact Name: Number:	
Print Name	
Email: Fax #:	
FY22 fee currently \$2.44 per linear foot	
1) Storm Sewer pipe footage (within proposed VDOT R/V	
2) Storm Sewer pipe footage (within dedicated County ea	
3) Storm Sewer pipe footage (within private easements)	L.F.
TOTAL LINEAR FOOTAGE TO BE INSPECTED (1 through 3)	L.F.
TOTAL AMOUNT DUE (\$2.44 linear foot) (minimum fee: \$29	92.60)
By signing below, I, certify that all information is accurate. I have read and understand the CCTV process. I also certify that my site is ready for inspection and all storm drainage pipe systems are cleaned, flushed, and pipe inverts are installed, structures for inspection are marked accordingly. I also certify that any steps, tops, or grates are installed and ready for County staff CCTV inspection as of this date:	
(Printed Name)	(Signature)

Effective 07/2021 FY 22 CCTVPROCESS