Statutory Framework Review & Peer Research Summary

Data Centers DCSM & Zoning Ordinance Update Project

9.25.2024








Table of Contents

Section 1 | Introduction and Methodol Section 2 | State Statues Overview Section 3 | Prince William County Regu Section 4 | Peer Communities Research Section 5 | Conclusions & Next Steps Section 6 | Appendix



ogy	4
	8
ulatory Context	16
1	26
	50
	52

Section 1 | Introduction and Methodology

Background & Context

Prince William County has emerged as a prominent hub in the global data center industry, leveraging its advantageous location, conducive business environment, and advanced infrastructure to become one of the leading regions for data center development worldwide. This surge in data center establishments has been driven by the County's strategic proximity to major metropolitan areas, its competitive tax incentives, and its well-developed utility and transportation networks. As a result, Prince William County now boasts one of the highest concentrations of data centers globally.

However, this rapid growth has brought with it a range of unforeseen impacts on the local community and environment. The influx of data centers has led to significant changes in land use, infrastructure demands, and community dynamics. With data centers occupying large tracts of land and requiring substantial resources, there have been both positive and challenging consequences that warrant thorough examination.

Analysis Overview

To address these issues and provide a comprehensive understanding of the current landscape, this report offers an in-depth analysis of key regulatory documents and practices that shape data center development in Prince William County. The analysis includes:

- » Virginia Statutes: A review of Dillon's Rule governance, and state-level regulations that influence data center operations and requlation of development within Virginia. This includes locality zoning requirements, environmental regulations, and other relevant state policies.
- County Zoning Ordinance (Chapter 32): A detailed evaluation of the specific zoning regulations that govern where and how data centers can be established in Prince William County. This chapter outlines zoning requirements, restrictions, and design standards for data center projects.
- County's Design and Construction Manual » (DCSM): An examination of the design and

construction standards imposed by the Methodology County to ensure that data centers meet The methodology employed for researching local aesthetic, safety, and environmental data center regulations across various jurisdicstandards. This manual includes requiretions involved a comprehensive approach that ments on infrastructure, landscaping, envicombined code research, email correspondence, ronmental and transportation systems. and video conference interviews. The research » 2023-2024 Rezoning Cases and Proffers: was structured into three tiers based on the A detailed look at recent rezoning applilevel of interaction and data collection required cations and proffer agreements related to for each jurisdiction. The following outlines the data centers. This section will assess how methodology used, including details on each developers and the County have negotier and the specific topics covered during the tiated conditions to address community research process.

impacts and infrastructure needs. It's worth noting that these cases are reviewed against guidance from the Comprehensive and Strategic Plans, and the team did not review these policy documents in full for this report.

Tier 1: Code Research In addition to reviewing local and state-level Method: Detailed examination of zoning documents, the consulting team has undertaken a comprehensive analysis of development codes ordinances. This involved reviewing zoning from a wide range of jurisdictions. This research ordinances and related documents to extract includes a comparative study of data center relevant information on data center and/or industrial regulations. regulations across 20 jurisdictions within Virginia and in other states and countries. By examining Jurisdictions: these diverse regulatory approaches, the report » Montgomery County, MD aims to offer valuable insights into current practices that could guide future policy and » Salt Lake County, UT planning in Prince William County.

Beyond code analysis, the team has conducted interviews via email and video conference with various key staff members. These discussions have explored the impacts and challenges faced by other communities in relation to data center development and the strategies they have employed to address these issues.

Through this comprehensive analysis, the report Method: In addition to code research, email seeks to offer a nuanced understanding of the correspondence was used to seek additional complexities surrounding data center develinformation for insights and context and clarify opment, including its regulatory framework, aspects of data center regulations. community impact, and potential future policies. It is intended to support informed decision-making Jurisdictions: and strategic planning as the County continues » Tower Hamlets, London, UK to navigate the evolving landscape of data center » Slough, UK growth.

RESEARCH TIERS AND JURISDICTIONS

The research was organized into three tiers, each representing a different level of engagement with the jurisdictions. The tiers were as follows:

- - » Irving, TX
- » Denver, CO
- » Maricopa County, AZ
- » Middlesex County, NJ
- » Hillsboro, OR

Tier 2: Code Research + Email Correspondence

- » Frankfurt, Germany
- Amsterdam, Netherlands »
- Virginia Beach, VA
- Stafford County, VA »
- Fairfax County, VA
- Culpeper County, VA »

Tier 3: Code Research + Video Conference Interviews

Method: Video conference interviews were conducted to gather detailed insights and firsthand experiences from jurisdictional representatives. These interviews complemented the code research by providing deeper context and understanding of regulatory practices.

Jurisdictions:

- » Elk Grove Village, IL
- Chandler, AZ »
- Cobb County, GA
- Loudoun County, VA
- Warrenton, VA
- Fauguier County, VA

CODE RESEARCH AND ANALYSIS

The code research process involved several key steps: automated data collection, manual accuracy checks, supplemental research and direct engagement.

Automated Data Collection using ChatGPT: The consulting team utilized ChatGPT to maximize research efficiency in this phase of the project, by locating specific code sections and text related to data centers and industrial development within zoning ordinances. First, the team crafted specific queries to extract all relevant information from ChatGPT related to data centers within each code, focusing on various aspects of zoning and development regulations. The team uploaded development codes from each jurisdiction into ChatGPT to facilitate the extraction of pertinent information and isolate findings to that document.

The research included the following list of topics:

- Definitions »
- Data Center Siting »
- Separation Distances »
- Lot Coverage/Open Space »
- **Building Height** »
- Architectural Standards »
- Screening/Landscaping/Buffers/Fencing
- » Floor Area Ratio
- » Mechanical Equipment
- Setbacks »
- Construction Traffic »
- **Erosion and Sediment Control**
- Water/Power »
- » Parking

Manual Verification: A member of the team manually verified the information extracted by ChatGPT to confirm accuracy and completeness. This involved cross-referencing the official zoning ordinance and any additional regulatory documents to confirm the data was correct.

Supplementary Research: Our team conducted further research to ensure no critical regulatory elements were missed. This included reviewing supplementary materials and industry reports related to data center regulations.

Direct Engagement: For jurisdictions in Tier 2, team members sent emails to request additional information and clarifications. The team made efforts to contact relevant personnel within each jurisdiction.

For jurisdictions in Tier 3, the team conducted video conferences with key staff members to discuss data center regulations in more detail.

Our team covered the following topics during these interviews:

» Protection of Residential Uses/Incompatible Development

- » "Wins" or Lessons Learned in Data Center to contact each jurisdiction and the corresponding Development responses.
- » Energy Sources
- » Water Usage
- Development

CONTACT EFFORTS AND RESPONSES

The combined approach of automated data extraction, manual verification, and direct engagement provided a robust framework for Specific Challenges Related to Data Center researching data center regulations across various jurisdictions. Although response rates from some jurisdictions were limited, our research methodology provided a representative overview of Despite attempts to engage with all communities common practices and regulations among peer in Tiers 2 and 3, responses were limited. The table on the following page outlines the team's efforts communities.

Contact Efforts and Responses for Tier 2 and Tier 3 Communities

Tier 2 Community	Contact Attem
Tower Hamlets, London, UK	Contacted twice v
Slough, UK	Contacted twice v
Frankfurt, Germany	Contacted twice v
Amsterdam, Netherlands	Contacted twice v
Virginia Beach, VA	Contacted via em
Stafford County, VA	Response received
Fairfax County, VA	Video conference
Culpeper County, VA	Video conference
Tier 3 Community	Contact Attem
Tier 3 Community Elk Grove Village, IL	
	Contact Atter Video conference Video conference
Elk Grove Village, IL	Video conference
Elk Grove Village, IL Chandler, AZ	Video conference Video conference
Elk Grove Village, IL Chandler, AZ Cobb County, GA	Video conference Video conference Contacted twice v Contacted twice v

npt / Response
via email; no response
ail; left voicemail; no response
d via email
e with Deputy Zoning Administrator
e with Principal Planner
npt / Response
e with Deputy Director of Community Development
e with Zoning Administrator
via email; no response
with email; left message with staff member; no

articipate due to ongoing litigation

with Chief of Planning

Section 2 | State Statutes Overview

Dillon's Rule and Local Powers

The Commonwealth of Virginia operates under Dillon's Rule. This means that the powers granted to local governments are only those that have been specifically authorized by the General Assembly. Dillon's Rule also provides that local governing bodies have powers that are implied by those that have been specifically authorized as well as those powers that are essential to the locality's purposes. There is a two-step process that is used when applying Dillon's Rule. The first step is to determine whether a local government has been authorized to exercise a particular power. If

they have been so authorized, it then needs to be determined whether they have exercised that power properly.

Powers granted to local governing bodies are outlined in Title 15.2 of the Code of Virginia. While there are no statutes that expressly reference data centers other than those relating to assessment of real property and taxes, Title 15.2 does provide the authority for other methods that may be used to regulate data center development. These regulations are summarized in the table below and are organized by topic area.

Section	Text Summary	
CONDITIONAL ZONING		
§ 15.2-975	States that localities authorized to accept cash proffers may also issue bonds to finance improvements contained in their construction improvement program(s).	
§ 15.2-2296	Grants local governments the authority to use conditional zoning as a regulatory tool.	

Section	Text Summary
§ 15.2-2297	Gives provisions for exte
CULTURAL / HISTO	RIC RESOURCES
§ 15.2-2306	Grants localities the aut landmarks, buildings, or tural, archaeological, or
DECOMMISSIONIN	G (SOLAR)
§ 15.2-2241.2	States that, as part of th the applicant to enter in energy equipment upor
ECONOMIC DEVELO	OPMENT
§ 15.2-1232.2	Allows localities to estab
§ 15.2-2413.13	Sets forth the manner in improvement and recrui
§ 15.2-2413.14	Allows localities to form upon submission of a w the proposed district.
§ 15.2-2413.15	States the process local petition to form a busin
§ 15.2-2413.17	Gives a list of subjects the establishing a business i
ENVIRONMENTAL /	ASSESSMENTS
§ 15.2-2242	States that a subdivision Phase I and Phase II env
§ 15.2-2286	Lists the provisions that environmental site asses
FEES	
§ 15.2-2243	States that local governi ordinance to charge app necessary sewerage, war property limits of the ap
§ 15.2-2319	Grants local governmen new development to pa that would benefit said
§ 15.2-2320	States that localities sha within their comprehens
§ 15.2-2321	States that localities nee and adopt a road impro fees.

ent of voluntary proffers in conditional zoning.

hority to adopt ordinances regulating historic r structures that have an important historic, architeccultural interest.

ne approval process, a local government shall require nto a written agreement to decommission solar n the terms and conditions stated in the Code section.

blish economic revitalization zones. n which a prospective business may file a business itment district plan with a locality.

n a business improvement and recruitment district ritten petition by a majority of the business owners in

governments must follow upon submission of a ness improvement and recruitment district.

hat localities may regulate in ordinances written when improvement and recruitment district.

n ordinance may include provisions for requiring vironmental site assessments.

are permitted in zoning ordinances when requiring ssments.

ments may include a provision in their subdivision plicants the pro rata share of the cost of providing ater, and drainage facilities located outside the oplicant's land.

nts the authority to assess and impose impact fees on ay for all or a part of the cost of road improvements development.

all delineate one or more impact fee service areas sive plans.

ed to conduct a road improvements need assessment ovements plan prior to adopting a system of impact

Section	Text Summary	
§ 15.2-2322	Allows localities to adopt an ordinance establishing a system of impact fees following the adoption of a road improvement program.	
§ 15.2-2323	States that the amount of impact fees to be imposed on a development must be determined before or at the time of subdivision/site plan approval.	
§ 15.2-2324	States that the dedication, contribution, or construction of transportation improvements by the developer shall be credited against any impact fees imposed on their project.	
§ 15.2-2325	Says localities must update the road improvements need assessment at least once every two years.	
§ 15.2-2326	Localities must establish a separate road improvement account for the impact fee service area.	
§ 15.2-2327	Impact fees shall be refunded if the project is not completed within a reasonable period of time, not to exceed fifteen years.	
GENERAL POWERS		
§ 15.2-1117	Grants localities the authority to regulate the light, ventilation, sanitation, and use and occupancy of buildings.	
LANDSCAPING		
§ 15.2-961.3	Allows localities to adopt ordinances regulating the planting and replacement of trees during the development process, provided that the ordinance(s) aligns with this Code section.	
§ 15.2-4403	Grants localities the authority to protect and enhance agricultural and forestal lands as an important economic and environmental resource.	
§ 15.2-4405	Grants participating localities the authority to create agricultural, forestal, or agricultural and forestal districts of local significance.	
§ 15.2-4406	States that any ordinance adopted by a local government that creates or renews an agricultural, forestal, or agricultural and forestal district must include several specific provisions listed in this Section.	
STORMWATER		
§ 15.2-2114	Allows localities to establish a utility or charge service fees to support a local stormwater management program.	
§ 15.2-2245.1	States that localities shall not require the removal of trees to create storm- water management ponds if certain requirements listed in this Section are met.	
§ 62.1-44.15:27	Says that if a locality operates a regulated municipal separate storm sewer (MS4) or that administers a Virginia Erosion & Stormwater Management Program (VESMP), they shall create an ordinance establishing a VESMP that must include several specific provisions outlined in this Section.	

Section	Text Summary
STREETS / TRAFFIC	
§ 15.2-2022	States that certain countion upon highways within the
§ 15.2-2028	Grants localities the authors of vehicular and
ZONING REGULATIO	ONS
§ 15.2-2280	Permits localities to organ regulate: (1) the use of lan area, etc. of structures; (3) occupied by buildings an soil.
§ 15.2-2283	Outlines the general purp
§ 15.2-2315	States that if this article o is required by a local ordi ordinance will control.
§ 15.2-2316.2	Allows governing bodies opment rights within thei

ies may regulate the tracking of mud and debris neir boundaries.

nority to regulate the operation of vehicles and the and pedestrian travel.

anize their jurisdiction into zoning districts and to and, buildings, and structures; (2) the size, height, 3) the areas/dimensions of land, water, and air space nd structures; and (4) the excavation or mining of

rposes of zoning ordinances.

of the statutes requires higher standards than what dinance enacted pursuant to this article, the local

to establish procedures for the transfer of develeir jurisdiction.

Data Centers and Virginia Building Code

The Virginia Uniform Statewide Building Code (USBC) provides a comprehensive regulatory framework governing the design, construction, and renovation of buildings across the state. It establishes minimum standards to safeguard public safety, health, and welfare, addressing critical aspects such as structural integrity, fire protection, accessibility, energy efficiency, and mechanical systems.

While local governments in Virginia cannot amend the USBC itself, they can impose additional

requirements on buildings through separate processes. This means localities can enforce extra measures related to building practices, as long as these do not conflict with the USBC's provisions. For instance, a locality might implement a noise ordinance requiring mufflers on generators or mandate that mechanical equipment be placed in specific locations or screened, thereby addressing local concerns without altering the core building code.

The following table outlines regulations in the USBC which are of particular interest in regards to data center development.

		.	
Торіс	Relevant Building Code Standards		
Fire Safety Systems	The building code requires that data centers provide clear and unobstructed access for fire department personnel. This includes proper signage and access routes that enable quick entry in an emergency.		E
	Data centers typically need redundant power systems to ensure continuous operation. The building code requires that backup generators and uninterruptible power supplies (UPS) be installed and maintained to provide power during outages. These systems must be designed to handle the entire load of the data center. While data centers primarily focus on electrical systems, plumbing is also important, particularly for cooling systems. The building code requires		
Electrical/Plumbing	that any water supply and drainage systems used for cooling (such as chilled water systems) be installed and maintained to prevent leaks and ensure efficient operation.		Ċ
	Data centers often use water-based cooling systems to manage the heat generated by equipment. The code mandates proper installation of these systems, including backflow prevention devices to protect the locality's water supply from contamination.		
Energy Efficiency	Data centers are required to adhere to stringent energy performance standards to minimize energy consumption. This includes implementing high-efficiency HVAC systems, lighting, and other energy-intensive equipment. Data centers must also comply with energy codes that mandate specific performance metrics and efficiency ratings for equipment.		c
	The building code encourages the integration of renewable energy sources. Data centers can incorporate solar panels, wind turbines, or other renewable technologies to reduce reliance on non-renewable energy sources and lower their carbon footprint.		

Торіс	Relevant Buildin
Sustainable Materials/ Construction	The code promotes the building materials. Fo have a lower environr or low emissions. Sustainable building p construction. Data cer disposing of construct
Water Efficiency	Data centers must inc Although water usage the building code req manage stormwater r Sustainable building s cooling systems. Data minimize water use a
Environmental Quality	The code emphasizes centers, this involves maintain a healthy ind well as optimizing the Although data center encourages the use o should implement lig consumption.
Certification/ Compliance	Data centers can purs and Environmental De building standards. Th providing guidelines Ongoing monitoring to ensure that data ce achieve their sustaina
On-site Energy	The code requires that standards to minimize related to HVAC syste mance. Virginia's code encou energy sources, such like data centers. This typical of data centers Data centers must im could involve advance use, ensuring that the Data centers are required which may involve per measures taken.

ng Code Standards

the use of sustainable and environmentally friendly or data centers, this means choosing materials that mental impact, such as those with recycled content

practices include proper waste management during enters must follow guidelines for recycling and ction and demolition waste responsibly.

corporate water-efficient fixtures and systems. e in data centers is often related to cooling systems, quires practices that reduce water consumption and runoff effectively.

standards encourage the use of water-efficient a centers are expected to use technologies that and manage wastewater responsibly.

s the importance of indoor air quality. For data ensuring that ventilation systems are designed to door environment for maintenance personnel, as e air quality in relation to cooling systems.

rs rely heavily on artificial lighting, the code of energy-efficient lighting solutions. Data centers phting controls and fixtures that reduce energy

sue certifications such as LEED (Leadership in Energy Design) to demonstrate compliance with green The building code supports these certifications by that align with their requirements.

and reporting of energy and water use are required enters adhere to green building standards and ability goals.

at data centers meet specific energy efficiency ze energy consumption. This includes measures ems, lighting, and overall building envelope perfor-

urages or mandates the integration of renewable as solar panels, especially for large-scale facilities s can help offset the significant energy consumption rs.

nplement energy management practices, which ced monitoring systems to track and optimize energy e facility operates efficiently.

uired to comply with local regulations and codes, eriodic reporting on energy usage and efficiency

Торіс	Relevant Building Code Standards
	Data centers require robust cooling systems to manage the heat generated by high-density server racks and other equipment. The building code mandates that these systems be designed to provide adequate cooling capacity, maintain proper temperature and humidity levels, and operate efficiently. This often includes the installation of precision cooling units and, in some cases, chillers or cooling towers. Proper ventilation is critical in data centers to ensure the effective dissi-
	pation of heat and to maintain air quality. The code requires that venti- lation systems be designed to handle the specific load conditions of data centers and to ensure that cooling and airflow are evenly distributed throughout the facility.
	The code emphasizes the importance of energy-efficient HVAC systems. Data centers must use high-efficiency equipment, including energy-efficient fans, compressors, and pumps, to reduce overall energy consumption and operational costs.
Sized to meet the demands of the data center. This in the heat load, airflow requirements, and ensuring that capable of handling the data center's operational needMechanical EquipmentMechanical equipment must be accessible for mainter The building code requires that adequate space be pre- HVAC systems and other mechanical equipment to face	The code stipulates that mechanical systems be properly designed and sized to meet the demands of the data center. This involves calculating the heat load, airflow requirements, and ensuring that all equipment is capable of handling the data center's operational needs.
	Mechanical equipment must be accessible for maintenance and repair. The building code requires that adequate space be provided around HVAC systems and other mechanical equipment to facilitate servicing and ensure safe operation.
Data centers often operate 24/7, so noise control is important. includes provisions for minimizing noise from mechanical syste reduce disturbances both within the data center and in adjacent	
	The building code requires that mechanical systems be integrated with other building systems, such as fire alarms and building management systems. This integration helps in monitoring performance, managing energy use, and ensuring that emergency protocols are followed.
	Data centers must monitor the performance of their mechanical systems to ensure they are operating efficiently and effectively. The code supports this by requiring regular inspections and maintenance to keep systems running at optimal levels.
	The building code promotes the use of energy management systems to track and control energy consumption in mechanical systems. Data centers are encouraged to implement advanced controls and monitoring to enhance efficiency and reduce energy usage.

Statutory Framework Review & Peer Research Summary 15



Section 3 | Prince William **County Regulatory Context**

Overview

The Zoning Ordinance (ZO) and the Design and Construction Standards Manual (DCSM) are the key documents governing development in Prince William County. Together, they enforce the County's Comprehensive Plan and cover a wide range of zoning and development issues as authorized by the Virginia General Assembly. This includes, but is not limited to, conditional zoning, transportation, land use, and the design of buildings and structures.

The ZO specifically regulates data centers by defining terms, setting siting requirements, and establishing use standards such as architectural guidelines, screening, and buffering. Notably, the ZO includes the Data Center Opportunity Zone Overlay District. In this district, data centers are permitted by-right, streamlining the approval process compared to other districts where they might be subject to special use reviews. Additionally, the overlay district offers benefits like an increased floor area ratio for data centers.

The ZO also delineates development regula-

tions for conventional zoning districts, covering aspects such as building height, setbacks, and lot coverage.


The DCSM complements the ZO by providing detailed standards for infrastructure and site design. It encompasses regulations related to landscaping, fire safety systems, water supply, sanitary sewer systems, transportation, environmental systems, parks, schools, and the Highway Corridor Overlay District.

For a comprehensive overview of the regulations pertinent to data center development, please refer to the following table, which consolidates the relevant provisions from both the ZO and DCSM.

Zoning Ordinance & DCSM Summary of Regulations

DEFINITION

"Data Center shall mean a use involving a building/premise in which the majority of the use is occupied by computers and/or telecom-



LEGEND
Data Centers Permitted By Right
Data Centers Permitted By Special Use Permit
Built Data Centers
Approved Data Centers
Zoning Use Categories Business & Office
Residential
Industrial
Mixed Use
Agricultural
Government Land
MANASSAS PARK
No.R.
SGITY
PRINCE WILLIAM
OCCOQUAN
DUMFRIES
m . w
QUANTICO
Ser .



munications and related equipment, including supporting equipment, where information is processed, transferred and/or stored."

DATA CENTER SITING

The map on the previous pages show parcels where data centers are currently permitted in Prince William County, either by-right or through special use permit. Additionally, the map identifies parcels that already have a data center built or approved.

Within the Data Center Opportunity Zone Overlay District, data centers are permitted by-right in the following zoning districts:

- » Office Low-Rise (O(L))
- Office High-Rise (O(H))
- Office Mid-Rise (O(M))
- Office/Flex (O(F)) »
- Heavy Industrial (M-1) »
- » Light Industrial (M-2)
- » Industrial/Transportation (M/T)
- » In designated office or industrial land bays in PBD (Planned Business District) and PMD (Planned Mixed Use District) districts.

Outside of the Data Center Opportunity Zone Overlay District data centers require a special use permit in the districts noted above.

The following maps show where data centers are currently permitted in Prince William County, either by-right or through special use permit and identifies parcels that already have a data center built or approved.

Data centers shall be prohibited in agricultural, residential, PMR, B-2, B-3 and V districts.

Electric Substations may be located in any zoning district within the Data Center Opportunity Zone Overlay District, subject to the public facility review requirements of the Code of Virginia, § 15.2-2232 and this chapter. Electric substations may be permitted by Special Use Permit within any zoning district outside of the Data Center **Opportunity Zone Overlay District.**

School sites should be located near the centers of projected student populations and located adjacent to compatible sites and uses including but not limited to parks and recreation facilities, day care centers, commuter parking, etc. Sites should be separated from industrial and commercial facilities, pollution, heavily traveled roadways, and other hazards.

Land considered undesirable or unsuitable for general construction or park development includes stream valleys, storm drainage areas, areas with an excessively high water table, excessively steep slope twenty five percent (25%) or greater, areas encumbered by major utility lines, or generally unsuited for foundation support or development.

Land to be provided as park or recreation sites should be centrally located to equally serve the entire subdivision or the section of the subdivision submitted for County approval. Play areas and tot lots should be within easy walking distance of the residents to be served and located where there are no dangerous areas or physical barriers, i.e., roads, railways, power lines, or unprotected waterways.

Lot Coverage

Zoning District	Max. Lot Coverage %	Min. Open Space %
O(L)	80	20
O(H)	80	20
O(M)	80	20
O(F)	80	20
M-1	85	15
M-2	80	20
M/T	85	15

BUILDING HEIGHT

Within the zoning districts where data centers may be allowed either by-right or as a special use, height maximums vary from 45 feet to 100 feet. However, the Board of County Supervisors may approve a structure with a greater height through a proffered rezoning or special use permit application.

Maximum Building Height

Zoning District	Max. Building Height
O(L)	45′
O(H)	100′
O(M)	70′
O(F)	45′
M-1	75′
M-2	60′
M/T	75′
PBD/PMD	100′

The Board of County Supervisors may, by approval of a proffered rezoning or a Special Use Permit application, approve a structure with a height greater than any specific limitation, subject to the following standards:

- a. For a rezoning application, the maximum » building step-backs or recesses; height shall be specifically proffered by the applicant and accepted by the Board of » fenestration; County Supervisors; for a Special Use Permit » change in building material, pattern, texture, application, the maximum height shall be color; or made a condition of approval of the appli-» use of accent materials cation; and
- b. The Board of County Supervisors shall be satisfied that approval of a proffer or Special Use Permit is a more appropriate course the height requested; and
- » Building façades facing Manassas Battlefield than a rezoning to a classification permitting Park, that are visible from viewshed anchors as identified in the Manassas Battlefields c. The Board of County Supervisors shall be Viewshed Preservation Study, shall be satisfied that the proposed height shall not non-reflective and dark green or dark brown have a substantial adverse impact on the in color. The Planning Director may approve light and air of adjacent and nearby propother colors provided the colors are demonerties; and strated to be earth tones that will help the building façade blend into the tree line. d. The County Fire Marshal has certified in
- writing that the proposed building or other SCREENING structure can be properly protected, and will not endanger improvements on adjacent properties, in case of fire; and
- e. All other requirements of this chapter for a

- conditional rezoning or Special Use Permit have been met; and
- f. The proposal shall not constitute a hazard to aerial navigation. Where the Board of County Supervisors believes a proposal may be such a hazard, the proposal shall not be approved unless the Federal Aviation Administration certifies in writing that the proposal does not constitute a hazard to aerial navigation.

ARCHITECTURAL REQUIREMENTS

Principal building facades shall include all building façades that face adjacent major arterials or interstates. When a building has more than one principal façade, such principal building façades shall be consistent in terms of design, materials, details, and treatment.

Principal building façades shall avoid the use of undifferentiated surfaces by including at least two of the following design elements:

» change in building height;

Building façades facing County registered historic site Manassas Battlefield Park.

Mechanical Equipment.

In order to minimize visibility from adjacent roads and adjacent properties, ground level and roof top mechanical equipment shall be screened

Statutory Framework Review & Peer Research Summary 19

from major arterials, interstates and abutting residentially zoned or planned properties. This screening may be provided by a principal building or existing vegetation that will remain on the property or is within a landscaping/buffer easement on an adjacent property. Mechanical equipment not screened by a principal building or existing vegetation shall be screened by a visually solid fence, screen wall or panel, parapet wall, or other visually solid screen that shall be constructed of materials compatible with those used in the exterior construction of the principal building. Notwithstanding the requirements of this section, mechanical equipment located in a manner found to have no adverse impact on adjacent roads and adjacent properties, as determined by the Planning Director, shall not be required to be screened.

When screening of certain on-site functions (e.g., loading, dumpsters, trash collection, outside storage areas, maintenance areas and equipment, mechanical equipment, etc.) is required by the Zoning Ordinance, the following screening options shall be used, depending on the type of function being screened:

- » A minimum six (6) foot high opaque fence or wall, the height of the fence or wall shall be no lower than the functions/items being screened. An appropriate gate shall be provided, if applicable.
- » A three (3) foot high berm with plantings of six (6) feet high evergreen screening is provided.
- » For mechanical and similar equipment, any architectural element compatible with the building is acceptable, as long as it covers the view of the equipment.
- The site functions listed above shall be oriented on the site so as to be as inconspicuous as possible, and shall be screened from all public streets and adjoining properties.

Substations.

Substations shall be screened from adjacent major roads or residentially zoned/planned properties as follows:

- » Ten-foot-tall opaque fencing facing residentially zoned/planned properties.
- All other buffering and landscaping requirements of the DCSM shall still apply.

FLOOR AREA RATIO (FAR)

Data Centers are permitted an increased FAR, within the Data Center Opportunity Zone Overlay District, up to 1.0 FAR provided all other development standards (excluding FAR limitations) for the underlying district are met.

Data centers outside of the Data Center Opportunity Zone Overlay District may request an increase in FAR through a special use permit process, as described and allowed in Section 32-400.04 of the Zoning Ordinance.

FAR by Zoning District

Zoning District	Max. FAR
O(L)	0.35
O(H)	1.25
O(M)	0.65
O(F)	0.5
M-1	0.5
M-2	0.5
M/T	0.75

Changes to FAR.

The Board of County Supervisors may approve a FAR higher than that permitted by-right by specifically proffered rezoning or Special Use Permit. In those districts where minimum FARs are specified, the Board may approve a FAR lower than that permitted by-right by proffered rezoning or Special Use Permit. When approved as part of a rezoning, the maximum (or minimum) FAR shall be specifically proffered; when approved by Special

Use Permit, the maximum (or minimum) FAR shall specifically referenced. The Board of County be made a condition of the permit. Matters to be Supervisors may modify this setback provision as considered by the Board of County Supervisors in a part of the approval of the rezoning or Special evaluating such application shall include, but not Use Permit, provided any minimum setbacks and be limited to, increased buffering and landscaping, yards required elsewhere in the chapter shall be unique design features that improve visual impact met. Setback requirements for telecommunicaor minimize shadow (such as stepped building tions facilities as defined herein are contained in design); general compatibility with surrounding part 240 of this chapter. uses; compatibility with surrounding structures Parking and loading spaces setbacks. (architecturally, materials used, etc); environ-Except for developments in the V, village district mental protection or enhancement on-site; and residential dwellings in the agricultural and public amenities on-site; off-site transportation improvements; fire and health safety design features (beyond those required by law), or any requirements: (a) Ten feet from any street rightother design improvement which promotes the of-way. (b) Ten feet from all other property lines, health, safety, and general welfare of the workers except: (i) where required buffer areas require a at the site and the citizens of the County.

residential districts, data center development shall meet the following minimum setback greater setback; or (ii) where proposed property lines are created around existing or new buildings SETBACKS shown on an approved site plan; or (iii) where a Unless the provisions of this chapter operate to parking lot of a development in the commercial, impose a greater standard, any structure above 45 feet in height, excluding telecommunications office, industrial district or on public or institutional facilities abuts the parking lot of another facilities as defined by this chapter, shall be set back a minimum of 20 feet plus two feet for each development in a commercial, office, or industrial foot in height above 45 feet from any property district or other public or institutional facilities if provisions of applicable section 32-250.82.2 and line that abuts a residential or agricultural district, and shall be set back a minimum of 20 feet plus section 32-400.25.6 of this chapter are satisfied. (c) Interior driveways shall be subject to the setbacks one foot for every foot in height above 45 feet from all other property lines, provided that this in subsection (a) and (b). Entrances and exits shall be subject to the setbacks in subsection (b). requirement shall not apply to the O(H) and O(M) Districts except when and only to the extent

Setbacks table

Zoning District	Front Setback (From street ROW)	Side/
O(L)	20 ft.	25 ft.
O(H)	20 ft.	25 ft.
O(M)	20 ft.	25 ft.
O(F)	20 ft.	25 ft.
NA 1	20 ft.	20 ft.
M-1		50 ft.
M-2	20 ft.	20 ft.
171-2		50 ft.
M/T	20 ft.	20 ft.
	20 II.	50 ft.

Rear Setbacks
(when abutting agricultural or residential district)
(when abutting commercial or office district)
(when abutting agricultural or residential district)
(when abutting commercial or office district)
(when abutting agricultural or residential district)
(when abutting commercial or office district)
(when abutting agricultural or residential district)

LANDSCAPING/BUFFERS/FENCING

Buffering & Screening.

A buffer yard is required in order to screen the data center from adjacent residentially zoned or planned properties. In lieu of the buffer yard requirement in DCSM Section 800, any side/ rear yard abutting property that is not planned or developed with commercial or industrial uses shall include a buffer yard required plantings installed on an earthen berm that has a minimum height of six (6) feet and a slope not steeper than 2:1, planted to a type C DCSM buffer standard. The buffer yard plantings shall be installed in accordance with the requirements of the DCSM. Notwithstanding the requirements of this section, use of natural topography and preservation of existing vegetation, supplemented by new vegetation, if needed, or on the outside of a six foot tall solid fence, may be substituted for the above requirements when found by the Planning Director to provide visual screening from adjacent land uses at the density, depth, and height equivalent to the buffer yard with earthen berm.

» Type C Buffer Area Width and Plant Requirements: 50' wide, 320 plants per 100 feet of ROW or property line.

Fencing of the property is permitted, provided that fencing along public or private streets is not chain-link, with or without slatted inserts, and does not include barbed wire or other similarly visibly intrusive deterrence device. Chain-link fencing or barbed wire fencing are prohibited along public or private street frontages. This fencing allowance does not relieve a property owner from complying with all fire and access code requirements. The Planning Director may allow for alternative compliance with this requirement, provided the applicant demonstrates that the fencing visibility is reduced, through the use of landscaping and other methods to reduce visibility.

Required Tree Canopy Cover at Ten Year Maturity.

» Commercial, Industrial, and institutional developments: 10% of area of site

Changes to Buffering & Screening.

Minimal utility crossings may be included within a buffer area upon approval of the Director of Public Works, as long as comparable performance standards are maintained. Landscaping with shrubs, ornamental grasses and perennials may be permitted in utility easements. However, planting of trees in utility easements is not allowed, unless specifically approved by the agency controlling the easement.

For areas within a MXD (mixed use district) and that abut with parcels that are not part of a MXD, buffer areas between proposed uses should be reviewed on a case by case basis and may be modified through Administrative approval by the Planning Director with consultation of the Public Works Director.

Where the buffer width will allow, a berm may be substituted for thirty percent (30%) of the plant unit requirement. The berm should be graded to appear smooth, rounded and naturalistic. The berm shall be a minimum of four (4) feet higher than the elevation of the adjacent ground. Its slope shall not exceed three-to-one (3:1), except in unusual situations where a two-to-one (2:1) slope would be allowed with special ground cover. In such instance where the reduction in plant units applies, at least fifty percent (50%) of the plant unit requirement shall be evergreen trees and shrubs.

A six (6) foot tall opaque fence (board-on-board, masonry, or similar material) or wall may be substituted for thirty percent (30%) of the plant unit requirement. For non-residential lots of three acres or less, a 6-foot-tall board on board, solid masonry fence/wall, or equivalent barrier may be substituted for 50% of the plant unit required by the Design and Construction Standards Manual.

When existing woodland is located within the entire minimum buffer area, preservation of the woodland shall be allowed to substitute for the required plant material, provided that:

» The woodland meets the minimum size requirement of Table 8-5, and

» The visual screen provided by the woodland meets the intent of this code.

The purpose of this section of the Code is to address the minimum requirements for design If a developing property with a nonresidential use and construction of public sanitary sewer systems is adjoining a vacant property zoned or planned and on-site sewage disposal systems, as suppleresidential, the full buffer width, as identified in mented by the Prince William Water Utility Table 8-1, shall be provided. If the vacant property Standards Manual (PWW – USM). Subsections to is zoned and planned nonresidential and a buffer specifically review when considering revisions: would be required, the buffer may be reduced to the next lower category. However, at a minimum, » Private On-site sewage disposal systems Buffer A shall be provided.

When a wall or a solid fence is used for The content included in this section of the Code landscaping/buffering purposes, plantings should relates to public access and safety minimum be provided on both sides of the fence to soften standards for the design and construction of its visual impact and to deter access for graffiti streets, roadways, access, parking, lighting and vandals. Suggested plantings to restrict access to pedestrian improvements. Reference is also made walls susceptible to graffiti vandalism: barberry to the provisions of VDOT and AASHTO standards or pyracantha to block access to the wall; ivy or and specifications. Subsections to specifically other plantings to cover the wall. Use of vine type review when considering revisions: plantings should depend on the type of material » Traffic Impact Analysis (TIA) used for the wall, as some building materials can » Setbacks be damaged by the plants.

FIRE SAFETY SYSTEMS

The content included in this section of the Code The content included in this section of the Code includes design and construction standards involves (site related) Fire Safety System compofor storm drainage, grading, stormwater nents including fire lanes, emergency access, fire management, floodplains, Chesapeake Bay lines, access to the building, fire hydrants, water supply and fire flow requirements. State Building preservation areas, erosion and sediment control and geotechnical soil testing. Subsections to fire code requirements are not specifically specifically review when considering revisions: restated.

- » Planning and Design
- » Additional/Conditional Fire Protection Measures

WATER SUPPLY SYSTEMS

The purpose of this section of the Code is to Public bodies have several legislative tools at address the minimum requirements for design their disposal, including comprehensive plan and construction of water systems, as suppleamendments, zoning text amendments, zoning mented by the Prince William Water Utility map amendments, special exceptions, and special Standards Manual (PWW – USM). Subsections to use permits. In Prince William County, these specifically review when considering revisions: critical land use decisions are made exclusively by » On-site private wells the Board of County Supervisors (BOCS). These decisions are designed to balance individual interests with the broader public goals of health,

SANITARY SEWER SYSTEMS

TRANSPORTATION SYSTEMS

ENVIRONMENTAL SYSTEMS

- » General Policy for BMP and Storm Water Quality
- » Erosion and Sediment Control Policy

Legislative Review Process



safety, and welfare, and are presumed to be correct, reasonable and constitutionally sound. Consequently, the BOCS wields considerable discretion in these matters.

While the Planning Commission can review applications and offer recommendations to the BOCS, it does so in an advisory capacity and does not possess official legislative authority. According to Title 15.2 of the Virginia Statutes, localities have the authority to accept cash and other voluntary proffers, as well as to employ conditional zoning.

The consulting team was provided with six rezoning applications for data centers that were approved in the last two years by County Staff and conducted a comparative analysis of the approved proffers. The tables below include the list of applications reviewed and a summary the common proffer language included in the approvals for these applications.

Case Number	Project Name
REZ2024-00006	Mid-County Industrial Park
REZ2022-00036	Compass Data Centers Prince William County Campus 1
REZ2022-00032	Digital Gateway North
REZ-2022- 00033	Digital Gateway South
REZ2023-00026	Stoneview
REZ2022-00022	Devlin Technology Park

USES

» Lists of permitted and prohibited uses are included either by reference to the Zoning Ordinance, or specifically listed.

BUILDING/SITE DESIGN

» Increased architectural standards are typically included in the proffer statements. This may include utilizing a higher amount of design elements than the minimum required by ordinance, or a minimum percentage of fenestration on certain facades.

- » Size limitations on electric substations
- » Building height and rooftop mechanical equipment height.
- » Lot coverage and open space amounts; Floor Area Ratios
- » Enhanced erosion and sediment control during construction
- Waivers of setbacks
- » Separation distances from residences and/ or schools

PROTECTION OF CULTURAL/NATURAL RESOURCES

- » Provide protection of any archaeological and cultural resources, cemeteries, remains during construction
- Tree preservation and wildlife corridor pres-» ervation
- » Archaeological surveys provided

LANDSCAPING/BUFFERS/SCREENING

- » Screening of mechanical equipment and specification and increased landscaping in terms of quantity and type
- Enclosure types for substations
- » Enhanced recreational facilities, such as multi-use trails
- Requirements and waivers of certain buffers
- Required tree canopy coverage
- » Landscaping maintenance plan

INFRASTRUCTURE

- » Limitation of wells, private septic systems and public water and sewer are specified
- Phasing of roadway networks and transportation improvements
- » Planned right-of-way dedications

WATER/STORMWATER

» Enhanced stormwater management facilities.

- » Limitations on type of water use for data center cooling.
- » Monetary contributions for water guality » Pollutants and flammable substances shall monitoring, drainage improvements, stream not be discharged into the stormwater restoration projects, fire and rescue, forestland conservation projects, and transportasystem, sanitary sewer, ground, or surface water unless approved. tion projects.

SUSTAINABILITY/ENERGY

- » As a condition of the first final site plan approval, the applicant will determine is site and/or building sustainability measures are appropriate.
- » Sustainable building/site design practices for portions of buildings and site to promote energy efficiency.
- » Commitment to run data center on 25% renewable energy.

NOISE

- » Noise levels are limited to ranges between Section § 15.2-2223 of the Virginia Code requires 55 – 79 dBA depending on location . local governments to adopt a comprehensive plan. The plan needs to be general in nature, and, » Substations are specifically not subject to together with any maps, charts, and descriptive noise levels in proffers. information, should show the locality's long-range » Sound study which provides mitigation recommendations for the general development recommendations. of the territory. Per Section § 15.2-2223.B.1 of » Sound barrier construction. the Code, comprehensive plans must include a transportation plan as well. Hours of outdoor construction activities are

- limited based on day of the week.

NOTICING

- » Written information and meetings regarding the use and construction of the use will be provided to local stakeholder groups.
- » Blasting schedule provided to local neighborhoods, homeowner's associations and schools.
- » Construction phasing, truck routing, and off-site debris mitigation plans are prepared and distributed to local stakeholder groups.

CASH PROFFERS

The Comprehensive Plan

Comprehensive planning helps communities plan proactively rather than reactively. A comprehensive plan establishes a framework to guide public and private decisions about future growth, preservation, and change within a municipality or county over a twenty to thirty-year timeframe. Comprehensive plans typically have a broad scope, addressing a wide range of topics that are of concern to the entire community, and they outline multiple goals and policies to be implemented over a long time period.

The Land Use chapter of the Prince William County 2040 Comprehensive Plan encourages data center development in industrial zoning areas. For example, the Gainesville Activity Center Land Use Plan supports data center development in Industrial T-4, while the County Register Historic Site (CRHS) associated with the Thomasson Barn provides an opportunity for data centers in the Industrial T-3 area along Hornbaker Road and Godwin Drive. However, Land Use Policy 12.3 does encourage the County to provide enough lands for industrial uses not to include data centers, and the Industrial Long-Range Land Use classification states that data centers are discouraged in Industrial T-2.

Section 4 | Peer **Communities Research**

Overview

Our research into data center regulations across peer jurisdictions involved a three-tiered approach combining code analysis, email correspondence, and video interviews. Tier 1 focused on code research, Tier 2 added email correspondence, and Tier 3 included video conferences.


Research topics covered a variety of topics including data center definitions, trends, siting, separation and screening, architectural standards and building design, as well as any relevant sustainability, power and water usage regulations. While response rates varied, our methodology provided a comprehensive overview of common practices and regulations among peer communities.

Please note that some jurisdictions we researched are in the process of updating their data center regulations or have recently updated their regulations and final ordinances were not available at the time of the drafting of this report (such as in the case of Fairfax, VA). These localities are marked with an asterisk.

Findings

This section highlights some of the most interesting and relevant data center regulations from our team's peer communities research. While not an exhaustive list of regulations and policies, this section provides a summary of examples of regulations, standards and potential approaches from other localities that could be applicable or relevant for Prince William County.

For a more comprehensive overview of our peer research, please refer to the appendix.



Equinix Data Center, Amsterdam, Netherlands,



Fauquier County, Virginia

	0	
	Торіс	Regulation
Compt Color Allowers A		Data centers are only considered for developmen Planned Commercial Industrial District (PCID). If t use, if not, it's a special exception use.
LANDSCAPE BUFFER	DATA CENTER SITING	Data centers should not be located contiguous to school or medical care facility.
E Constanting of the second se		100' setback for property lines where a new indus use.
		Petroleum products, diesel fuel and other potenti safe distance from any public or private water sou management facilities.
man of the second secon		All new power lines, including transmission or sub ground.
and the second s		Rezoning applications are highly encouraged to c how electricity will be provided to accommodate overall power demand relates to the overall regio
60C A A CAR	POWER	This should include any on or off-site need for a r switching station, and/or any other electrical infra
88 1		Rezoning applications should commit, through a demand for the entire development.
1 23 1 1 1 1 Co		On-site solar and geothermal energy and other re meet a portion of the development's energy requ
and B B		Data Centers are encouraged to commit to a Pow proffer such commitment.
A Long and the lon		Buildings should be oriented to take advantage o
PROFOSED -		Innovative technologies which reduce power condesign.
Jon Bull	SUSTAINABILITY	Heat generated by Data Center operations should possible.
Man A A A A A A A A A A A A A A A A A A A		Buildings should incorporate heat reflective roofing
		Sustainable building materials should be used.
Constration and the		Generators which incorporate advanced emission emission standards are strongly encouraged.
100' BUILDING SETBACK	BUILDING DESIGN	Building heights shall not be increased above the demonstrate that proposed height is compatible not have an adverse impact on adjacent and near

ent in two zoning districts: Business Park (BP) and the facility will use recycled water, it is a permitted

to land zoned residential, or planned for a park,

lustrial use is proposed next to an existing residential

ntially hazardous materials should be stored a ource, waterbodies, wetlands, and stormwater

substation feedlines are required to be placed under-

clearly demonstrate, to the greatest extent possible, te the project's development, and how the project's jional network.

a new substation, expansion of an existing substation, frastructure.

a voluntary proffer, to a maximum electrical load/

renewable sources are encouraged to be utilized to quirements.

ower Usage Effectiveness (PUE) ratio of 1.5 or less and

of passive cooling and daylight opportunities.

onsumption should be incorporated into the project's

uld be trapped and reused to the maximum extent

ofing.

on control technologies and meet the EPA's Tier 4

he 45-foot maximum unless the Applicant can le with the surrounding development and that it will earby properties (Visual Impact Analysis is required).



Warrenton, Virginia*

, 0		
	Торіс	Regulation
	DATA CENTER SITING	Data centers are only considered for developmen
	MECHANICAL EQUIPMENT	Mechanical equipment shall be completely scree vegetation so that no part of the mechanical eq right-of-ways.
		All generators shall be equipped with mufflers to
		The maximum building height is 35 feet', however, than 35 feet during the review of the Special Use
	BUILDING DESIGN	Buildings must be setback one (1) additional foo each additional one (1) foot (vertically) greater the with the Comprehensive Plan.
		The data center building shall be setback a minim
OVHcloud	LANDSCAPING WATER/POWER	In addition to the landscape planting requiremen of the data center (including equipment) visible residential district shall be screened by vegetatior trees planted 15 feet on center. A minimum 3 for evergreen shrubs planted 10 feet on center may evergreen trees required above.
		Buffer Yard: Industrial uses from residential and re for each foot of building height over thirty-five (planted fifteen (15) feet on center, or a double s feet on center, forming a dense, continuous visua year of planting or a fence or wall or earthen berm trees interspersed every twenty-five (25) feet alon
		The data center shall utilize recycled water or air c cooling purposes. Potable water shall not be usec
		All electric service lines from the substation to the

ent as a special use in the Industrial district.

eened through the use of walls, fences or evergreen equipment can be seen from adjoining properties or

to reduce emissions and noise.

er, Town Council may approve building heights greater se Permit.

foot (horizontally) from the required setback line for than 35 feet. Building heights shall be in conformance

imum of one-hundred (100) feet from property lines.

ents of Article 8 of the Zoning Ordinance, any portion le from a park or adjoining/across the street from a on consisting of a double staggered row of evergreen foot berm planted with a double staggered row of nay be used in place of the double staggered row of

recreational uses: Fifty (50) feet wide plus one (1) foot (35) feet.; Double staggered row of evergreen trees staggered row of evergreen shrubs planted ten (10) sual screen at least six (6) feet in height within one (1) rm, with a minimum six (6) foot height, with evergreen ong the side of the wall facing the residential use

^r chillers, in conjunction with using recycled water, for ed for cooling.

the data center shall be placed underground.

Loudoun County, Virginia*

	Торіс	Regulation
	DATA CENTER SITING	Currently permitted in three zoning districts (IP, ((PD-RDP, CLI, OP).
		In the process of amending their zoning ordinance tions. There will be no districts where data centers
		Parking must be setback at least 50 feet from the other natural screening exists within 50 feet of t undisturbed or enhanced; or, if no forest or natu feet in height constructed to a maximum 2:1 slop fencing and plantings are placed on top of the be
	SETBACKS AND BUILDING MASSING	Structures must be setback at least 200 feet from
	WHEN ADJACENT TO RESIDENTIAI	If a building is located within 400 feet measur property, any building façade facing the adjacent at a minimum interval no less frequent than every times the average height of the building; and the less than 15 feet from the building wall at a heigh the building or 40 feet, whichever of the two is lo
		For data centers, site-specific energy storage fac of the use; otherwise, the use is subject to the rec
	POWER	The energy storage facility must be located within t building. Alternately, the energy storage facility n when fully screened from public view.
		Energy Storage Facility Container Size. Container 900 square feet in size.
	BUILDING DESIGN	Building heights shall not be increased above the strate that proposed height is compatible with the an adverse impact on adjacent and nearby prope
		Data Center Mechanical Equipment must be sho screened on all sides. Such visually solid screen m and treatment compatible with those used on the
	MECHANICAL EQUIPMENT	Ground mounted Data Center Mechanical Equipm has existing residential development, an approv opment, or Zoning District permitting residentia permitted adjacent to residential property.
		Ground mounted Data Center Mechanical Equipn

, GI, MR-HI), and special exceptions in three districts

nce to change all permitted districts to special excepers are permitted.

ne common property line, provided existing forest and the lot line, and such forest and screening remains tural screening exists, berms are provided at least 10 ppe on either side of the crown edge, and 10-foot-tall berm

m the common property line;

ured from the property line adjacent to residential ent property must include a change in building height ery 150 horizontal linear feet or no less frequent than 3 ne building envelope must provide a step- back of no the point that begins at the top of the second story of lower.

acilities must not exceed 30% of the gross floor area equirements for utility scale energy storage facilities. n the principal building or within a permitted accessory may be located on the roof of the principal building

ers housing energy storage equipment are limited to

ne 45-foot maximum unless the Applicant can demonhe surrounding development and that it will not have perties (Visual Impact Analysis is required).

shown on any proposed Site Plan and must be fully must be constructed with a design, materials, details, he nearest Principal Façade of a building;

oment must be separated from adjacent property that oved CDP or plat or plan showing residential develtial uses, by a principal building, or is otherwise not

oment must not be located in any required front yard.

Chandler, Arizona

	Торіс	Regulation
	DATA CENTER SITING	Data centers are not permitted to operate in the of a Planned Area Development zoning district. D are permitted if they a) occupy no more than ten serve the enterprise functions of the on-site prop and processing services to third parties, and c) are the parcel. All uses permitted within a Planned Area Develop the time of zoning approval, and be set forth in t
	BUILDING DESIGN	approved by the Mayor and Council. Architectural style is not prescribed; the design commensurate with the neighborhood and as pu- building design for some other location, climate, e sarily fit in a given location in Chandler and shall environment and meet the intent set forth in this Building mass: Large building facades are deemed
	MECHANICAL EQUIPMENT	of Chandler and are discouraged. Mechanical equipment screening: All mechanical and/or screened from view in their entirety as an ir manners, and subject to approval by the Zoning / » Parapets are acceptable for screening, provid highest point on the mechanical equipment; » Screening of mechanical equipment shall be similar to the building, and so arranged that the building mass. All mechanical equipment and appurtenances sha elevations indicating dimensions of equipment ar

ne City of Chandler unless explicitly approved as part Data centers that are ancillary to another primary use n (10) percent of the building footprint, b) are used to operty owner and are not used to lease data storage are not housed in a separate stand-alone structure on

opment (PAD) zoning designation shall be identified at the ordinance and/or Preliminary Development Plan

gn, however, shall convey a high degree of quality prescribed in the Chandler General Plan. A standard , environment or set of circumstances may not necesall be modified to be harmonious with the immediate is paragraph.

ed inconsistent with the low-key small-town character

cal equipment and appurtenances shall be concealed n integral part of the building in one (1) of the following Administrator:

vided the height shall be equal to, or higher than, the nt; or

be constructed of similar materials and painted colors nat the screening is perceived to be an integral part of

shall be indicated and shown on building sections and and screening.



Chandler, Arizona (continued)

Торіс	Regulation
LANDSCAPE/BUFFERS/SCREENING	 Landscape Buffer areas for dissimilar land uses: A six-foot masonry wall reflecting the design within the project, excluding approved gated and evergreen trees a minimum of seven (7) existing or planned residential development on center and shrubs planted at a rate of for
	Additional requirements for new non-residential v per day.
WATER	New non-residential water users who have an es (9,000) gallons per day or more (excluding turf re plan" sealed by an Arizona registered architect condition of issuance of a building permit. The "w » A description of any available water conserva
	 Whether alternative water sources will be us non-groundwater sources); Operating levels of total dissolved solids (cooling capacity; Whether the user will use the best available compared to the set available compared to the best available
	process uses (i.e., re-circulating systems fo automatic shut-down devices to eliminate co » Any plans for the reuse of wastewater or pro » Type of landscaping and irrigation system.

sign, material and/or color of the primary structures ted openings;

(7) feet in height; twelve (12) feet in height if abutting nt, planted at a maximum spacing of twenty (20) feet four (4) per twenty (20) lineal feet.

water users of nine thousand (9,000) gallons or more

estimated annual use which averages nine thousand related facilities) are required to submit a "water use t or engineer that it complies with this section as a "water use plan" shall contain at least the following:

rvation training programs offered to employees;

used (i.e., effluent, poor quality groundwater or other


(TDS) or conductivity for cooling towers and total

conservation technologies in accordance with existing for process water, alternative dust control methods, continual running water);

rocess water at the facility; and



Elk Grove Village, Illinois



Data centers are permitted in I-1, I-2 and Innovation and Technology Center (ITC) districts. They become a special use in these districts if 100' height or more is requested within 1,000 feet of

One specific example of a data center located within a residential area: Residents were heavily involved in the planning process. Specific site elements included: 250' setback, 6' berm, rock wall and landscaping, residential drainage program around property. Resulted in no public opposition

For I-1 and I-2 zoning: Building height is limited to 45'/2 stories if site is within 200' of residential zoning, 60'/6 stories if site is between 200' – 1,000' from residential zoning, and 100' if site is more


Docks for Data Centers: In considering whether a loading space reduction may be granted, the Zoning Administrator shall consider comparable loading space utilization data provided by the applicant, circumstances unique to the business function of the use, future reuse of the facility, and

Zoning code intentionally allows for flexibility since there are lots of unknowns around power sources.

Site amenities such as ponds, fountains, statuary, plazas and outdoor areas for gathering, walking



Culpeper County, Virginia*



Cobb County, Georgia

	Торіс	Regulation
	DATA CENTER SITING	Data centers are not specifically mentioned in th located a minimum of 500 feet from any school pi
	MECHANICAL EQUIPMENT	When abutting any residential property line, heat within any required buffers (min. 20').
		No ground-based heating and air conditioning u
C 2024 pende	BUILDING DESIGN	Maximum height of 4 stories/70 feet.

Data Centers are permitted by-right in industrial and heavy industrial zoning districts; Conditional

Comprehensive Plan requires data centers are located no more than 0.5 miles from existing electrical

County protects against speculative rezonings by proffering out certain uses, typically applications

Building height maximum of 45' with the ability to increase to 75' if the site is in the Technology

this code, however, similar uses are required to be property and 200 feet from any residential property.

ating and air conditioning units shall not be located

unit shall exceed 35 feet in height.

Henrico County, Virginia

0	
Торіс	Regulation
DATA CENTER SITING	Data Centers are permitted by-right in O-1, O-2, Edge Overlay and as a part of a master plan in LI- » If a data center is small enough that all HV enclosed building, it is treated as an office u » Large data centers requiring external HVAC are power generators and other emergency po- trial use and are only allowed in the industri
BUILDING DESIGN	 For non-residential uses, including data centers, zoning ordinance includes standards for "neigh a proper transition from and ensure compatibil residentially zoned districts and more intense for centers include: » For a site with multiple buildings, building located nearest the adjacent single-family residential development must be orienter lots, rather than toward single-family resider » Loading, service, fuel storage, and mechanis single-family residential lots to the maximur » Required open space must be located betw family residential lots. » Building heights within 75' feet and 150' feet exceed 45' and 55' feet, respectively.

- -2, O-3, O/S, B-1, B-2, B-3, M-1, M-2, M-3, Highway LI-PD.
- HVAC and other mechanical systems are within an use and allowed in all districts above.
- and other mechanical systems (including emergency power supply equipment) are classified as an industrial districts.

- s, proposed adjacent to residential uses, the county ghborhood compatibility." Such standards provide ibility between single-family detached dwellings in orms of development. Applicable standards for data
- ng containing the lowest intensity of use must be residential lots.
- nted to face similar forms of development on adjacent lential lots.
- anical equipment areas must be located away from um extent possible and screened from view.
- etween the proposed development and the single-
- eet from adjacent residential property lines, must not

Fairfax County, Virginia*

	Торіс	Regulation
	DATA CENTER SITING	Data Centers are permitted by-right in C-3 and C I-4 – I-6 is limited by district height of 75' and FAR increase in height/FAR in any listed district; permit
		Data center buildings must be at least 200 feet fro district or property. Equipment such as back-up residential property or separated from the lot line data center building. Lesser distances may be allo
		Data centers must be at least one mile from a Me
		Main entrance features, façade variations, and ot the visual appeal of these industrial buildings.
	BUILDING DESIGN	All equipment must be enclosed or screened by impacts
		Height maximums range from 40' to 120' based o

Amsterdam, Netherlands

Торіс	Regulation
DATA CENTER SITING	Data centers are currently limited to the industrial put into place which will increase regulations on c
POWER	Fines are imposed on data centers that fail to i servers, particularly the requirement to switch off

C-4 up to 40,000 sq. ft; 1-2, I-3 up to 80,000 sq. ft.; AR of 0.5; special exception is required for larger size or nitted in PRC, PDC, PTC if shown on development plan.

from the lot line of an adjacent or abutting residential up generators must be 300 feet from the lot line of ne of a residential district or residential property by the llowed with special exception approval.

Metro station.

other architectural elements are required to enhance

by a wall or similar barrier to reduce visual and noise


d on zoning district.

ial zones of the City. There's a two-phase policy being data centers, and limit siting further.

implement power management protocols on their off idle servers to conserve energy.



Stafford County, Virginia



Data Centers are permitted by-right in M-2 and Integrated Corporate and Technology Park Overlay

Within the M-2 district, all uses conducted within 500' of any A-2, R-1, R-2, R-3 or R-4 district shall be

Data Center facilities are encourage to be located on sites with established and/or preserved vegetative and/or forested buffers of enough depth or density to effectively screen the facility. A viewshed analysis should be submitted for developments adjacent to non-industrial or non-commercial properties, public roadways and cultural/historic resources to demonstrate that the proposed buffers sufficiently

All primary structures must be set back at least 200' from any property line abutting non commercial

Avoid locating on sites with active agriculture, high levels of biodiversity, threatened and endangered species habitat, and large tracts of mature forests. Consideration should be given for connectivity of

Applicants are encouraged to seek certification through programs that help corporate landholders demonstrate a long-term commitment to managing quality habitat for wildlife, conservation education

When in close proximity to passive and active parks and conservation properties, enhanced setbacks and buffers should be considered. A minimum one-mile buffer zone should be considered from the

All mechanical equipment, both on ground and roof-mounted equipment, shall be attenuated through

Facilities should utilize water reuse systems or closed-loop systems for cooling. Should public water and sewer utilities not be available, private wells and septic drainfields may be used for facility bathrooms

The County is working with the data center developers to develop a water service agreement that would require them to construct a reuse water system to limit potable water demands for cooling.

Ensure the electrical grid can support power demands of the end user without negatively impacting

Encourage energy efficiency in building and/or campus design (i.e. LEED certification)



Tower Hamlets, London, United Kingdom

	, 0	
	Торіс	Regulation
		Development is required to use the most approp to minimize noise and vibration impacts, identify vibration from new development, including duri development from existing operational noise, an ating development or noise-sensitive developme
	DATA CENTER SITING	Where new noise-sensitive land uses are propo development is required to robustly demonstra through mitigation measures.
Recenters and		Development is required to demonstrate that the ventilation plant will be below the background le
		During construction, major development is requi low emission zone requirements, minimize levels fumes or dust pollution; consider the routing, timi to reduce their impact on vulnerable road users, construction and/or freight consolidation centre water supply, flood risk and drainage and implen
	CONSTRUCTION	Major development must consider the cumulative the vicinity on levels of noise, vibration, artificial l plan timings of works, delivery timings and route this cumulative impact.
		Development is required to employ the highes Sustainable construction methods, such as the us the use of demolished material from the developr transportation of waste and reduce carbon dioxid
		Development is required to maximize energy eff non-residential development over 500 square n exceed BREEAM 'excellent' rating
	SUSTAINABILITY	Major residential and major non-residential de assessment. The energy assessment should demo accordance with the energy hierarchy and how it w of low nitrogen dioxide decentralized energy, a dioxide emissions through on-site renewable ene

priate, layout, orientation, design and use of buildings tify/outline mitigating measures to manage noise and iring the construction phase, separate noise-sensitive and provide a noise assessment where noise-genernent is proposed.

posed in proximity to existing noise-generating uses, trate how conflict with existing uses will be avoided,

the level of noise emitted from any new heating or level by at least 10dBA.

uired to: comply with the non-road mobile machinery vels of noise, vibration, artificial light, odor, air quality, ming and frequency of heavy goods vehicle movements rs, local amenity and congestion; use, where available, tres, and consider the impact of construction on the ement suitable mitigation measures where required.

ative impact of other major development occurring in al light, odour, air quality, fumes or dust pollution, and utes and location of equipment accordingly to reduce

nest standards of sustainable construction, including: use of sustainably sourced and recycled materials, and ppment site, where practicable, in order to minimize the xide emissions.

efficiency based on the following standards: a. All new meters floor space (gross) are expected to meet or

development will be required to submit an energy monstrate how the development has been designed in it will: maximize energy efficiency, outline the feasibility and seek to provide up to 20% reduction of carbon energy generation.

Section 5 | Conclusions & Next Steps

Early Considerations for Prince William County

The team has conducted a thorough review of state code and local ordinances, policies, and legislative approvals related to data center development in Prince William County. In addition, the team has analyzed the requirements and policies of several peer communities who are currently experiencing data center development. This work has allowed the team to begin to identify areas where Prince William County's regulations governing data center development could be enhanced and updated.

The following page outlines potential areas for improvement related to data center development in Prince William County. These are initial considerations that will be further refined and developed into proposed updates to the Zoning Ordinance and Design and Construction Standards Manual through engagement with County staff, the Data Center Ordinance Advisory Group (DCOAG), local

stakeholders, and residents of Prince William County.

As the team continue its work, the list of topics will evolve into more specific and detailed language that can be incorporated into the Zoning Ordinance and Design and Construction Standards Manual.

At the conclusion of this work, our team along with County staff will present a draft ordinance and DCSM amendment to the Planning Commission and Board of County Supervisors. These bodies will have the opportunity to consider the proposed changes and decide how to incorporate them into the County's regulatory documents.

Overall, the goal is to develop recommended updates to the Zoning Ordinance and DCSM that effectively balance the economic benefits of data center development with the need to protect the quality of life of Prince William County's residents and its natural, cultural, and historic resources.

Early Considerations for Updates to the ZC	
Торіс	Potential Updates or
Allowable Uses	Reassess which zoning dis prohibited uses to confirm
Definition	Refine the definition of "d substations and alternativ on power and water usag
Separation and Buffers	Enhance requirements for landscaping, particularly or or protected areas like scl erations for substations a
Architectural Standards	Strengthen architectural r renderings for review; cor and security fencing desig office buildings, particula
Water Supply	Consider requirements as or non-potable water, clo submission of a water usa
Power and Energy	Consider requirements th ground; confirm that a po renewable energy; and co (PUE) ratio to assess energi
Site layout / building configuration	Consider changes to site open space, impervious s generators and associated
Bulk and Massing	Consider linking bulk, hei proximity to residential ar inclusive of requirements
Substations and Generators	Enhance the review proce locations on site, screenir
Noise	Incorporate requirements mechanical equipment, su noise and emissions, and
Construc- tion Impact Mitigation	Consider regulations spec hauling and disposal to a activity.

and DCSM

Changes

stricts classify data centers as permitted, special, or m appropriate alignment with land use goals.

lata center"; consider exclusions for facilities such as e power sources and separate classifications based le.

setbacks, separation distances, screening, and when data centers are near residential, agricultural, hools, parks, and cultural resources. Include considnd mechanical equipment in these revisions.

requirements for data centers and require 3D nsider requirements for breaking up large facades gn standards; data center designs can resemble rly within office zoning districts.

sociated with water usage, such as use of recycled sed loop systems, pretreatment of effluent and age plan for review.

at new transmission lines be installed underortion of the facility's energy needs is sourced from onsider implementing a Power Usage Effectiveness gy efficiency.

layout requirements and evaluate requirements for surfaces, viewshed impacts, and locations for utilities, d equipment.

ight, and massing of data center buildings to their eas and the architectural design of the facility, for rooftop mechanical equipment.

ess for substations and generators, including their ig, emissions, and noise.

for specific modifications to reduce noise from uch as installing mufflers on generators to mitigate requirements for monitoring.

cific to construction truck routing, phasing, off-site ddress negative impacts related to construction

Section 6 | Appendix

Overview

The Appendix provides a more comprehensive catalog of the regulations compiled by the consulting team from the three tiers of peer research. This section offers a deeper dive into the regulations and standards from the localities researched for this report to serve as a supplement to the findings of the report.

Please note that the following tables only include regulations from jurisdictions that have adopted regulations addressing the each topic. These lists are presented in no particular order, except the regulations from Prince William County are listed first in each table.



Equinix Data Center, Amsterdam.

Definitions	
Jurisdiction	Definition
Prince William County, VA	Data Center shall mean a us of the use is occupied by co equipment, including suppo transferred and/or stored.
Stafford County, VA	A facility where the principal and/or transmission of digit computer systems and/or re- may include but is not limite facilities, utility substations suppression systems, and/or require additional approvals
Fairfax County, VA	A facility containing one or data storage and processing includes back-up batteries suppression systems, and e
Henrico County, VA	A facility containing one or data storage and processing includes back-up batteries a suppression systems, and e has few on-site employees.
Elk Grove Village, IL	A facility primarily used for transmission of digital data support equipment such as components.
Chandler, AZ	A facility or portion of a fac telecommunications equipr distribution of data.
Loudoun County, VA	Data Center: An establishmo processing, and/or transmis network equipment, system nents related to digital data Data Center Mechanical Equ and/or provide energy for t
Warrenton, VA	A facility containing one or data storage and processing includes back-up batteries units, fire suppression syste

se involving a building/premise in which the majority omputers and/or telecommunications and related orting equipment, where information is processed,

al use is the storage, management, processing, tal data, and containing one or more large-scale elated equipment. Such facility or use typically ed to air handlers, water cooling and storage and infrastructure, back-up power generation, fire or enhanced security systems, any of which may s or conditional use permits, as applicable.

more large-scale computer systems used for g for off-site users. Typical supporting equipment and power generators, cooling units, fire nhanced security features.

more large-scale computer systems used for q for off-site users. Typical supporting equipment and power generators, cooling units, fire nhanced security features. A data center typically

the storage, management, processing and including related office areas through the use of servers, networks and other similar computer-based

ility housing networked computer systems and ment used for remote storage, processing, and

ent engaging in the storage, management, ssion of digital data, and housing computer and/or ns, servers, appliances and other associated compooperations.

uipment: On-site exterior machines used to sustain he operations of a Data Center."

more large-scale computer systems used for q for off-site users. Typical supporting equipment and power generators, electric substations, cooling ms, and enhanced security features.

Siting Requirements

Jurisdiction	Siting Requirements	
	Within the Data Center Opportunity Zone Overlay District, data centers are permitted by-right in the following zoning districts:	
	» O(L) – Office Low-Rise	
	» O(H) – Office High-Rise	
	» O(M) – Office Mid-Rise	
	» O(F) – Office/Flex	
	» M-1 – Heavy Industrial	
Prince William County	» M-2 – Light Industrial	
	» M/T – Industrial/Transportation	
	In designated office or industrial land bays in PBD (Planned Business District) and PMD (Planned Mixed Use District) districts. Outside of the Data Center Opportunity Zone Overlay District data centers require a special use permit in the districts noted above. Prohibited Districts: Data centers shall be prohibited in agricultural, residential, PMR, B-2, B-3 and V districts.	
Montgomery County, MD	allowed within IL (Industrial Light) and IM (Industrial Moderate) zones	
Hillsboro, OR	Permitted by-right as an accessory uses where industrial services and manufacturing are the primary uses, I-G district	
Amsterdam, NE	Industrial areas; the city only allows for moderate growth and concen- tration of data centers until 2030 with 550 megavolt amperes (in addition to some data centers for which environmental permit applications have already been submitted).5 No additional space for data centers is available in Haarlemmermeer after 2030 (except for some specific locations).These conditions relate to the spatial quality and landscape integration, energy use and sustainability of the data centers	
Stafford County, VA	Permitted: M-2, ICTP (Integrated Corporate and Technology Park Overlay)	
Fairfax County, VA	"By-right: C-3,c-4 up to 40,000 sf; SE required for larger size or increase in height/FAR I-2,I-3 up to 80,000 sf; SE required for larger size or increase in height/FAR I-4 now has a size limit I-5,I-6 limited by district height of 75' and FAR of 0.5; SE required for increase in height or FAR PRC,PDC, PTC if shown on development plan	
	Limits on the size of by-right data centers are retained where they previously applied and now the I-4 District has a size limit as well. Larger developments require special exception approval, except in the I-5 and I-6 Zoning Districts"	

Jurisdiction	Siting Requiremen
Henrico County, VA	Permitted by-right: O- Highway Edge Overlay Allowed as a part of m
Culpeper County, VA	Data processing and co support is a permitted (HI)
Elk Grove Village, IL	Permitted in: ITC (Innov requesting 100' height
Chandler, AZ	Data centers are not per explicitly approved as p Data centers that are a a) occupy no more that used to serve the enter are not used to lease d and c) are not housed
Loudoun County, VA	"Permitted: IP, GI, MR- Special Exception: Plan Park, Commercial Light **In the process of am permitted districts to s data centers are permi
Warrenton, VA	Special Use Permit: Ind
Fauquier County, VA	"Permitted: BP in servic and with all new power feedlines, placed under recycled water for cool mission or substation f

nts

- -1, O-2, O-3, O/S, B-1, B-2, B-3, M-1, M-2, M-3,
- naster plan: LI-PD "
- computing, secure messaging services and customer l use in Light Industry - Industrial Park and Industrial
- ovation and Technology Center); I-1; I-2; Special use if t within 1,000 feet of residential zoning.
- permitted to operate in the City of Chandler unless part of a Planned Area Development zoning district. ancillary to another primary use are permitted if they an ten (10) percent of the building footprint, b) are erprise functions of the on-site property owner and data storage and processing services to third parties, in a separate stand-alone structure on the parcel. -HI
- nned Development Research and Development nt Industry, OP
- nending the zoning ordinance to change all special exception. There will be no districts where itted."
- dustrial district
- ce district; PCID (using recycled water for cooling er lines, including transmission or substation erground) Special Exception Use: BP; PCID (not using bling and with all new power lines, including transfeedlines, placed underground)"



Separation, Buffering, Landscaping, and Screening

Jurisdiction	Separation/Buffering/Landscaping/Screening Requirement
Prince William County	Buffer Area Width and Plant Requirements: Type A: 15 feet; 110 plants per 100 feet of ROW or property line Type B: 30 feet; 180 plants per 100 feet of ROW or property line Type C: 50 feet; 320 plants per 100 feet of ROW or property line Type D: case by case (min. 15 feet); based on approval width fence or berm may be substituted for 30% of buffer width
Montgomery County, MD	A 200-ft buffer between operations and any lot line and a min. 300-ft separation from streams, floodplains, or wetlands.
Stafford County, VA	All primary structures shall be set back at least one hundred (100) feet from any property line abutting non-commercial or non-industrial zoned properties for sites located within the urban services area, and at least two hundred (200) feet from any property line abutting non-commercial or non-industrial zoned properties for other sites.
Fairfax County, VA	Data center buildings must be at least 200 feet from the lot line of an adjacent or abutting residential district or property. Equipment such as back-up generators must be 300 feet from the lot line of residential property. Data centers must be at least one mile from a Metro station.
Elk Grove Village, IL	» 50 feet separation requirement when data center abuts residential district; height requirements change based on distance to residential zoning districts.
	 When abutting areas zoned for residential use, an opaque screen along all lot lines adjacent to residential use is required. Fences shall be black wrought iron or similar design as approved by the Zoning Administrator.
Cobb County, GA	Data centers shall not be located closer than 500 feet to any school property. Data centers shall not be located closer than 200 feet to any residential property line. Any property within an office & industrial district which abuts a residentially zoned property shall have a minimum 20-foot landscaped screening buffer. Required buffers may be included within required setbacks; Landscape buffers are subject to review and approval by the county arborist or county landscape architect and buffer should provide a 100 percent visual barrier to a height of six feet within two years of planting.

Jurisdiction	Separation/Buffering/La
	The following requirement be located on a property residential, or Zoning Dist separated by a principal a
Loudoun County, VA	 Parking must be setted provided existing for feet of the lot line, if provided at least 10 and plantings are pl
	 » Structures must be s property line;
	 Building Step-Back. property line adjace envelope must prov building wall at a he story of the building
	 Industrial uses, inclu provide a buffer yar ational uses.
	 » Buffer Yard: Industri (50) feet wide plus of ty-five (35) feet.;
Warrenton, VA	 » Double staggered r center, or a double s feet on center, form (6) feet in height with earthen berm, with interspersed every to the residential use.
	 In addition to indust center (including ed the street from a re consisting of a doub on center. A minimu of evergreen shrubs the double staggere
	 » No buffer yard sha percent of the gross

andscaping/Screening Requirement

nts apply when a proposed Data Center is to adjacent to property with existing or approved strict permitting residential, including when arterial or lesser designated roadway:

tback at least 50 feet from the property line, prest and other natural screening exists within 50 if no forest or natural screening exists, berms are) feet in height constructed and 10-foot-tall fencing laced on top of the berm;

setback at least 200 feet from the common

If a building is located within 400 feet from the ent to property with residential, the building vide a step- back of no less than 15 feet from the eight point that begins at the top of the second g or 40 feet, whichever of the two is lower.

Iding associated parking lots and storage areas, shall rd where they are adjacent to residential and recre-

ial uses from residential and recreational uses: Fifty one foot for each foot of building height over thir-

row of evergreen trees planted fifteen (15) feet on staggered row of evergreen shrubs planted ten (10) ming a dense, continuous visual screen at least six vithin one (1) year of planting or A fence or wall or a minimum six (6) foot height, with evergreen trees twenty-five (25) feet along the side of the wall facing

trial screening requirements, any portion of the data quipment) visible from a park or adjoining/across esidential district shall be screened by vegetation ble staggered row of evergreen trees planted 15 feet um 3 foot berm planted with a double staggered row s planted 10 feet on center may be used in place of ed row of evergreen trees required above.

Ill be required to comprise more than fifteen (15) s area of the subject property

Jurisdiction	Separation/Buffering/Landscaping/Screening Requirement	Jurisdiction	Separation/Buffering/La
Salt Lake County, UT	20 foot wide buffer required between nonresidential & residential containing a min. of 1 tree for every 25 feet.		Within the M-2 district, a of any A-2, R-1, R-2, R-3 buildings. Storage may be screened by a wall, hedge
Maricopa County, AZ	 » Solid masonry, concrete or earthen product at least 6 ft tall required along any side/rear property line adjacent to any rural or residential zoning. » Any part of site not used for buildings, etc. must be landscaped and maintained. 		thereof, so that such out of-way or property zone For sites abutting or acro zoned properties, a veget landscaped strip at least s security fencing at least s anti-climbing device, and
Middlesex County, NJ	30 foot wide buffer is required between industrial uses and residential zones. Barbed wire/similar fences permitted as long as not in front yard and barbed wire must be above 6 feet high.	ong as not in front yard and The foll or archi ground	
Hillsboro, OR	Industrial properties abutting residential zones must maintain a dense evergreen buffer at least 7 feet high. Buffer must be 20 feet wide. Setbacks increased to 75 feet when adjacent to residential zoning.		HVAC units, electric, wate transformers, generators, including wall-mounted e Commercial and Industria transitional buffer 25-35 Commercial and Industria
Virginia Beach, VA	When a zoning lot within an I-1 Industrial District adjoins a residential or apartment district without an intervening street, alley or body of water over twenty-five (25) feet in width, a twenty-five-foot minimum yard shall be required along all lot lines adjoining the residential or apartment district. Category II buffer: 25' wide, 5-6' height at planting, 20' height at maturity,		 zoning: transitional buffer » Buffer 25: 25 feet wide and 16 shrubs per 10 » Buffer 35: 35 feet wide w trees and 19 shrubs » Buffer 50: 50 feet wide
Montgomery County, MD	 » If an industrial property abuts agricultural or residential zones, the perimeter planting area must be at least 30' wide, with a min. 6' high fence, wall, or berm, and two canopy trees per 100'. » A 50-ft buffer is required between industrial properties and railroad or utility ROWs, nonresidential public use properties, and if the property abuts a limited-access freeway, a parkway, or similar infrastructure. 		 and 24 shrubs per 1 » Brick or architectura 12-20', reduces plan » Opaque fence of a minimum buffer by » Evergreen plantings maturity, reduces minimaturity, reduces minimaturity

Landscaping/Screening Requirement

all uses conducted within five hundred (500) feet or R-4 district shall be conducted within enclosed be permitted outdoors, but shall be effectively ge, berm, fence, or landscaping, or a combination tdoor storage will not be visible from a public righted other than M-1 or M-2.

oss a road from non-industrial or non-commercial etated buffer shall be required consisting of a t fifty (50) feet wide. The site shall be enclosed with seven (7) feet in height, include an appropriate nd shall be secured with gates. Security fencing shall iny required buffer.

st be screened by the principal buildings on the site, ated building elements, or opaque walls or fences: poftop utility and mechanical equipment, including ter, and gas meters, junction and accessory boxes, s, and accessory solar energy equipment, but not equipment

- rial uses 15,000 sf of less adjacent to A/R zoning:
- rial uses greater than 15,000 sf adjacent to A/R fer 50
- vide, 4 large and 2 small deciduous or evergreen trees 100 linear feet
- wide, 5 large and 2.5 small deciduous or evergreen os per 100 linear feet
- vide, 7 large and 4 small deciduous or evergreen trees 100 linear feet
- ral block wall: 6-10 feet, reduces minimum buffer by int quantity by 30-50%
- approved design and materials: 6 feet, reduces y 12 feet, reduces plant quantity by 30%
- as in an unbroken strip at maturity: 6 planted, 10 at minimum buffer by 8', reduces plant quantity by 30%.

Jurisdiction	Separation/Buffering/Landscaping/Screening Requirement		
	 When required, screening shall consist of new plantings, existing vegetation, an opaque masonry wall or wooden fence, or combination thereof, to the reasonable satisfaction of the Approving Authority. Where only vegetation is provided, a planting strip of not less than twenty feet in width shall be provided. 		
Culpeper County, VA	 Where new plantings are to be installed, they shall consist of (i) two rows of evergreen trees planted ten feet on center and staggered, or (ii) a berm not exceeding a slope of 2:1 with two rows of evergreen shrubs planted twenty feet on center and staggered. 		
	» Alternate methods of vegetative screening may be approved by the Approving Authority as follows: one large shade tree, one medium shade tree and one evergreen tree, per 500 square feet of area, and one shrub per 50 square feet of area.		
	Where a wall or fence is provided, it shall be a minimum of six feet in height and evergreen plantings shall be required at approximately ten-foot intervals along the side of any such wall or fence facing a public street or the use for which the screening shall benefit.		
	Landscape buffer areas/dissimilar land uses:		
	 A six-foot masonry wall reflecting the design, material and/or color of the primary structures within the project, excluding approved gated openings; and 		
Chandler, AZ	 » Evergreen trees a minimum of seven (7) feet in height; twelve (12) feet in height if abutting existing or planned residential development, planted at a maximum spacing of twenty (20) feet on center and shrubs planted at a rate of four (4) per twenty (20) lineal feet. Landscape buffer areas/dissimilar land uses: 		
	 A six-foot masonry wall reflecting the design, material and/or color of the primary structures within the project, excluding approved gated openings; and 		
	 » Evergreen trees a minimum of seven (7) feet in height; twelve (12) feet in height if abutting existing or planned residential development, planted at a maximum spacing of twenty (20) feet on center and shrubs planted at a rate of four (4) per twenty (20) lineal feet. 		

Bulk & Massing

	0
Jurisdiction	Bulk & Massing Req
Prince William County, VA	The maximum lot covera minimum open space of lot coverage is 85% with heights range from 45 fe added by Special Use Pe ranges from 0.35 - 1.25 k tunity Zone Overlay Dist visors may approve a FA proffered rezoning or Sp
Montgomery County, MD	Maximum uilding height FAR ranges from 0.25 - 2
Salt Lake County, UT	The maximum lot covera industrial districts.
Irving, TX	The maximum building h
Denver, CO	The maximum lot covera feet - 110 feet, with no h maximum FAR is 2.0.
Maricopa County, AZ	The maximum lot covera
Middlesex County, NJ	The maximum lot covera recharge areas, and the r
Hillsboro, OR	The maximum lot covera However, high-profile bu are locatedwithin 100 fee 45 feet, with further redu setback.
Virginia Beach, VA	When an industrial zonir maximum height is 35 fe for the different apartme uses is 2.5.
Stafford County, VA	A minimum of 30% oper services area. Height ma from 65 to 80 feet. The r

quirements

rage for Office and M-2 districts is 80% with a f 20%. For the M/T and M-1 districts, the maximum h a minimum open space of 15%. Maximum building feet - 100 feet, however additional height may be ermit or Rezoning applications. The maximum FAR by zoning district, however the Data Center Opportrict allows a FAR of 1.0. The Board of County Super-R higher than that permitted by right by specifically pecial Use Permit.

nt ranges from 25 feet - 120 feet and the maximum 2.5.

rage is 80%, and maximum height is 35 feet for

height is 50 feet.

rage is 50%, and the maximum height ranges from 45 height limitations in general industrial zoning. The

rage is 60%, and the maximum height is 40 feet.

rage is 50% when located on aquifer outcrop or maximum height is 35 feet.

rage is 50% with a maximum height of 45 feet. uildings may be allowed up to 150 feet, but if they eet of a residential district, the height is reduced to uctions of 1 ft for every 2 ft less than than 100 ft

ing district is adjacent to a residential district, the feet. The maximum height varies from 35 - 120 feet ent zoning districts. The maximum FAR for industrial

en space is required for sites outside of the urban aximums where data centers may be permitted range maximum FAR is 1.0.



Jurisdiction	Bulk & Massing Requirements	
Fairfax County, VA	"The maximum size of a data center varies by zoning district, in C-3 and C-4 data centers up to 40,000 sq. ft. are permitted, and 80,000 sq. ft. in 1-2 and I-3. Maximum heights range from 40 feet - 120 feet depending on zoning district. 10%-20% minimum landscaped open space is required. The maximum FAR varies from 0.25 to 1.0 depending on district.	
Henrico County, VA	Maximum lot coverages range from 60% - 90% and maximum heights range from 45 feet - 200 feet depending on zoning district.	
Culpeper County, VA	Maximum lot coverages range from 50% - 75% depending on zoning district. The maximum height is 75 feet and the maximum FAR ranges from 0.5 - 1.0.	
Elk Grove Village, IL	"Maximum lot coverage is 50% for the ITC district, and 80% for I-1 and I-2 districts. If the site has I-1 or I-2 zoning and is within 200 feet of residential zoning, the maximum height is 45 feet or 2 stories. The maximum increases to 60 feet or 6 stories within 1,000 feet of residential, and 100 feet if over 1,000 feet from residential zoning. The maximum height for ITC is 375 feet or 25 stories. The FAR for I-1 and I-2 ranges from 0.8 - 2.0, and is 0.5 for each floor for the ITC district.	
Chandler, AZ	Bulk and Massing of data centers is determined through the Planned Area Development (PAD) process, and based on the quality of the proposal.	
Cobb County, GA	Maximum lot coverage for industrial districts is 80%, with a maximum height ranging from 52 - 70 feet or four stories.	
Loudoun County, VA	unty, VA Maximum lot coverage ranges from 0.40 - 0.55, with a maximum height of 45 feet - 100 feet. The maximum FAR ranges from 0.4-2.0.	
Warrenton, VA	The maximum lot coverage is 75%, with a maximum height of 35 feet.	
Fauquier County, VA	The maximum lot coverage is 50% with a maximum height of 45 feet However, if the applicant can demonstrate that the proposed height is compatible with no adverse impacts through a viseal impact analysis, it may be increased.	

Mechanical Equipment

Jurisdiction	Mechanical Equipmen
Prince William County	Ground level and roof top r arterials, interstates and abu This screening may be prov to remain or is within a land Mechanical equipment not vegetation shall be screened with the principal building. impact on adjacent roads o Substations. Substations sha residentially zoned/planned other buffering and landsca
Salt Lake County, UT	Mechanical Equipment mus berms, or a combination of
Irving, TX	Must be screened by solid r element of the equipment.
Denver, CO	Rooftop mechanical equipn should be similar to that of
Maricopa County, AZ	Rooftop equipment must be integrated into the building solid screen wall at least 6 f
Hillsboro, OR	Roof-mounted equipment r materials compatible with b
Stafford County, VA	All mechanical equipment, l be attenuated through sour sound muffling materials.

t Requirements

mechanical equipment shall be screened from major outting residentially zoned or planned properties. vided by a principal building or existing vegetation dscaping/buffer easement on an adjacent property. screened by a principal building or existing ed by a visually solid fence, wall or panel compatible . Mechanical equipment found to have no adverse or properties shall not be required to be screened.

nall be screened from adjacent major roads or d properties with a 10 feet tall opaque fence and all aping requirements.

ist be screened by plants, solid opaque fencing, the above.

masonry wall at minimum height of the highest Finished in a color similar to the building facade.

ment screened from ground level view. Materials the main building façade.

be screened to the height of the tallest equipment or g design. Ground equipment must be enclosed by a feet high.

must be screened from street-level view with building design and must be placed behind parapets.

both on ground and roof-mounted equipment, shall und mitigation measures including, but not limited to,



Section 6 | Appendix

Jurisdiction	Mechanical Equipment Requirements	
Fairfax County, VA	All equipment must be enclosed or screened by a wall or similar barrier to reduce visual and noise impacts	
Henrico County, VA	For data centers in all districts except the M-1, M-2, and M-3 districts, all equipment necessary for cooling, ventilating, or otherwise operating the facility must be contained within an enclosed building where the use is located. This includes emergency power generators and other emergency power supply equipment.	
	Mechanical equipment must be screened by the principal buildings on the site, or architecturally integrated building elements, or opaque walls or fences of approved design and materials compatible with the principal buildings."	
Culpeper County, VA	Rooftop mechanical equipment are required to be screened by exterior architectural material of the same type as the building. All utility or mechanical equipment not entirely within a screened service area shall have a natural evergreen planting screen provided. In lieu of such screening, utility or mechanical equipment may be shielded from view by any structure architec- turally compatible with an adjacent building.	
Elk Grove Village, IL	All ground mounted equipment shall be screened by fencing, berms, plantings, screen wall or any combination, to sufficiently obscure such equipment from view from all adjacent streets and residentially zoned property.	
Chandler, AZ	All mechanical equipment shall be screened from view in their entirety as an integral part of the building by parapets, or screening of similar materials as the primary building to appear as part of the structure. All mechanical equipment must be shown on building sections and elevations submitted to the City.	
Cobb County, GA	Heating and air conditioning units shall not be located within any required buffers when abutting residential land and shall be at least 5 feet from side and rear property lines when abutting nonresidential zoning districts. No ground- based heating and air conditioning units shall exceed 35feet in height.	
Loudoun County, VA	All ground level and roof top equipment must be shown on the site plan and screened on all sides with a visually solid screen compatible with those of the principal building. Screening may incorporate perforated surfaces for ventilation. Ground mounted mechanical equipment must be separated from adjacent residential zoning by a principal building, and is prohibited in front yards. Additionall there are no screening requirements when the property is adjacent to industrially zoned property.	

Jurisdiction	Mechanical Equipment
Warrenton, VA	Mechanical equipment shall fences or evergreen vegetati can be seen from adjoining p equipped with mufflers to re
Fauquier County, VA	Ground and/or rooftop mou tions should be screened fro or planned properties. The se not feasible, the design shou compatible with the design of should be located and screen attenuation.

t Requirements

l be completely screened through the use of walls, tion so that no part of the mechanical equipment properties or right-of-ways. All generators shall be reduce emissions and noise.

ounted mechanical equipment and on-site substarom roadways and adjacent residentially zoned screening preference is the principal building, if buld include a solid fence, wall or panel and be of the principal building. Mechanical equipment ened in a manner which provides appropriate noise



Architectural Standards

Jurisdiction	Architectural Requirements		Jurisdiction	Architectural Requir	
Prince William County	Principal building façades shall include all building façades that face adjacent major arterials or interstates. When a building has more than one principal façade, such principal building façades shall be consistent in terms of design, materials, details, and treatment. Principal building façades shall avoid the use of undifferentiated surfaces by including at least two of the following design elements: change in building height, building step-backs or recesses, fenes- tration, change in building material, pattern, texture, color; or use of accent materials.		Fauquier County, VA	Buildings should be sited streets and adjacent non- street. Loading dock, gro be viewable from importa and developments with r each other. Where feasib passive cooling and dayli Multi-building developm	
Hillsboro, OR	Permitted exterior materials include brick, natural stone, concrete masonry units, and metal. Glass is allowed as an accent material, wood is acceptable for soffits, overhangs, & entrance canopies. Buildings must incorporate features such as cornices, pilasters, belt courses, ornamental masonry, bays, etc.			and appearances. Reduce down the large massing of recommended to occur e least one change in horiz or architectural elements shadow lines and variatio 4.Variation at the ground mass as viewed from pub Fenestration should be us congruent with adjacent building that face public Primary building facades that a minimum of 50% of façade and 20% of all oth	
Fairfax County, VA	Main entrance features, façade variations, and other architectural elements are required to enhance the visual appeal of data center buildings.				
Chandler, AZ	Architectural style is not prescribed, however the design shall convey a high degree of quality commensurate with the neighborhood and consistent with the Chandler General Plan. Large building facades are deemed inconsistent with the low-key small-town character of Chandler and are discouraged.				
Loudoun County, VA	Data center principal façades must incorporate fenestration and a change in design elements no less frequent than every 150 horizontal feet or 3 times the average height of the building.Multiple principal facades must be consistent in terms of design, materials, details, and treatment. Each principal facade must include 30% fenestration and meet the fenestration coverage requirements. Main entrance features must include projection or recession from the main building plane, and incorporate plantings a minimum of 50% of the facade length.	mes the stent in stent in stent in stent in stend stends and stends		precast and cast-in-place systems. All metal panels systems.	
Warrenton, VA	Building facades shall include at least two of the following design elements: change in building height, building step-backs or recesses, fenestration (25% minimum), change in building material, pattern, texture, or color, and use of accent materials.				

irements

ed and oriented to minimize visual impacts from public on-industrial uses and oriented towards the public round equipment and other storage areas should not rtant viewsheds, street frontages and open spaces, multiple buildings should orient service areas to face ible, buildings should be oriented to take advantage of ylighting opportunities.

ments should include a variety of building sizes masses, ice the perceived scale of buildings by visually breaking g of typical buildings. Changes in horizontal plane are every 150 to 200 feet. All facades should include at rizontal plane. Building step-backs, projections, recesses ts should have a minimum depth of 4 feet to create tions in the façade.

nd plan can be utilized to create transition in scale and ublic streets.

used to avoid monolithic appearances and to be nt uses. Transparency shall be provided on faces of the c roads.

es should use a neutral color palette. It is recommended of the entrance elevation; 35% of any street facing ther elevations shall include: brick, concrete (both ce), metal panels or anodized aluminum, glazing els should be fully engineered, architectural quality



Water Usage

Jurisdiction	Water Usage
Prince William County, VA	No requirement
Chandler, AZ	Data centers are not permitted to use reclaimed water for their facilities. Additionally, new non-residential water users who have an estimated annual use which averages nine thousand (9,000) gallons per day or more are required to submit a "water use plan" sealed by an Arizona registered architect or engineer that it complies with this section as a condition of issuance of a building permit. The plan will contain among other requirements, whether alternative water sources will be used, operation levels of total dissolved solids or conductivity for cooling towners and total cooling capacity, whether the best available conservation technilogy will be used (re-circulating systems for process water, etc), and any plans for the reuse of wastewater or process water at the facility
Warrenton, VA	Data centers are required to utilize recycled water or air chillers, in conjunction with using recycled water, for cooling purposes. Potable water shall not be used for cooling.
Fauquier County, VA	Applicants shall demonstrate and commit to meeting the County's recycled water requirement, demonstrate adequacy of water for firefighting situations (without impacting local private wells or public water sources). Construction activities, including any required blasting, should not impact the public water supply.

Power / Energy Usage

Jurisdiction	Power / Energy Usage
Prince William County, VA	No requirement
London, UK (Tower Hamlets)	All new non-residential dev are expected to meet or exe and major non-residential of assessment. Minor nonresid prepare an assessment. The assessmen maximize energy efficiency, tralized energy and seek to reduction through on-site r
Amsterdam, NE	Fines are imposed on data protocols on their servers, p conserve energy.
Loudoun County, VA	For data centers, site-specif of the gross floor area of th within the principal building nately, the energy storage f building when fully screene components and associated clearances, and electrical cin marked with the environme compliance with NFPA 70 - Container Size. Containers f 900 square feet in size.

Requirements

velopment over 500 square metres floorspace (gross) ceed BREEAM 'excellent' rating. Major residential development will be required to submit an energy idential development will be strongly encouraged to

nt should demonstrate how the development will y, the feasibility of low nitrogen dioxide dencenprovide up to 20% carbon dioxide emissions renewable energy sources.

centers that fail to implement power management particularly the need to switch off idle servers to

ific energy storage facilities must not exceed 30% he use. The energy storage facility must be located g or within a permitted accessory building. Alterfacility may be located on the roof of the principal ed from public view. All energy storage facility ed equipment must have required working space ircuitry must be within weatherproof enclosures ental rating suitable for the type of exposure in - National Electrical Code. Energy Storage Facility housing energy storage equipment are limited to



Jurisdiction	Power / Energy Usage Requirements
Warrenton, VA	All electric service lines from the substation to the data center shall be placed underground. The facility shall provide access to Town and County emergency services staff at all times.
Fauquier County, VA	Data Centers should be where existing infrastructure exists to support the development and should be located no further than 1 mile from an existing electric transmission line, with all new lines being placed underground. On-site solar and geothermal energy as well as other renewable sources are encouraged to be utilized to meet a portion of the development's energy requirements. Data Centers are encouraged to commit to a Power Usage Effectiveness (PUE) ratio of 1.5 or less and proffer such commitment. Buildings should be oriented to take advantage of passive cooling and daylight opportunities. Innovative technologies which reduce power consumption should be incorporated into the project's design. Heat generated by Data Center operations should be trapped and reused to the maximum extent possible. Rezoning applications are highly encouraged to clearly demonstrate, to the greatest extent possible, how electricity will be provided to accommodate the project's development, and how the project's overall power demand relates to the overall regional network. This should include any on or off-site need for a new substation, expansion of an existing substation, switching station, and/ or any other electrical infrastructure. Rezoning applications should commit, through a voluntary proffer, to a maximum electrical load/demand for the entire development. Site Plan applications shall clearly demonstrate how electricity will be provided to accommodate the project's development.

