

# Potomac Heritage National Scenic Trail Feasibility Study

 $Gap\ Area\ 2-Town\ of\ Dumfries$ 

Prince William County, VA

**July 2025** 

# **Table of Contents**

Executive S	Summary	1
1.0 Introdu	ction, Background, and Purpose	
1.1	Introduction	1
1.2	Background	2
Histo	ory	2
Socia	al and Economic Benefits	3
Socia	al and Demographic Data Along the Trail Study Areas	4
Previ	ious Planning and Studies	5
1.3	Purpose and Needs	9
Purp	ose	9
Need	ds	9
2.0 Stakeho	older Coordination	11
2.1 Stak	eholder Meetings – Round 1	11
2.2 Stak	eholder Meetings – Round 2	11
3.0 Evaluat	ion of Existing Conditions and Potential Environmental Consequences	12
3.1	Traffic Data and Crossings	
3.1.1	Traffic Volumes	12
3.1.2	Crossings	12
3.1.3	Safety Issues Identified	12
3.2	Trails and Connections	
3.3 Majo	or Destinations, Attractions, and Military Facilities	13
3.4 Utilit	ties	
3.5 Topo	ography	14
3.6	Environmental Resources	14
3.6.1	Socioeconomic Resources	14
3.6.2	Natural Resources	
3.6.3	Hazardous Materials	16
3.6.4	Air Quality	17
3.6.5	Noise	17
3.6.6	Historic Resources	17
3.6.7	Parks and Recreational Facilities	17
3.6.8	Visual Quality	18
3.6.9	Section 4(f) and 6(f) Resources	18
4.0 Propose	ed Alternatives	19

4.1	Gap Area 2 Alternative Concepts	19
Alte	rnative 2.1	19
Alte	rnative 2.2	20
Alte	rnative 2.3	21
5.0 Alterna	atives Screening and Evaluation	22
5.1 Scre	eening and Evaluation	22
Acce	ess and Mobility	22
Hea	lth, Safety, and Quality of Life	22
Есоі	nomic Benefits	23
5.2	Screening Summary	24
6.0 Retain	ed Alternatives and Impact Evaluation	25
6.1	Gap Area 2 Retained Alternatives Impact Evaluation	26
6.1.1	L Socioeconomic Resources	27
6.1.2	2 Natural Resources	27
6.1.3	3 Hazardous Materials	28
6.1.4	Air Quality and Noise	29
6.1.5	5 Historic Resources	29
6.2.6	S Section 4(f) / 6(f) Resources	30
6.1.7	7 Safety	30
7.0 Recom	mended Alternative	31
7.1	Alternative 2.1	31
Trai	Attractiveness	32
Cost	of Construction	32
8.0 Project	t Costs	33
9.0 Project	t Phasing	35
9.1	Phasing Within Gap Area 2:	35
10.0 Next 5	Steps	36
10.1	Incorporation of Recommended Alternative into Relevant Plans	36
10.2	Funding Opportunities	36
10.2	.1 Federal Sources	37
10.2	.2 Non-Federal Sources	38
10.3	Conclusion	39
Citatiana		4.0

# **Tables**

Table 1 - Ability of Proposed Alternatives to Meeting Purpose and Need Elements	24
Table 2 - Gap Area 2 Retained Alternatives Impact Summary	26
Table 3 - Species with Habitat Identified Within the Vicinity of the Study Area	28
Table 4 - Water Resources Mapped within the Vicinity of the Study Area	28
Table 5 - Estimated Alternative Costs	34
Figures	
Figure 1 – PHNST Gap Area 2 Study Area	1
Figure 2 - PHNST Extent	
Figure 4 - Health Benefits	
Figure 3 - Economic Benefits	
Figure 5 - Transportation Benefits	
Figure 6 - Priority Investment Rating	8
Figure 7 - Alternative 2.1 Alignment	19
Figure 8 - Alternative 2.2 Alignment	20
Figure 9 - Alternative 2.3 Alignment	
Figure 10 - Recommended Alternative Alignment	31
Appendices	
Appendix A	Existing Conditions Mapping
Appendix B	Alternatives & Impact Mapping
Appendix C	Project Costs
Appendix D	Project Phasing
Appendix E	VDOT Comments

# **List of Acronyms**

AASHTO - American Association of State Highway and Transportation Officials

ADT - Average Daily Traffic

CAA - Clean Air Act

CADD - Computer-aided Design and Drafting

CBPA – Chesapeake Bay Preservation Act

CIP – Capital Improvement Plan

CRP - Carbon Reduction Program

DCR – Virginia Department of Conservation and Recreation

DEQ - Virginia Department of Environmental Quality

DPR – Prince William County Department of Parks and Recreation

DWR - Virginia Department of Wildlife Resources

EPA - Environmental Protection Agency

ERIS - Environmental Risk Information Services

ERNS - Emergency Response Notification Systems

ESA – Endangered Species Act

FEMA – Federal Emergency Management Agency

FLAP – Federal Lands Access Program

GIS – Geographic Information Systems

IPaC – Information, Planning, and Conservation

LOD – Limits of Disturbance

NAAQS - National Air Ambient Air Quality Standards

NEVI - National Electric Vehicle Infrastructure

NLEB - Northern Long-eared Bat

NPS - National Park Service

NRHP - National Register of Historic Places

NTS - National Trail System

NVTA - Northern Virginia Transportation Authority

NWI – National Wetlands Inventory

PHNST - Potomac Heritage National Scenic Trail

PIR - Priority Investment Rating

RCRA – Resource Conservation and Recovery Act

RPA - Resource Protection Area

RTA - Recreational Trails Program

SQG - Small Quantity Generators

TAP - Transportation Alternatives Program

T & E – Threatened and Endangered

USDA - U.S. Department of Agriculture

USFWS - United States Fish and Wildlife Service

VAFWIS - Virginia Fish and Wildlife Information System

VCRIS – Virginia Cultural Resource Information System

VDHR - Virginia Department of Historic Resources

VDOT – Virginia Department of Transportation

VSQG - Very Small Quantity Generators

WOTUS - Water of the US

WSS - Web Soil Survey

# **Executive Summary**

This study was performed by ATCS Incorporated (ATCS / The Consultant) on behalf of Prince William County Department of Parks and Recreation (DPR). ATCS was contracted by DPR to perform feasibility studies including preliminary engineering and to identify a recommended alternative for the identified Gap Area described in this report. The study included a background section with a purpose and needs, an evaluation of existing conditions in the Gap Study Area, development of three feasible trail alternatives, screening and evaluation of the three alternatives, resulting in a recommendation for a preferred alternative to be advanced for implementation.

This report evaluates Gap Area 2, which is located around the town of Dumfries and includes portions of the town with an easternmost boundary following Duke Street and Batestown Road before crossing under I-95 and following Van Buren Road towards Prince William Forest Park.

The evaluation of the three trail alternatives included all standard factors in an environmental study such as socioeconomic resources, natural resources, hazardous materials, air quality and noise, historic resources, Section 4(f)/6(f) resources, and safety. It also evaluated right-of-way impacts and costs. For the preferred alternative, ATCS developed plan view drawings and planning level cost estimates, by phase, for construction. Additionally, ATCS developed a Phasing Plan for this Gap Area as well as a narrative of Next Steps to move the project(s) forward.

After evaluation, Alternative 2.1 was determined to be the alternative that best meets the Purpose and Needs while balancing costs and impacts. Based on meeting these criteria, Alternative 2.1 is the recommended alternative for Gap Area 2.

The recommended alternative begins at the intersection of Main Street and Duke Street. The alignment follows Duke Street before turning left onto Cameron Street for approximately two-tenths of a mile. The alignment then crosses to the south side of Batestown Road and follows Quantico Creek, crossing under I-95 to intersect Van Buren Road. The alignment then travels along the south side of Van Buren Road before connecting to existing and planned trail alignments within Prince William Forest Park. This route was evaluated for its potential to provide access to Merchant Park, The Weems-Botts Museum, Dumfries Elementary School, and Prince William Forest Park


This recommendation considered constructability, feasibility, and input from the County and the public. The recommended alternative meets the Purpose and Needs by:

- Increasing access and mobility by providing additional travel mode choices and available travel routes to those living in or around Gap Area 2.
- Improving health, safety, and quality of life by providing a dedicated trail separated from traffic and increasing choices for travel and to move throughout the study area.

• Providing economic benefits to the region by providing residents with additional connections and modes of access between the Town, retail centers, and recreation areas.

Overall construction costs are estimated at \$3.5 million for the Gap Area 2 recommended alternative.

#### GAP AREA 2 RECOMMENDED ALTERNATIVE



# 1.0 Introduction, Background, and Purpose

#### 1.1 Introduction

Prince William County's Department of Parks and Recreation (DPR) applied for and received a National Park Service (NPS) Federal Lands Access Program (FLAP) grant for a Potomac Heritage National Scenic Trail (PHNST) gap analysis. The goal of the project is to support NPS's goals of closing gaps in the PHNST network and allowing visitors and residents continuous access and enjoyment of the trail in Prince William County.

Trails are most often considered a recreational resource used for pleasure or exercise. However, trails play a key role in creating a resilient, interconnected, and multimodal transportation system by providing safe, reliable, alternative transportation options to individuals. Crucially, trails provide individuals with a choice in the mode of transportation which best suits their needs for any given trip. Creating and providing accessible transportation options is a key component of a well-developed mobility network and provides healthy alternatives for individuals while also reducing vehicle traffic and associated greenhouse gas emissions.

The Potomac Heritage National Scenic Trail Gap Analysis Feasibility Study analyzes the feasibility of providing a connection in three Gap Areas within Prince William County. This report evaluates Gap Area 2. The Study will identify a planned alignment that provides feasible, safe, and convenient access to bicycle and pedestrian modes of transportation as well as recreational trail opportunities. This new connection




Figure 1 – PHNST Gap Area 2 Study Area

will be beneficial to the physical and mental health of residents and trail visitors alike, while providing recreation and active transportation opportunities in locations where they do not currently exist.

Gap Area 2 shown in *Figure 1* above is located around the town of Dumfries and includes portions of the town with an easternmost boundary following Duke Street and Batestown Road before crossing under I-95 and following Van Buren Road towards Prince William Forest Park.

#### 1.2 Background

#### History

The National Trail System (NTS) was established through the National Trail System Act of 1968. This act aimed to create and protect a network of scenic, historic, and recreational trails across the United States, providing opportunities for outdoor recreation, promoting the enjoyment and appreciation of the nation's scenic, historic, natural, and cultural resources. One of the most significant additions to the NTS is the PHNST. Designated by Congress in 1983 through an amendment to the National Trail System Act, the



PHNST represents a major effort to preserve and celebrate the unique heritage of the Potomac River corridor. Spanning nearly 900 miles (Commission, 2023) of existing and planned trails, the PHNST traverses multiple states in the Potomac River basin, extending from the Laurel Highlands Trail in western Pennsylvania to the mouth of the Potomac River in Virginia. Across its length, the PHNST consists of both paved and unpaved sections, offering varied hiking experiences suited for many different skill levels.



Figure 2 - PHNST Extent

The PHNST winds its way through five physiographic provinces as shown in *Figure 2*, including a diverse range of landscapes and ecosystems. It also passes through the nation's capital, Washington, D.C., and includes 140 miles of trails in Northern Virginia. This extensive trail system is composed of both existing and planned sections, each tracing the natural, historical, and cultural features of the Potomac River corridor. Hikers, cyclists, and outdoor enthusiasts using the PHNST can explore significant sites, such as Civil War battlefields, colonial settlements, and areas of rich natural biodiversity, all while enjoying the scenic beauty of the Potomac River and its surroundings.

Visitors to the PHNST are offered a unique opportunity to traverse the same paths once walked by George Washington, who owned roughly 12,000 acres of land dispersed throughout the Potomac River corridor. The PHNST not only allows for a journey through history but also provides access to a rich tapestry of natural and cultural resources. The Potomac River corridor is a haven for biodiversity, featuring a variety of endangered species and an array of vibrant wildflowers. Along the trail, hikers and nature enthusiasts can enjoy the natural beauty of the area, experiencing areas and ecosystems that have remained largely untouched for centuries.

In addition to its natural resources, the trail is steeped in historical significance. It passes by numerous historic sites that played pivotal roles in the founding of the United States of America. Visitors can explore remnants of early American settlements, colonial-era structures, and landmarks that tell the story of the nation's birth and development. Whether one is a history buff, a nature lover, or simply looking for a picturesque outdoor adventure, the PHNST provides an enriching experience that combines the natural splendor and historical depth of the Potomac River corridor.

#### Social and Economic Benefits

The PHNST provides significant health, social, economic, and transportation benefits to the Northern Virginia region. According to a 2022 study, users of the PHNST in Northern Virginia walk a combined 13.6 million miles and bike a combined 45 million miles each year. These impressive numbers highlight the trail's extensive use and its importance to the community, in those areas where it has been completed. The health benefits of the PHNST are also

#### **Economic Benefits** TRAIL-FACING BUSINESSES Businesses within 1.5 miles of the trail, limited to restaurants and retail establishments related to outdoor activities. \$86.8 million \$3.8 million in total annual generated by 16 revenue generated outdoor retail by 254 trail-facing establishments businesses \$83 million generated by 238 restaurants

Figure 4 - Economic Benefits




Figure 3 - Health Benefits

substantial. The trail is estimated to generate \$404 million in health benefits annually. These benefits include reduced healthcare costs due to increased physical activity, lower rates of chronic diseases, and improved mental health among users who are able to enjoy the natural and recreational aspects of the trail. Economically, the PHNST also plays a vital role in the region, contributing \$86 million in direct economic benefits each year. These benefits stem from increased tourism, local spending at businesses near the trail, and enhanced property values in communities connected by the trail. The trail helps to create jobs and stimulate local economies, demonstrating its value beyond recreational use. From a transportation perspective, the PHNST offers considerable savings. It is estimated to save \$4 million in avoided transportation costs annually. By providing a safe and scenic route for walking and biking, the trail

reduces the reliance on motor vehicles, which in turn lowers traffic congestion, reduces greenhouse gas emissions, and decreases wear and tear on public roadways.

Connecting and completing gaps within the existing PHNST network has the potential to amplify these benefits. Filling gaps could result in \$5.2 million in avoided healthcare costs and \$34.1 million in mortality reduction benefits. These figures underscore the importance of a continuous and accessible trail network for maximizing public health outcomes. In addition to the health and economic benefits, closing gaps in the PHNST network could lead to significant transportation savings. It is estimated that in the Northern Virginia region, 630,000 miles of commuting could be avoided each year. This reduction in commuting miles would not only save individuals time and money but also contribute to environmental sustainability by decreasing the number of vehicles on the road (Northern Virginia Potomac Heritage National Scenic Trail: Health, Social Equity, and Economic Impact Study, 2022).

Overall, the PHNST is an asset to the Northern Virginia region. Its contributions to public health, the economy,

#### **Transportation Benefits**

# Based on data from StreetLight, commuting on the PHNST accounts for: 1.9 million miles of walking annually 4.6 million miles of biking annually 45,000 miles of commuting each year per average mile of trail AVOIDED TRANSPORTATION COSTS \$3.7 million personal vehicle costs avoided \$480,000 environmental costs avoided

Reductions in environmental pollutants:

27 metric tons of CO
1.2 metric tons of NOx
2,500 metric tons of CO2e



Figure 5 - Transportation Benefits

and transportation are substantial, and further investments in connecting and completing the trail network promise even greater returns for the community.

#### Social and Demographic Data Along the Trail Study Areas

The population of Prince William County, Virginia in 2022 was 486,943, increasing 19.9% since 2010 (TIGER/Line Shapefiles, 2024). The county has experienced a significant amount of growth and prosperity over this time; however, there are still communities that are considered disadvantaged. A disadvantaged community is defined as a community which has been denied access to and use of the same tools or resources needed for self-sufficiency. Disadvantaged areas and groups of individuals are identified by the patterns of inequitable access to resources as well as barriers encountered (rather than the fact of race, poverty, or sex). Groups may be considered disadvantaged if they face one or more barriers in access to resources. Considering demographics within a trail system is a critical tool in aiding the reconnection of communities to resources where access is limited (A snapshot of disadvantage in the United States, 2022).

Trail systems like the PHNST in the Northern Virginia region greatly contribute to the health, economy, and transportation in the communities they touch. Closing gaps in the PHNST trail system will enhance disadvantaged communities by providing an alternate and cost-effective mode of transportation that reduces the need for motorized vehicles while promoting exercise and improving health. In return, the communities along the PHNST will have access to use the tools needed for self-sufficiency to achieve an overall better quality of life.

#### **Previous Planning and Studies**

Prince William County has conducted several studies to assess the needs of the existing and planned trail system within the county. The County also understands that parks and recreation facilities are an essential service for residents and that these facilities often serve as an indicator for measuring quality of life. Green spaces and recreational areas offer residents and visitors a place to engage in physical activity, enjoy nature, and participate in community events, all of which contribute to overall well-being and community cohesion.

Closing the gaps in the PHNST trail system within Prince William County will better provide residents and visitors with a unified trail experience. By addressing the gaps in the trail system, the County can enhance connectivity, making it easier and safer for people to traverse the region on foot or by bicycle. Additionally, a unified trail system encourages more consistent usage, additional tourism, and a shared responsibility for maintaining the trail as a valuable public resource.

#### Prince William County 2040 Comprehensive Plan

The County's transportation goals contained within the Mobility Chapter of the 2040 Comprehensive Plan (Prince William County 2040 Comprehensive Plan: Mobility, 2022) are centered around offering a diverse array of public and private transportation options to the region, ensuring that accessibility and affordability are prioritized for all individuals. By reducing reliance on single-occupancy vehicles, the County aims to enhance community connectivity and walkability. Additionally, the County has committed to minimizing environmental impacts and preserving the region's natural environment while



improving transportation infrastructure. Multi-use and recreational trails such as the PHNST help meet these transportation and environmental goals.

The County's environmental goals focus on maximizing the protection and enhancement of the region's open spaces, green spaces, and wildlife preserves (Prince William County 2040 Comprehensive Plan: Environment, 2022). This includes efforts to preserve these areas by providing connections to the vast array of county, state, and federal parks/wildlife refuges located in proximity to the PHNST in Prince William County, including Occoquan Bay Wildlife Refuge, Featherstone Wildlife Refuge, Leesylvania State Park, and Prince William Forest Park (a NPS park). Connecting the gaps in the PHNST will help enhance and promote

walking and bicycling as modes of transportation, making it easier to access county, state, and federal lands and recreational attractions while also providing safe routes to schools in Prince William County. To achieve these objectives, environmental impacts will be key metrics in this analysis, helping to identify alternatives that align with local, state, and federal environmental goals.

The County's economic goals are focused on improving the economic well-being of the community and enhancing the quality of life for residents, including investments in parks and trails. The PHNST represents a multi-state initiative aimed at integrating natural, cultural, economic, and tourism assets to boost the economic resilience of the Potomac River watershed. This project aligns with the County's comprehensive and strategic plan and will foster economic development by generating new opportunities in recreation and tourism (Prince William County 2040 Comprehensive Plan, 2022).

#### Prince William County 2040 Mobility Chapter

A primary goal of the Mobility Chapter, contained in the 2040 Comprehensive Plan, is to provide an accessible, safe, and comprehensive multimodal transportation network that allows for the safe and efficient movement of goods and people throughout the county and into neighboring areas (Prince William County 2040 Comprehensive Plan: Mobility, 2022). The Mobility Chapter recognizes that current infrastructure will need to adapt and expand to meet the increasing demands of a growing population through policies that support a safe, equitable, and connected mobility network.



The County acknowledges the importance of offering diverse transportation options to help residents fulfill their residential, recreational, commercial, and work-related travel needs. This means adapting to changing mobility trends, improving multimodal options, increasing the use of public transit, and increasing travel time reliability. Additionally, the Mobility Chapter emphasizes the need for sustainable and environmentally friendly transportation solutions to reduce greenhouse gases and promote a healthier environment.

Focusing population, jobs, and infrastructure within walkable and bikeable communities throughout the county will help reduce roadway congestion and manage future demand by reducing the reliance on automobiles. Integrating connections and expanding the county's recreational trail network also fosters healthier communities, enhances cross-county connectivity, provides commuter transportation alternatives, and boosts economic growth through tourism.

#### Prince William County 2040 Countywide Trails Plan

As part of the Mobility Chapter, the County adopted a Countywide Trails Map (Countywide Trails Plan, 2022) that identifies an interconnected network of recreational and active transportation trails, which the County intends to serve as the backbone for a countywide trail network. Development of an interconnected, multimodal, countywide active mobility and trail network requires substantial investment and careful

planning. Coordination among local governments, developers, and community stakeholders will help ensure the seamless integration of various transportation modes. High priority should be given to trails identified on the Countywide Trails Map when reviewing land development applications and allocating funding sources such as development proffers, grants, and bonds. Proper prioritization will expedite the establishment of these trails.

The Mobility Chapter recommends that all communities within the county work to incorporate appropriate pedestrian connections, including sidewalks, paths, and recreational trails. These connections will enable residents to easily access the countywide trail network from their homes. Implementing this infrastructure will not only enhance connectivity but also promote healthier lifestyles by encouraging additional walking and



cycling. Moreover, it will improve access to recreational areas, public transit, and places of employment, all while reducing reliance on automobiles. This decrease in vehicle dependency will help alleviate traffic congestion, reduce environmental impacts, and create a more sustainable and livable community for all residents.

Trails, like the PHNST, align with the goals of the Mobility Chapter by providing a safe, reliable, and interconnected multimodal network that enables residents to choose the mode of transportation that best suits their needs ranging from exercise, access to transit, or commuting to work or school. In addition, trails like the PHNST give residents a healthy alternative to reach their destination while reducing vehicle traffic as well as greenhouse gas emissions. Addressing the gaps along the PHNST will provide access to safe bicycle and pedestrian transportation pathways as well as recreational opportunities that are beneficial to physical and mental health. Connecting the current gaps in the trail will also bring these features to communities where similar recreation opportunities do not currently exist.

#### 2019 Prince William County Parks and Recreation Needs Assessment Survey

In 2019, Prince William County Department of Parks and Recreation conducted a Community Needs Assessment Survey (Recreation, 2019). The results from the survey, shown in *Figure 6* below, found that 105,676 out of total 145,961 (72%) households had a need for walking and biking trails. In addition, 43% of households responded that walking and biking trails were the most important recreational facilities within the county. This percentage was almost double that of the next highest rated facility (natural wildlife habitats (22%)). Walking and biking trails received a Priority Investment Rating of 200.0 based on the survey results. The Priority Investment Rating (PIR) identifies the facilities and programs residents think should receive the highest priority for investment. A rating of 100 or above indicated a relatively high level of unmet needs and that residents find it important to fund improvements to these areas. In return, improvements to areas with a high PIR will likely have a positive impact on the greatest number of households.




Figure 6 - Priority Investment Rating

#### 1.3 Purpose and Needs

#### Purpose

The purpose of this Feasibility Study is to examine potential routes for the PHNST through Gap Area 2, and to directly address provision of service and trail access to underserved communities in the County. As stated previously, providing connections within gap areas will allow access to underserved communities, provide safe and convenient access for cyclists and pedestrians, and provide recreational opportunities to improve physical and mental health where these opportunities do not currently exist. Completing these gaps will bring the overall completion of the PHNST closer to fruition, after which the County and its residents will be able to partake in the social and economic benefits of a contiguous National Scenic Trail.

#### Needs

The gaps within the existing PHNST corridor present challenges for residents and visitors attempting to use the trail for either transportation or recreation. These gaps prevent residents from using the trail as an access point to destinations and prevent visitors from having a unified and safe trail experience. Providing connections between these trail gaps will help meet the needs described below.

#### Access and Mobility

Trails are an essential piece of the County's existing and planned transportation network and contribute to the County's goal of providing an interconnected, multimodal countywide active mobility and trail network. As discussed in *Section 1.2*, trails provide safe, reliable, and interconnected transportation alternatives to residents and visitors throughout the county. They provide alternative methods of transportation which allow individuals to choose the most appropriate method of transportation based on their needs.

Providing connections between existing sections of the PHNST will increase county residents' ability to utilize the PHNST as a mode of transportation to access areas throughout the county which were previously only accessible via automobile. These connections will provide the freedom for residents to choose the mode of transportation which best suits their daily needs and will increase the resilience of the transportation network by eliminating vehicle trips from local roadways. Providing trail access for residents not only provides a choice in the method of transportation individuals use, but it can also provide residents in traditionally underserved areas with access to goods and services that were otherwise out of reach.

#### Health, Safety and Quality of Life

Physical activity such as biking and walking can significantly enhance both the physical and mental well-being of individuals. Those who incorporate biking or walking into their daily routines are less prone to health issues such as diabetes, obesity, and hypertension. These physical activities help improve cardiovascular health, strengthen muscles, and boost overall fitness levels. Additionally, engaging in activities like walking or biking can reduce stress, anxiety, and depression by promoting the release of endorphins, which are natural mood lifters.

Furthermore, an active lifestyle fosters a sense of community and social interaction. People who walk or bike regularly are more likely to connect with their neighbors, creating a supportive social network that

enhances their sense of belonging and emotional well-being. This community engagement can lead to increased motivation to maintain an active lifestyle, creating a positive feedback loop of health and social benefits.

The cumulative health benefits of an active population also help alleviate the burden on the local healthcare system. With fewer individuals suffering from chronic illnesses, there is less demand for medical services, leading to reduced healthcare costs and expenses. Preventative health measures, such as promoting physical activity, are cost-effective strategies that benefit both individuals and society. By encouraging active lifestyles, communities can foster healthier, happier populations and create more sustainable and economically viable healthcare systems.

Safety is also a key component of the County's vision for developing a comprehensive and well-connected mobility network. Addressing the gaps in the PHNST is critical to achieving this goal. By closing these gaps, the County will create a cohesive trail experience, ensuring that users can traverse these trail sections without interruption. Furthermore, closing these gaps will significantly enhance safety for trail users. Currently, visitors face relatively dangerous situations when navigating sections of the trail that require crossing heavily trafficked roads with no dedicated pedestrian or bicycle infrastructure. These crossings pose risks and diminish the overall experience for users. Closing the trail gaps will allow users to be able to follow a continuous, well-designed route that minimizes exposure to traffic hazards. This improvement will not only promote safety but also encourage more people to use the trail, ultimately supporting the County's broader goals of fostering active transportation and recreational opportunities. Combined, the health and safety benefits of the trail will provide overall improvements to the quality of life for residents and visitors alike.

#### **Economic Benefits**

A robust interconnected trail system offers numerous economic benefits. Local businesses along the trail see increased foot traffic and revenue, while employees enjoy convenient transportation options. Additionally, neighborhoods with trail access often experience higher property values due to the recreational and lifestyle advantages provided by trails.

Completing gaps in the PHNST will enhance its appeal as a destination trail, attracting more tourists who will spend on lodging, dining, and other services, thereby boosting local revenue. Events like marathons and cycling races hosted on these trails also contribute to economic growth. Moreover, using the trail for commuting can lead to significant fuel cost savings for individuals, reducing the economic burden of vehicle maintenance and contributing to a more sustainable transportation system (Stafford County Virginia, 2019).

Addressing the trail gaps will also decrease reliance on automobiles which can create significant savings for individual households and the local jurisdiction through reduced road improvements and maintenance needs.

# 2.0 Stakeholder Coordination

Involvement of Gap Area Partners is an important aspect of this feasibility study. Stakeholders included trail users, trail advocates, and others who have important knowledge to include in the feasibility study. Groups involved in the stakeholder meetings included: PWC Trails and Blueways Council, Northern Virginia Regional Commission, Greater Prince William Trails Coalition, the National Park Service, the Town of Dumfries, and representatives from local homeowner's associations and the development community. The County Government was also represented by staff from the Department of Parks and Recreation, Office of Transportation, and Office of Planning. Two rounds of stakeholder meetings were held during the course of the study. The first round was held in September 2024 as the existing conditions phase of the study neared completion, and the second round was held in February 2025 to review the evaluated alternatives and the recommended alternative.

#### 2.1 Stakeholder Meetings - Round 1

The first stakeholder meeting was held on September 25, 2024, at the offices of the Prince William County Department of Parks and Recreation. A virtual option was also provided for those attendees who were unable to join in person. Following a presentation from the project team, discussion was held to solicit feedback from those in attendance. Overall, the meeting attendees expressed a desire to align with the Town's Main Street Plan, incorporate historic aspects of the Town, and connect the PHNST to the East Coast Greenway along Richmond Highway.

A follow-up meeting for Governmental representatives was held virtually on October 31, 2024. The purpose of this meeting was to allow key Government stakeholders to provide additional input and was also an alternate date for those unable to attend the September 25<sup>th</sup> stakeholder meeting. The discussion focused on the status of the Town of Dumfries' Comprehensive Plan Update and point of access to Prince William Forest Park from Van Buren Road, south of Batestown Road.

# 2.2 Stakeholder Meetings – Round 2

A second round of stakeholder meetings was held in February 2025. During these meetings, the consultant presented the work completed including: the existing conditions analyses, development of alternatives, screening of alternatives, evaluation of the screened alternatives, and the recommended alternative.

The second stakeholder meeting for Gap Area 2 was held on February 20, 2025, and was held solely as a virtual meeting due to inclement weather. The consultant presented the three alternative alignments for the Gap Area, as described in *Chapter 4.0*, and the screening process to determine which alternatives had been advanced for further evaluation, described in *Chapter 5.0*.

Attendees asked several questions about Gap Area 2 related to the right-of-way needed and about the screening of the alternative along Quantico Creek. However, there was general acceptance of the recommended alternative.

**-** 11

# 3.0 Evaluation of Existing Conditions and Potential **Environmental Consequences**

Existing Conditions Analysis was performed utilizing field and desktop review across a variety of environmental resources, demographic factors, and elements of the built environment within Gap Area 2. During field visits, photos, video, and extensive notes were taken detailing the observed resources. The desktop review utilized socioeconomic data, environmental data, previous studies performed within the Gap Area, traffic analysis, and analysis of aerial imagery. This combined approach ensured a thorough understanding of the current conditions, forming a solid foundation for future planning and decisionmaking.

The Existing Conditions Analysis provided the study team with essential information to identify constraints and potential issues within the Gap Area. Many of the resources described below are shown on the existing conditions mapping located in Appendix A. General details about each evaluated resource are provided below. Additional supporting documentation and analysis associated with the individual resource evaluations was prepared by ATCS, as part of this study. This supporting documentation and analysis has been provided to DPR as a separate data file and is not included as an appendix to this report due to size.

#### 3.1 Traffic Data and Crossings

GIS Data, VDOT Traffic Data, aerial imagery, and field review were used to analyze traffic volumes, safety issues, and crossings of concern within the Gap Area. The results for each of the conditions analyzed are presented below.

#### 3.1.1 Traffic Volumes

Traffic volumes were documented with the objective of placing the trail along roads with lower volumes of traffic when possible. Within Gap Area 2, the highest traffic volumes were identified on Main Street with an Average Daily Traffic (ADT) volume of 5,800 vehicles.

#### 3.1.2 Crossings

Major crossings were documented with the objective of avoiding these crossings when possible. One major roadway crossing was identified along Batestown Road south of the intersection with Richmond Highway. Should a trail be proposed in this location, it would likely need to cross to the south side of the road around a curve where Batestown Road continues to the west. Additionally, Batestown Road does not have existing sidewalks or crossings except near the corner with Cameron Street.

#### 3.1.3 Safety Issues Identified

To identify potential safety issues, crash data was sourced from the Virginia Department of Transportation (VDOT) Full Crash Layer published on ArcGIS Online. This data layer shows crashes since 2016. When considering crashes for multimodal projects, it is important to identify conflict points which have the

potential to cause increased pedestrian or bicycle crashes following construction. No high-density crash locations were identified within the Gap Area. The only hotspot identified was associated with crashes on I-95, which does not intersect with the potential trail alignment "at grade" and therefore does not present a potential safety issue. Additionally, one bicycle and pedestrian crash was identified near Batestown Road on Main Street.

#### 3.2 Trails and Connections

Prince William County has a robust trail network and as such, there are several existing trails that traverse the Gap Area. Closing gaps within the existing PHNST network will not only help unify the PHNST experience, but it will also allow for increased mobility throughout the regional trail system by increasing connectivity between existing trails.

Gap Area 2 does not include any existing trails. However, connecting the PHNST through this area would provide access to the Town of Dumfries to the east and Prince William Forest Park to the west where visitors would have access to the amenities of this NPS Park including hiking/biking trails, fishing, outdoors courses, and camping facilities. Providing trail access through the Town of Dumfries would allow residents and visitors to access public facilities such as The Weems-Botts Museum, the Williams Ordinary site, and Merchant Park. The trail would also potentially provide a safe route for students to access Dumfries Elementary School.



#### 3.3 Major Destinations, Attractions, and Military Facilities

Evaluation was performed to determine which existing amenities and services would be potential destinations and attractions for residents and visitors to the expanded and connected PHNST. Gap Area 2 is located near the Town of Dumfries and a trail connection in this location would provide access to Prince William Forest Park as well as amenities within the Town including the Weems-Botts Museum, the Williams Ordinary Site, and Dumfries Elementary School.



#### 3.4 Utilities

Above-ground utilities, including utility poles, overhead power lines, and communication infrastructure, were assessed through aerial imagery, Geographic Information Systems (GIS) data, and on-site inspections to ensure accuracy. For underground utilities, identification was limited to visible surface features such as stormwater drains, manhole covers, and other utility access points, as subsurface utility investigations were not conducted at this stage.

All identified utilities were documented and incorporated into base mapping to facilitate integration into the proposed trail alignments. This process ensured that potential conflicts with existing infrastructure were identified early in the planning phase, allowing for necessary adjustments to minimize disruptions and maintain safety standards. Additional coordination with utility providers will be performed during subsequent project phases to obtain detailed subsurface utility information and confirm the precise locations of underground infrastructure.



#### 3.5 Topography

potential trail and is discussed in Chapter 6.0.

Topography across the Gap Area varies significantly and ranges from 4 feet to 118 feet above sea level. There are several low areas which include streams, wetlands, and floodplains which will need to be avoided to minimize impacts to these resources. The most direct path with the fewest topographic obstacles between the eastern and western ends of this Gap Area would likely follow Batestown Road and cross under I-95 towards Prince William Forest Park. Additional analysis was performed during the design and alignment phase of this study to determine feasible locations for the



#### 3.6 **Environmental Resources**

Potential impacts and consequences to environmental resources were evaluated as part of this feasibility study. The resources described below include many of those that would be evaluated within a federal environmental document or final design evaluation. The impacts described are estimates to be used for planning purposes should the study be carried forward to additional phases of design or study. Individual resources were evaluated using a combination of aerial photography, desktop analysis, and database review. Additionally, Geographic Information Systems (GIS) data from Prince William County and other publicly available data sources were used to perform estimated impact analyses.

#### 3.6.1 Socioeconomic Resources

#### Community Facilities

Community facilities including schools, libraries, parks and recreation areas, community centers, police, fire and rescue services, hospitals, places of worship, and cemeteries were identified using data from the Prince William County GIS Data Portal, aerial photography, and field review. Analysis identified one school which was taken into consideration when determining potential trail alignments and efforts were made to provide connections to these facilities to increase connectivity and provide easy access to residents within the Gap Area.

#### Land Use, Parcels, and Available Right of Way

A detailed survey was not performed as part of this feasibility study. Instead, parcel data from the Prince William County GIS Data Portal was utilized to identify existing parcels and right-of-way. While the data is useful for high-level evaluation of right-of-way needs for the project, the estimates given in subsequent sections of this report are subject to change based on an official survey which will be carried out as part of future phases of design or study.

#### Open-Space Easements

The Gap Area was evaluated for existing open-space easements utilizing data from Prince William County GIS Data Portal. No easements were identified within the Gap Area.

#### Significant State and Federal Lands

Significant State and Federal Lands located within the Gap Area were evaluated using data from Prince William County's GIS Data Portal, aerial photography, and field review. Following review, Prince William Forest Park was identified within the Gap Area. Particular attention will be given to this resource as potential trail alignments are developed. Additionally, the team worked to avoid and minimize any impacts, while also evaluating potential logical connections to these facilities

#### Environmental Justice Populations

Evaluation of environmental justice populations was not performed as part of this study. Due to the implementation of Executive Order 13990 in February of 2025, environmental justice is no longer to be considered as part of Federal decision-making for environmental evaluation and documentation. Should Federal guidance change in the future, environmental justice may need to be evaluated as part of the next phases of this project.

#### Soils & Farmland of Statewide Importance

The U.S. Department of Agriculture's (USDA) Web Soil Survey (WSS) Tool was utilized to evaluate soil type and the presence or absence of Farmlands of Statewide Importance. Much of the Gap Area is heavily developed but does still maintain some areas of undeveloped land. However, the potential for impacts to these resources is minimal.

#### 3.6.2 Natural Resources

#### Wetlands and Streams

Desktop review was used to evaluate the Gap Area for potential wetlands and streams that could be impacted by the proposed trail project. Available aerial imagery, GIS data, and National Wetlands Inventory (NWI) data were utilized to identify potential wetlands and streams. Zero acres of wetlands and approximately 13,670 linear feet of streams were identified within the Gap Area boundaries.

These totals are estimates and will be confirmed via field review during the preliminary engineering and final design phases of the project to determine more precise totals and the appropriate amount and type of mitigation required should impacts to these resources occur.

#### Floodplains

A review of the Federal Emergency Management Agency's (FEMA) online floodplain database shows that portions of the Gap Area are located within FEMA identified floodplains (FEMA FIRM Numbers 51153C and 51179C). Floodplains located within the Gap Area are classified as AE, and X and include floodways associated with Quantico Creek and its tributaries. Proper planning and design considerations will need to be implemented during development to ensure that the proposed alignments will not permanently increase downstream flooding and that any temporary impacts during construction will be handled in accordance with all necessary floodplain/floodway regulations

#### Resource Protection Areas

Waterways within Prince William County feed the Potomac River which drains into the Chesapeake Bay. Prince William County adopted the Chesapeake Bay Preservation Act (CBPA) into its local ordinances. Part of this ordinance requires Resource Protection Areas (RPA) to be established along all streams within the county. RPAs are defined by Prince William County as, "... the land area within 100 feet of a perennial stream

bank or edge of wetlands adjacent to the perennial stream. RPA areas are protected under state law and local ordinances. In general, no development, land disturbance, or vegetation removal is allowed in an RPA, although water access paths (boardwalk trails) may be permitted as long as the boardwalk does not cause erosion.

A desktop review was performed to evaluate the Gap Area for potential RPAs that had the potential to be impacted by the proposed trail project. To perform this analysis, Prince William County's RPA GIS Data as well as available aerial imagery was utilized. The analysis identified 18.7 acres of RPAs within the Gap Area. Proper planning and design considerations for any boardwalk trail segments will need to comply with RPA regulations.

#### State and Federally Listed Threatened and Endangered Species

A desktop review was performed to identify possible State and Federally threatened and endangered (T & E) species and critical habitat present within the vicinity of the Gap Area. The Virginia Department of Wildlife Resources (DWR), Virginia Fish and Wildlife Information Service (VAFWIS), and the Virginia Department of Conservation and Recreation (DCR), and the United States Fish and Wildlife Service (USFWS) online Information, Planning, and Conservation (IPaC) databases were searched looking for species with confirmed or potential occurrences within the Gap Area.

Preliminary database reviews of State listed species returned several species known to occur within the immediate Project Area, or within a 2-mile buffer surrounding the Project Area. A review of Federally listed species and designated critical habitat, including Bald Eagles, was completed and returned several endangered species within the immediate project area. As the project progresses, additional coordination with DWR, DCR, and USFWS will be necessary to determine whether the project will impact any of the identified species, and determine whether time-of-year restrictions, species surveys or other species restrictions will be required.

#### 3.6.3 Hazardous Materials

A hazardous materials search was performed using multiple databases to obtain information on potentially contaminated areas, including areas with hazardous materials. The Virginia Department of Environmental Quality (DEQ) recommends searching multiple databases to obtain information on potentially contaminated areas, including areas with hazardous materials. A third party, Environmental Risk Information Services (ERIS) was utilized to perform a database review of the proposed Gap Area.

The database review revealed a total of 12 potentially contaminated sites. The sites identified included but were not limited to Resource Conservation and Recovery Act (RCRA) Small Quantity Generators (SQG), RCRA Very Small Quantity Generators (VSQG), RCRA Non-generators (Non GEN), Emergency Response Notification System (ERNS), LST, UST, AST, INST, and VRP sites. This evaluation is preliminary and does not replace the need for a Phase I Site Analysis later during project development. Proper planning and consideration will be taken to avoid any of the listed sites during the construction phase of the project.

#### 3.6.4 Air Quality

The proposed improvements were assessed for potential air quality impacts and compliance with applicable air quality regulations and requirements defined under Clear Air Act (CAA) 42 USC §7401 et seq. and EPA's 40 CFR § 93.114 and § 93.115. The assessment indicates that the project will not cause or contribute to a new violation, increase the frequency or severity of any violation, or delay timely attainment of the National Air Ambient Air Quality Standards (NAAQS) established by the Environmental Protection Agency (EPA) as the project does not involve the construction of transportation facilities with the potential to increase the number of vehicles within the Gap Area.

#### 3.6.5 Noise

Evaluation of the Gap Area, potential project alignments, and the project scope resulted in the determination that this project does not qualify as a Type I Project per 23 CFR §772.5 and the VDOT noise manual for purposes of a noise analysis. Therefore, the project was not evaluated for potential noise impacts.

#### 3.6.6 Historic Resources

A desktop review utilizing The Virginia Department of Historic Resources (VDHR) archives database, Virginia Cultural Resource Information System (VCRIS) was conducted to identify possible architectural or archeological resources and cemeteries within the vicinity of the Gap Area. As discussed below, several resources were identified within the study area and were taken into account when developing potential alignments.

#### Architectural Resources

The VCRIS search results identified six architecture resources, two of which were determined to be listed in the National Register of Historic Places (NRHP) or eligible for the listing in the NRHP.

#### Archaeological Resources

The VCRIS search results identified nine archeological resources, of which two have been determined to be eligible for the listing in the NRHP.

#### Cemeteries

One cemetery was identified within the Gap Area, the Dumfries Church and Public Cemetery (DHR IDs 212-0008 and 44PW0001) in the Town of Dumfries. The Dumfries Church and Public Cemetery is located north of the overpass of I-95 along Batestown Road, and according to VDHR's VCRIS Database, has not been evaluated for eligibility or listing within the NRHP. Due to the unevaluated status of the Dumfries Church and Public Cemetery, it's unclear at this time whether impacting this property would constitute a Section 4(f) "use". However, particular attention will need to be paid during future development of the trail alignment to avoid and minimize impacts in both areas.

#### 3.6.7 Parks and Recreational Facilities

Parks and Recreational Facilities were identified using a combination of data from the Prince William County GIS Data Portal, aerial imagery, field review, and coordination with Prince William County Staff. Two

resources were identified comprising two parks (Merchants Park and Prince William Forest Park). There was an identified preference for alignment options that created an opportunity for the PHNST to connect to and/or pass through a County or local park. As such, these facilities were taken into consideration during alternative development.

#### 3.6.8 Visual Quality

The presence and use of trails can alter the landscape in ways that are visible and noticeable to people, at times detracting from the natural or aesthetic qualities of an area. Visual impacts will be considered during the final design of the trail, including construction elements, maintenance plans, and cultural and aesthetic elements. At this stage of the project, when evaluating potential alignments, consideration was given to alignment locations that provided improved visual quality to trail users.

#### 3.6.9 Section 4(f) and 6(f) Resources

The Gap Area was evaluated to determine the presence of potential Section 4(f) and 6(f) Resources in accordance with the U.S. Department of Transportation Act of 1966 which provided for consideration of park and recreation lands, wildlife and waterfowl refuges, and historic sites during project development. Based on a review of available mapping databases, there are currently no planned acquisitions of property under the protection of Section 6(f), other unique areas, or special lands. However, Prince William Forest Park has a number of Land and Water Conservation Funded sites which would fall under the protection of Section 6(f). Additionally, as discussed in *Section 3.6.6*; there are a number of historic resources scattered throughout the Gap Area which could be considered Section 4(f) resources. Special consideration will need to be given during preliminary and final design to avoid and minimize impacts to any Section 4(f) or 6(f) resources. Should impacts to these resources be unavoidable, formal coordination will need to occur between VDHR, NPS, the County, and any other formal stakeholders to determine if there is an official resource "use".

# **4.0 Proposed Alternatives**

This section describes the proposed alternatives developed for Gap Area 2 as part of this feasibility study. Alignment alternatives generally follow design criteria and guidance laid out in the American Association of State Highway and Transportation Officials (AASHTO) Guide for the Development of Bicycle Facilities (American Association of State Highway and Transportation Officials, 2012). A total of three preliminary alternatives were developed based on the Purpose and Needs, stakeholder feedback, and identified existing conditions. The proposed alignment base mapping is included in *Appendix B*. Additionally, Computer-aided Design and Drafting (CADD) Plan Sheets have been developed to show a greater level of engineering detail and are also included in *Appendix B*. These Plan Sheets are preliminary in nature. Additional engineering evaluations will need to be performed during future studies and trail development.

#### 4.1 Gap Area 2 Alternative Concepts

#### Alternative 2.1



Figure 7 - Alternative 2.1 Alignment

The proposed alignment of evaluated Alternative 2.1 begins at the intersection of Main Street and Duke Street. The alignment follows Duke Street before turning left onto Cameron Street for approximately two-tenths of a mile. The alignment then crosses to the south side of Batestown Road and follows Quantico Creek, crossing under I-95 to intersect Van Buren Road. The alignment then travels along the south side of Van Buren Road before connecting to existing and planned trail alignments within Prince William Forest Park. This route was evaluated for its potential to provide access to Merchant Park, The Weems-Botts Museum, Dumfries Elementary School, and Prince William Forest Park

#### Alternative 2.2



Figure 8 - Alternative 2.2 Alignment

The proposed alignment of evaluated Alternative 2.2 begins at the intersection of Main Street and Duke Street. The alignment follows Main Street to the south before continuing west onto Batestown Road. The alignment continues along the north side of Batestown Road to Cameron Street, before crossing to the south side of Batestown Road and following Quantico Creek, crossing under I-95 to intersect Van Buren Road. The alignment then travels along the south side of Van Buren Road before connecting to existing and planned trail alignments within Prince William Forest Park. This route was evaluated because it offers the most direct connection between Main Street and Prince William Forest Park.

#### Alternative 2.3




Figure 9 - Alternative 2.3 Alignment

The proposed alignment of evaluated Alternative 2.3 begins at the intersection of Main Street and Duke Street. The alignment follows Main Street to the south until it reaches Quantico Creek. From this point, the alignment follows along the south side of Quantico Creek until it crosses under I-95 to intersect Van Buren Road. The alignment then travels along the south side of Van Buren Road before connecting to existing and planned trail alignments within Prince William Forest Park. This route was evaluated based on stakeholder feedback and preference for the trail to follow open space/greenway corridors and incorporating more scenic opportunities where possible.

# **5.0 Alternatives Screening and Evaluation**

#### 5.1 Screening and Evaluation

As an initial screening tool the three alternatives presented in *Chapter 4.0*, were evaluated by how well each met the need elements identified in *Section 1.3 (Purpose and Needs)*. Potential environmental consequences associated with each alternative as well as Stakeholder and public input were also considered as part of the alternative evaluation process, with a trail wide enough for pedestrians and cyclists being a top priority.

#### Access and Mobility

As discussed in *Section 1.3*, providing connections between existing sections of the PHNST will increase county residents' ability to utilize the PHNST as a mode of transportation to access areas throughout the county which were previously only accessible via automobile. These connections will provide the freedom for residents to choose the mode of transportation which suits their daily needs best and will increase the resilience of the transportation network by eliminating vehicle trips from roadways. Providing trail access for residents not only provides a choice in the method of transportation individuals use, but it can also provide residents in traditionally underserved areas with access to goods and services that were otherwise out of reach. Creating active mobility connections where residents are able to use trails for commuting purposes is also a priority in the County's Comprehensive Plan.

Each of the three proposed alternative alignments was evaluated for its ability to meet the needs identified and described above. It was determined that the following alternative did not meet this need:

- Proposed *Alternative 2.2* did not meet this need because it does not provide access to resources within the Town of Dumfries.
- Proposed *Alternative 2.3* did not meet this need because it does not provide access to resources within the Town of Dumfries.

#### Health, Safety, and Quality of Life

The cumulative health benefits of an active population also help alleviate the burden on the local healthcare system. With fewer individuals suffering from chronic illnesses, there is less demand for medical services, leading to reduced healthcare costs and expenses. Preventative health measures, such as promoting physical activity, are cost-effective strategies that benefit both individuals and society. By encouraging active lifestyles, communities can foster healthier, happier populations and create more sustainable and economically viable healthcare systems.

Safety is also a key component of Prince William County's vision for developing a comprehensive and well-connected mobility network. Addressing the gaps in the PHNST is critical to achieving this goal. By closing these gaps, the County will create a cohesive trail experience, ensuring that users can traverse these trail

sections without interruption. Furthermore, closing these gaps will significantly enhance safety for trail users. Currently, visitors face relatively dangerous situations when navigating sections of the trail that require crossing heavily trafficked roads with no dedicated pedestrian or bicycle infrastructure. These crossings pose risks and diminish the overall experience for users. Instead, users will be able to follow a continuous, well-designed route that minimizes exposure to traffic hazards. This improvement not only promotes safety but also encourages more people to use the trail, ultimately supporting the County's broader goals of fostering active transportation and recreational opportunities. Combined, the health and safety benefits of the trail will provide overall improvements to the quality of life for residents and visitors alike.

Each of the three proposed alternative alignments was evaluated for its ability to meet the need identified and described above. It was determined that the following alternative did not meet this need:

- Proposed *Alternative 2.2* did not meet this need due to its alignment following Batestown Road south of the Town. The curve in Batestown Road south of the Town poses safety risks to trail users. While this area can be designed to meet current standards, it would create a potentially hazardous location for motorists and trail users with the trail being located along the inside of a blind curve.
- Proposed *Alternative 2.3* did not meet this need because it is located within a FEMA designated floodplain which runs along Quantico Creek. This area has the potential to rapidly flood during storm events, creating a hazardous environment for trail users.

#### **Economic Benefits**

Completing gaps in the PHNST will enhance its appeal as a destination trail, attracting more tourists who spend on lodging, dining, and other services, thereby boosting local revenue. Events like marathons and cycling races hosted on these trails also contribute to economic growth. Moreover, using the trail for commuting can lead to significant fuel cost savings for individuals, reducing the economic burden of vehicle maintenance and contributing to a more sustainable transportation system (Stafford County Virginia, 2019). Addressing the trail gaps will also decrease reliance on automobiles which can be a significant savings to individual households as well as communities overall through reduced road improvements and maintenance needs.

Each of the three proposed alternative alignments was evaluated for its ability to meet the need identified and described above. It was determined that the following alternative did not meet this need:

- Proposed *Alternative 2.2* did not meet this need due to the alignment bypassing resources in the Town of Dumfries.
- Proposed *Alternative 2.3* did not meet this need due to the alignment bypassing resources in the Town of Dumfries

### 5.2 Screening Summary

*Table 1* below provides an overview of the screening evaluation for each alternative. Based on this analysis, one alternative was recommended to be carried forward for detailed evaluation.

Table 1 - Ability of Proposed Alternatives to Meeting Purpose and Need Elements

Gap Area	Alternative	Provides Access and Mobility	Increases Health, Safety, and Quality of Life	Provides Economic Benefits
	2.1	Yes	Yes	Yes
2	2.2	No	No	No
	2.3	No	No	No

# **6.0 Retained Alternatives and Impact Evaluation**

Based on the screening evaluation and analysis of the concepts, one alternative (Alternative 2.1) was recommended to be carried forward and receive detailed evaluation. Descriptions of the retained alternative can be found in *Section 4.1*.

The following chapter presents summaries of potential impacts of the retained alternative within the Gap Area. This chapter also presents information on potential minimization and mitigation measures for unavoidable impacts, where applicable. The discussion in this chapter is limited to the data, information, and issues that would have an impact on the identification of a recommended alternative for the Gap Area.

In coordination with the Prince William County Department of Parks and Recreation, it was determined that the proposed designs should account for a 10-foot-wide shared-used-path. From this design, a limit of disturbance (LOD) was created in order to account for impacts associated with the proposed designs. An illustrative planning-level limit of disturbance (LOD) was developed for each alternative and is shown in *Appendix B*. The LODs are based on planning-level engineering, which accommodates potential short-term and permanent impacts, and construction access and will be further refined during final design. The LODs for this Study also include a buffer area that is 15 feet beyond the limits of construction for a total width of 40 feet. The impacts quantified and described in this chapter are anticipated to be a worst-case scenario and impacts may be minimized during future design phases of the project. Refinement of the LODs will occur during future design and development.

# 6.1 Gap Area 2 Retained Alternatives Impact Evaluation

A summary of the impacts for Gap Area 2 is shown in *Table 2* below.

Table 2 - Gap Area 2 Retained Alternatives Impact Summary

Resource Category	Resource	Alternative 2.1
	Community Facility Relocations	0
	Community Facilities (acres)	0
	Dumfries Elementary School	0.56
	Residential Property Relocations	0
	Commercial/Business Relocations	0
Casia and namina	Right-of-Way Impacts (/acres)	19 (3.03)
Socioeconomics	Residential	0
	Commercial	0
	Industrial	0
	Agricultural	0.40
	Municipal / Governmental	1.17
	Mixed Use	1.46
	Northern Long-eared Bat	Potential Habitat
	(Myotis septentrionalis)	Present
	Tri-colored Bat	Potential Habitat
	(Perimyotis subflavus)	Present
Natural Resources	Wood Turtle	Potential Habitat
Natural Resources	(Glyptemys insculpta)	Present
	Wetlands (acres)	0
	Streams (linear feet)	1,421
	Floodplains (acres)	9.33
	RPAs (Acres)	2.31
Hazardous Materials	Hazardous Materials Sites	3
	Historic Architectural Properties	2
Historic and Section 4(f) / 6(f)	Historic Archaeological Properties	0
Resources	Section 4(f) Properties	0
	Section 6(f) Properties	1
Safety	Major Road Crossings	1

#### 6.1.1 Socioeconomic Resources

This section describes the potential environmental consequences for the following socioeconomic resources: community facilities, land use, and environmental justice.

#### Community Facilities

Alternative 2.1 potentially impacts one community facility, the Dumfries Elementary School, located in the Town of Dumfries. Impacts associated with this alignment would be minimal and would likely involve modifications to the existing sidewalk in front of the school. No additional school property is proposed to be impacted by this alignment. The impacts would not affect access to or use of the facility and overall, the alternative is expected to improve access to the school and Town by providing the option for additional modes of transportation and creating new access points throughout the study area.

#### Land Use

Approximately 3.03 acres of land required for implementation of Alternative 2.1 are on land zoned for agricultural, municipal / governmental, and mixed-use land uses. The largest amount of the total, approximately 48 percent, is on land zoned for mixed use. The next largest amount, approximately 38 percent, is on land zoned for municipal/governmental uses, followed by agricultural uses at 14 percent.

Trail construction has the potential to reduce the time and cost of travel in the area, thereby enhancing the attractiveness of properties on surrounding and nearby land. However, the contribution of Alternative 2.1 to cumulative land use change is expected to be minor, as land on the proposed trail alignment is already heavily developed or consists of protected land uses.

#### 6.1.2 Natural Resources

This section describes the potential environmental consequences for the following natural resources: threatened, endangered, and special status species and Waters of the US (WOTUS) including Streams, Wetlands, Floodplains, and Resource Protection Areas (RPAs).

#### Threatened, Endangered, and Special Status Species

Based upon a query of agency databases, a total of 15 Federally or State listed threatened or endangered listed species were identified for evaluation as having the potential to occur within the Study Area

Evaluation of all Federally listed species that would be considered in an Endangered Species Act (ESA) Section 7 determination was performed based on the list above. Based upon an understanding of the life histories of the listed species, potential habitat was verified within the Study Area for three potential species described in *Table 3*. Multiple confirmed maternity roost trees or hibernacula for the NLEB (Northern Longeared Bat) are located within five miles of the Study Area (NLEB Regulatory Buffer Interactive Tool, 2024). Also, no hibernacula or maternity roosts for tri-colored bat are located within the vicinity of the Study Area.

Regarding the tricolored bat (Perimyotis subflavus), the species is currently proposed for federal listing as an endangered species. Although it is not currently federally listed, the species is included in this analysis

as habitat for the species occurs in the Project Study Area and coordination with USFWS for the species would be required if the project advances Section 7 coordination/consultation.

Should this project progress to more detailed design, field surveys may be required to verify the presence or absence of Section 7 listed species.

Table 3 - Species with Habitat Identified Within the Vicinity of the Study Area

Species	Type of Habitat Impacted	Alternative 2.1
Northern Long-eared Bat	Summer roosting habitat	Potential Habitat Present
Tri-colored Bat	Summer roosting habitat	Potential Habitat Present
Wood Turtle	Hibernation habitat	Potential Habitat Present

#### WOTUS: Including Streams, Wetlands, Floodplains, and Resource Protection Areas (RPAs)

Wetlands and streams were not delineated, and a jurisdictional determination was not received as part of this study. A desktop review was conducted to evaluate the Gap Area for potential wetlands and streams that could be impacted by the proposed trail project. ATCS utilized available aerial imagery, GIS data, and National Wetlands Inventory (NWI) data to identify potential wetlands and streams within the LOD of the proposed trail alignments in Gap Area 2. The total acreage of wetlands, streams, RPAs, and Floodplains is shown in *Table 4* below. Should any of these alignments be carried forward to final design, detailed analysis will be required to determine the full extent of each resource.

Table 4 - Water Resources Mapped within the Vicinity of the Study Area

Factor	Alternative 2.1
Wetlands Impacted (Acres)	0
Streams (feet)	1,421
RPAs (Acres)	2.31
Floodplain (Acres)	9.33

#### 6.1.3 Hazardous Materials

The Virginia Department of Environmental Quality (DEQ) recommends searching multiple databases to obtain information on potentially contaminated areas, including areas with hazardous materials. A third party, Environmental Risk Information Services (ERIS) was utilized to perform a database review of the proposed Gap Area.

Based on the above-mentioned databases, three sites of potential concern were identified along the proposed Alternative 2.1 alignment.

Based on the database search and field inspection, there is the potential for impacts to hazardous materials sites during construction activities. Potential issues due to contaminated groundwater are of particular

concern. Additional surveys will need to be performed prior to construction to ensure the avoidance and minimization of any impacts to the above-mentioned sites

#### 6.1.4 Air Quality and Noise

Alternative 2.1 was assessed for potential air quality impacts and compliance with applicable air quality regulations and requirements defined under Clear Air Act (CAA) 42 USC §7401 et seq. and EPA's 40 CFR § 93.114 and § 93.115. The assessment indicates that the project will not cause or contribute to a new violation, increase the frequency or severity of any violation, or delay timely attainment of the NAAQS established by the EPA as the project does not involve the construction of transportation facilities with the potential to increase the number of vehicles within the Gap Areas.

Evaluation of the potential project alignments, and the project scope resulted in the determination that this project does not qualify as a Type I Project per 23 CFR §772.5 and the VDOT noise manual for purposes of a noise analysis. Therefore, a noise analysis is not required as part of this project.

#### 6.1.5 Historic Resources

#### Architectural Resources and Archaeological Resources

As discussed in *Section 3.7*, several historic resources are located within Gap Area 2. Alternative 2.1 has the potential to impact two NRHP listed architectural resources: the Prince William Forest Park Historic District (DHR ID: 076-0299) and the Weems-Botts House (DHR ID: 212-0010). The Prince William Forest Park Historic District is comprised of approximately 17,000 acres of piedmont forest and straddles the fall line of Quantico Creek, extending from the Coastal Plain up to the Piedmont. Remnants are still visible of the farms and other early, man-made features that were present prior to the Federal Government's purchase of the large tract of land that now comprises the Prince William Forest Park. Evidence of the abandoned settlement areas includes family cemeteries, mill sites, foundations of old buildings--dwellings, churches and schools--outlines of once-worked fields that have yielded to the new growth of pine stands, and traces of old roads that once crisscrossed the region. The ruins of a late 19<sup>th</sup>/early 20th century pyrite mine can be seen where Quantico Creek meets the South Fork of the Quantico. Evidence of two pre-colonial Native American campsites has also been found in the park.

The Weems-Botts House has both architectural and historical significance. It is associated with two prominent early Virginians, Mason Locke (Parson) Weems and Benjamin Botts. The house is one of the few remaining early buildings in Dumfries, a tobacco port on the Potomac, which flourished from the mid-18th century to the early 19th century. The earliest part of the building is a fine example of a small commercial structure of the late 18th century and is a true story-and-a-half building, a rare type in Virginia. It is believed that Mason Locke Weems, the first biographer of George Washington and an itinerant preacher, established a bookshop and temporary residence in the house, which he likely built sometime after he purchased Lot 51 from the town of Dumfries in 1798.

While the proposed alignment of Alternative 2.1 does pass by the Weems-Botts House and into Prince William Forest Park, the proposed improvements are unlikely to significantly alter the character or integrity

of these resources and are expected to constitute a "no adverse effect" finding. However, additional evaluation and coordination with VDHR will be necessary during preliminary and final design to coordinate and confirm a "no adverse effect" finding.

#### 6.2.6 Section 4(f) / 6(f) Resources

As discussed above and in *Section 3.7*, there are historic resources and parks located within Gap Area 2. However, there are no wildlife or waterfowl refuges present. There are currently no planned acquisitions of property under the protection of Section 6(f), other unique areas, or special lands. However, Prince William Forest Park has a number of Land and Water Conservation Funded sites which would fall under the protection of Section 6(f), none of these sites are anticipated to be impacted by the proposed alternative.

As discussed in *Section 3.7.6*, there are several historic resources within the Gap Area which have the potential to be considered Section 4(f) resources. Currently, minor right-of-way acquisition may be required adjacent to the Weems-Botts House along the north side of Cameron Street to accommodate a wider path/sidewalk in this location, and this has the potential to be considered a Section 4(f) use. Special consideration should be given during preliminary and final design to avoid and/or minimize impacts to this and any other historic resources adjacent to the project alignment. However, coordination will be necessary between VDHR, NPS, the County and any other formal stakeholders to determine if there is an official "use" associated with Alignment 2.1.

#### 6.1.7 Safety

#### Road Crossings and Traffic Volumes

Alternative 2.1 begins at the intersection of Main Street and Duke Street. The alignment follows Duke Street before turning left onto Cameron Street. The alignment then crosses to the south side of Batestown Road, which it follows crossing under I-95 to intersect Van Buren Road. The alignment then travels along the south side of Van Buren Road before connecting to existing and planned trail alignments within Prince William Forest Park. Alternative 2.1 only has one major road crossing, located on Batestown Road. The crossing occurs at an all-way stop-controlled intersection at Batestown Road and Cameron Street. Batestown Road has an estimated ADT of 5,800 vehicles per day in this area. A RRFB is recommended at this location to enhance the safety of trail users. Overall, Alternative 2.1's alignment is along local town streets with lower traffic volumes reducing the time trail users are along roads with high traffic volumes.

## 7.0 Recommended Alternative

This chapter presents the recommended alternative (i.e. preferred alignment) based on the environmental, technical, and community considerations discussed throughout this report. The recommended alternative reflects a balance between enhancing recreational opportunities, preserving natural resources, and addressing stakeholder input gathered throughout the planning process. The recommended alternative aims to provide a flexible solution that aligns with the project's overall needs while considering potential impacts and feasibility. By presenting this alternative, we aim to support informed decision-making and ensure the selected trail alignment delivers the greatest value to the community and environment.

#### 7.1 Alternative 2.1




Figure 10 - Recommended Alternative Alignment

After evaluation, Alternative 2.1 was determined to be the alternative that best meets the Purpose and Needs while balancing costs and impacts. Based on meeting these criteria, Alternative 2.1 is the recommended alternative for Gap Area 2. See *Chapter 4.0, Section 4.1* for additional details on Alternative 2.1's proposed alignment.

The identification of the recommended alternative also considers constructability, feasibility, and input from the County and the public. Alternative 2.1 will meet the Purpose and Needs by:

• Increasing access and mobility by providing additional travel mode choices and available travel routes to those living in or around Gap Area 2.

- Improving health, safety, and quality of life by providing a dedicated trail separated from traffic and increasing choices for travel and to move throughout the study area.
- Providing economic benefits to the region by providing residents with additional connections and modes of access between the Town, retail centers, and recreation areas.

#### Trail Attractiveness

Trail Attractiveness is evaluated by the extent to which the trail is separated from traffic, its scenic value and level of bicyclist comfort. In this respect, Alternative 2.1 has favorable features due to its alignment through the Town along Duke and Cameron Streets, which are residential and have low traffic volumes. These roads also serve Town amenities as discussed in *Section 6.1.1*. Trailheads, waysides, and opportunities for interpretation were not included in the design of this study. However, there will be opportunities to address these visual additions to the alignments when the project progresses to more detailed design.

#### Cost of Construction

The construction cost estimate process is described in detail in *Chapter 8.0* and additional details are provided in *Appendix C.* Overall, construction cost estimates are estimated at \$3.5 million for Alternative 2.1.

## **8.0 Project Costs**

A planning-level cost estimate was developed for each evaluated alignment within the Gap Area to support analysis and help inform decision-making. This estimate incorporates a comprehensive range of cost factors essential to the successful implementation of each alternative. Key components included are described below. Each of these components were integrated into the feasibility study to ensure the estimates reflected realistic and context-sensitive project requirements. Additionally, a contingency amount of 50% was included for each alternative, reflecting recent VDOT guidance. It should be noted that engineering and design costs were not included as part of this estimate.

Following the completion of the conceptual alignment designs, preliminary construction cost estimates were prepared for each recommended alternative alignment. To facilitate a fair and objective comparison, the methodology for calculating quantities and associated costs was standardized across all alignments. This standardized approach was aligned with VDOT's established cost estimation procedures, ensuring consistency, accuracy, and transparency in the evaluation process.

Each cost estimate was organized into key engineering and construction disciplines to clearly identify the scope and associated cost implications. The estimates were broken down as follows:

- Mobilization/Construction Survey Project setup, site access, and initial surveying activities.
- Roadway/Trail Pavement, grading, curbs, gutters, and other road/trail infrastructure elements.
- **Hydraulics** Stormwater management systems, drainage structures, erosion & sediment control, and water quality features.
- Traffic Traffic control measures, signage, signals, and pavement markings.
- Structures/Bridges Bridges, retaining walls, culverts, and other structural elements.
- Earthwork/Geotechnical Excavation, embankment, grading, and soil stabilization measures.

Each of the previously listed items was individually estimated and incorporated into the overall cost of major construction components, including asphalt paving, aggregate base, curb and gutter installations, ADA-compliant ramps, fencing, stormwater drainage piping, pavement markings, raised walkways, retaining walls, and other key infrastructure elements. Quantity take-offs for these items were developed based on the proposed alignment lengths, supplemented by available GIS data—particularly for earthwork estimation—and verified using aerial imagery to ensure accuracy at this conceptual stage.

Given the preliminary nature of this feasibility study, certain cost elements were included as allowances rather than being based on detailed quantity calculations. These items included stormwater management facilities, maintenance of traffic (MOT), roadside development, and signage. This approach provides flexibility to accommodate future refinement as the design progresses.

For all estimated items, representative unit cost data was applied. Where applicable, unit pricing was derived using VDOT's cost estimation tools and databases, referencing comparable recent roadway and multi-use trail projects within the Northern Virginia region. This ensured alignment with current market conditions and regional construction cost trends. In cases involving specialized infrastructure, additional guidance and input were obtained from local industry experts to develop a more accurate and context-sensitive estimate. Once the overall estimated project construction costs were completed, it was separated according to the proposed project phasing outlined in *Chapter 9.0* of this report. These estimates are for construction costs in current year (2025) dollars and do not include right-of-way acquisition or utility relocation. However, right-of-way, utility relocations, and environmental costs can be generally calculated based both on the amount of impact and the number of impacts as described below.

- *Right-of-Way*. Right-of-way impacts include both permanent right-of-way acquisition and the necessity for permanent and temporary easements. These can be the result of the physical trail construction itself, and the easements required to build, access, and maintain the trail. The number of individual parcels affected by the trail can be quantified for each alignment option. Once the number of parcels is known, an estimated area can be calculated and a cost placed for comparison.
- *Utility Relocation:* During the initial investigation phase, existing utility infrastructure locations were noted and placed on GIS mapping. The layout of the multiple trail alignments was then designed to avoid areas with major utility conflicts. The number and length of the remaining impacted utilities can then be included as an evaluation criterion.
- Environmental Mitigation. Potential sensitive areas, including wetlands, streams, and historical locations and properties, were similarly noted within the overall study area during the initial investigation phase. Trail alignments attempted to avoid and minimize impacts to these areas where possible. Where impacts were unavoidable, it was proposed to bridge these resources to limit the area affected. Each potentially affected area could then be quantified for comparison similar to the utility and right-of-way items.

These estimates are based on the best data available as described above. Detailed cost estimates based on current survey data will need to be developed at the onset of the design and engineering stage of each project. *Table 5* contains a summary of the costs for the evaluated gap area. Detailed summaries, cost breakdowns, and supporting details are included in *Appendix C*.

Table 5 - Estimated Alternative Costs

Alternative	Estimated Cost
Alternative 2.1	\$3.5 Million

## 9.0 Project Phasing

Phasing a trail project allows for a strategic, incremental approach to development, ensuring efficient use of resources while delivering benefits early. Dividing the project into manageable phases can allow funding to be secured incrementally, minimize construction disruptions, and integrate community feedback throughout the process. Prioritizing key segments—such as high-use areas, critical connections, or sections with available funding also helps build momentum and support for the full trail network over time. Graphical illustrations of the proposed project phasing can be found in *Appendix D*.

#### 9.1 Phasing Within Gap Area 2:

The proposed phasing should move from east to west beginning at Main Street and Cameron Street. The proposed phases are described in additional detail below.

#### Phase 1

- Connect to existing Town sidewalks
- Widen existing shared use paths and connect users to major points of interest including the Weems-Botts Museum, churches, historical markers, the Dumfries Elementary School and the cemetery.
- Estimated Cost: \$1,062,100

#### Phase 2

- Continue trail from town west along Batestown Road.
- Estimated Cost: \$913,000

#### Phase 3

- Connect to Prince William Forest Park including construction of new pedestrian bridge over Quantico Creek.
- Estimated Cost: \$1,592,100

The phasing plan outlined above represents a strategic approach to planning and implementation for the Gap Area described as part of this feasibility study. With that in mind, it is possible that design details, proposed alignments, and potential impacts may change in the future, which could preclude or allow for the construction of some, or all of the phases described above. The information included in this report can be used by the County and DPR to move forward with closing gaps in the PHNST. Additional information about potential next steps and funding opportunities is included in *Chapter 10*.

## **10.0 Next Steps**

Following the completion of this feasibility study, the next steps focus on advancing the project from planning to implementation. Incorporation of the preferred alignment into relevant planning documents should occur as soon as possible. As project funding becomes available for each phase, preliminary design should be initiated and required environmental approvals should be obtained, including securing all necessary permits and approvals. Funding opportunities, including grants and public-private partnerships, should be pursued to support project implementation. Additionally, right-of-way acquisition and land agreements need to be secured through negotiations with property owners and municipalities. A phased construction plan should be developed to align with funding availability and community priorities, with a timeline that considers seasonal and environmental constraints. Design and engineering will be subject to review by pertinent agencies through the County's land development and permitting process. By following these steps, this project can continue to move toward becoming a valuable community asset that enhances connectivity, recreation, and environmental sustainability.

#### 10.1 Incorporation of Recommended Alternative into Relevant Plans

It is the recommendation of the study team that the preferred alignment be incorporated into the County's Trail Plan, in the Mobility Chapter of the Comprehensive Plan, at such time that the Trail Plan map is updated. This will be helpful for advancing the project. It should be noted that some segments of the recommended alternatives are already consistent with the Trails Plan. As soon as practical or as soon as funding is obtained, the preferred alignment for this Gap Area should also be added to the County's Capital Improvement Plan (CIP). The CIP has a section for the PHNST and for FY 2026-FY2031, two sections of the trail were included: Featherstone Refuge and Neabsco Wetland Preserve Boardwalk. Both of these PHNST trail sections are currently under construction and the County should begin to secure funding for completion of Gap Area 2, to maintain this momentum for completion of the PHNST in Prince William County. Additionally, the County should submit this Gap Area 2 alignment as an addition to TransAction (Northern Virginia's long-range multimodal transportation plan) at the next cycle in 2027, so that it is eligible for funding from the Northern Virginia Transportation Authority (NVTA).

#### 10.2 Funding Opportunities

Funding is necessary for the project(s) to advance to design and construction. The County could fund the projects fully, or leverage County funds to obtain State or Federal funding assistance. Listed below are the primary funding programs from which the County could seek funds to advance these projects. This list is not intended to be comprehensive, and the County should continue to look for new and additional funding opportunities. Securing funding for projects like the PHNST can be complex and it is recommended that the County consider opportunities to "stack" or "braid" funding sources to support development and delivery of the full PHNST.

#### 10.2.1 Federal Sources

At the time of this report, a number of changes to Federal funding criteria are being made by the current presidential administration, particularly with regard to discretionary funding provided to projects including equity activities, Diversity, Equity, and Inclusion (DEI) activities, climate change activities, environmental justice (EJ) activities, gender specific activities, when the primary purpose is bicycle infrastructure (i.e., recreational trails and shared-use paths, etc.), electric vehicles (EV), and EV charging infrastructure. In these cases, projects are being reviewed to identify and potentially remove scope items as noted.

Federal formula funding programs (with the exception of the Carbon Reduction Program (CRP), the National Electric Vehicle Infrastructure (NEVI), and PROTECT), are generally flowing, including those with eligibilities pertaining to non-traditional transportation and mobility such as the Transportation Alternatives Program (TAP). Given that the Infrastructure Investment and Jobs Act, also known as the Bipartisan Infrastructure Law, is the current federal transportation authorization and remains in effect until at least September 30, 2026, it is reasonable to continue to consider federal formula program funding as potential opportunities to support advancing the PHNST. For example, the Notice of Funding Opportunity for the Safe Streets and Roads for All (SS4A) Program was issued in March 2025.

#### Transportation Alternatives Program (TAP)

This Federal reimbursement program provides funding for a variety of transportation projects such as pedestrian and bicycle facilities; construction of turnouts, overlooks, and viewing areas; community improvements such as historic preservation and vegetation management; environmental mitigation related to stormwater and habitat connectivity; recreational trails; safe routes to school projects; and vulnerable road user safety assessments. The TAP is a critical component to support Complete Streets that are safe for all users and achieve safe, connected, and equitable on-and off-road networks. "On- and off-road trails for pedestrians, bicyclists, and other non-motorized forms of transportation" is first on the list of eligible project categories, so the PHNST is well aligned to this program.

VDOT administers the TAP under the auspices of FHWA and, under VDOT's guidelines. Funding is focused on providing pedestrian and bicycle facilities and community improvements that expand or enhance the non-motorized travel network. Eligible projects must meet a transportation purpose. VDOT administers TAP as a competitive grant program with a biennial application cycle. The current application cycle recently began on April 1, 2025 with project selections scheduled in calendar year 2026, and funding anticipated to be made available beginning in FY 2027. Assuming no change to VDOT's application cycle, the next round of applications will begin in Spring 2027. VDOT recommends early coordination with the Northern Virginia District Office, and the anticipated timeline for the next round of TAP funding aligns well with accomplishing other needed actions, such as adding these segments to local plans and gaining appropriate approvals.

Funding is provided on a reimbursement basis, like most federal funds, with an 80% federal share and a 20% local share. Projects are to be under construction within four years of the initial allocation. Project costs are capped at \$2.5 million per project.

#### Virginia Recreational Trails Program (RTP)

RTP is a federal program funded by the Infrastructure Investment and Jobs Act at 80% federal and 20% local funding levels. The Virginia DCR administers the RTP in conjunction with FHWA. The program's purpose is to develop and maintain public recreational trails for motorized and non-motorized use and therefore, by definition, projects eligible for funding under RTP do not generally serve a transportation purpose. Therefore, classifying the recommended alternatives as recreational for purposes of applying for RTP funding could preclude or complicate pursuing the transportation funding sources described above, which have far larger funding pools available, although they are historically oversubscribed.

#### Federal Lands Access Program (FLAP)

This is the program that is funding the current feasibility study. Consequently, the recommended alternatives are logically eligible for continued project funding for implementation. This program is administered by FHWA. The purpose of this program is to improve transportation facilities that provide access to, are adjacent to, or are located within Federal lands. It supplements state and local funds with an emphasis on high-use recreation sites and economic generators. Generally, the federal share of FLAP grants would be 80%. For FY 2027- FY 2029, approximately \$8.5 million is available for this program. However, at the time of this report's publication, the deadline for applications for that cycle has passed.

#### 10.2.2 Non-Federal Sources

#### VDOT Revenue Sharing

This program is for construction, reconstruction, or improvement of highway systems. It provides state matching funds at a 50% state share and a 50% local share. It may include sidewalks and trails that accommodate pedestrian and bicycle access along the state highway network. Consequently, only the segments of the recommended alternatives that are along VDOT roadways are likely to be eligible for this funding source. Furthermore, the projects must contain a construction component; projects cannot be limited to the environmental approval or design phase. This program is a competitive application-based program and applicant projects are prioritized based on criteria published by VDOT. VDOT accepts applications on a biennial basis in odd numbered years, with the application period open in the April-May time frame. As with TAP, VDOT recommends early coordination with the Northern Virginia District Office.

#### **NVTA TransAction**

The NVTA is the regional organization that develops and funds the long-range transportation plan for Northern Virginia. TransAction is the long-range multimodal transportation plan for Northern Virginia containing transportation needs through 2045, including bicycle and pedestrian improvements that provide connectivity in the region. This plan is updated every five years, with the last update approved at the end of 2022. The next update is anticipated to be completed by the end of 2027. As a regional facility with a transportation purpose, the PHNST is aligned as a candidate project for TransAction. Currently, TransAction includes other regional bike-ped projects such as improvements to the W&OD Trail.

Additionally, there are several PHNST adjacent or overlapping projects included in the current TransAction Plan. In Gap Area 2, there is a project to develop a multi-use trail along Richmond Highway connecting Alexandria to Woodbridge via Fort Belvoir (Project 433).

#### 10.3 Conclusion

This feasibility study has documented a range of factors necessary for completion of approvals for the preferred Gap Area 2 alignment. However, the formal process for environmental approval, often completed simultaneously with the preliminary design phase, still requires additional detailed study. Based on the work done in this feasibility study, it is likely that each of the recommended alternatives would be eligible for evaluation under a Categorical Exclusion (CE) due to a lack of individual or cumulative significant effects on the human environment. However, this will need to be determined during the next phase of the project based on the overall scope of activities.

The funding programs described above represent the most likely sources to advance the project. Funding for transportation projects is far more abundant than funding for recreation projects and competition for these funds is fierce. While the funding landscape is quite volatile at the publication of this report, it will likely continue to evolve. Filling gaps in the PHNST, must remain a priority, not only for residents of and visitors to Prince Willaim County, but for the greater strengthening the National Trail System.

### **Citations**

- A snapshot of disadvantage in the United States. (2022, October 18). Retrieved from ESRI: A snapshot of disadvantage in the United States
- American Association of State Highway and Transportation Officials, A. (2012). *Guide for the Development of Bicycle Facilities*, *5th Edition*.
- Commission, N. V. (2023). *Potomac Heritage National Scenic Trail Northern Virginia Dashboard*. Retrieved from About the PHNST: https://www.potomacheritagenova.com/about-the-phnst
- Countywide Trails Plan. (2022, December 13). Retrieved from Prince William County Virginia: https://storymaps.arcgis.com/collections/bb8f73148987481380f30c110a658ef2?item=4
- Dumfries, T. o. (2025, March 3). Comprehensive Plan Update 2024. Retrieved from Town of Dumfries: https://www.dumfriesva.gov/government/departments/planning\_and\_community\_development/comprehensive plan/destinationdumfries2044.php
- NLEB REgulatory Buffer Interactive Tool. (2024, August). Retrieved from Virginia Department of Wildlife Resources: https://dgif-virginia.maps.arcgis.com/apps/webappviewer/index.html?id=32ea4ee4935942c092e41ddcd19e5ec5
- (2022). Northern Virginia Potomac Heritage National Scenic Trail: Health, Social Equity, and Economic Impact Study.

  Northern Virginia Regional Commission.
- Prince William County 2040 Comprehensive Plan. (2022, December 13). Retrieved from https://experience.arcgis.com/experience/ea093ab38cdb425c8d29b14bbfaa97f0
- Prince William County 2040 Comprehensive Plan: Environment. (2022, December 13). Retrieved from https://storymaps.arcgis.com/collections/130026d53ede48e3a7850c37969b33c6
- Prince William County 2040 Comprehensive Plan: Mobility. (2022, December 13). Retrieved from Prince William County Virginia: https://www.pwcva.gov/department/planning-office/prince-william-county-comprehensive-plan
- Prince William County Federal Lands Access Program (FLAP) Agreement. (n.d.). FLAP Agreement Worksheet.
- Recreation, P. W. (2019). 2019 Prince William County Parks and Recreation Needs Assessment Survey.
- Stafford County Virginia. (2019). Bicycle & Pedestrian Facilities Plan.
- TIGER/Line Shapefiles. (2024, October 9). Retrieved from United States Census Bureau: https://www.census.gov/geographies/mapping-files/time-series/geo/tiger-line-file.html


# **Appendix A- Existing Conditions Mapping**


**A.1 - Community Resources** 

A.2 - Existing Trails and Utilities

A.3 - Water Resources







# **Appendix B- Alternatives and Impact Mapping**

**B.1 – CADD Plan Sheets** 

**B.2 – Community and Cultural Resources** 


**B.3 – Water Resources** 


# Appendix B.1 POTOMAC HERITAGE NATIONAL SCENIC TRAIL (PHNST) GAP ANALYSIS FEASIBILITY STUDY

PREPARED FOR:

PRINCE WILLIAM COUNTY DEPARTMENT OF PARKS AND RECREATION 14420 BRISTOW ROAD MANASSAS, VIRGINIA 20112

SHEET LIST TABLE								
SHEET NUMBER	SHEET TITLE	SHEET DESCRIPTION						
01	GI001	COVER SHEET						
02	CP100	PHNST - PREFERRED ALIGNMENT - GAP 1 OVERALL						
03	CP101	PHNST - PREFERRED ALIGNMENT - GAP 1						
04	CP102	PHNST - PREFERRED ALIGNMENT - GAP 1						
05	CP103	PHNST - PREFERRED ALIGNMENT - GAP 1						
06	CP104	PHNST - PREFERRED ALIGNMENT - GAP 1						
07	CP105	PHNST - PREFERRED ALIGNMENT - GAP 1						
08	CP106	PHNST - PREFERRED ALIGNMENT - GAP 1						
09	CP107	PHNST - PREFERRED ALIGNMENT - GAP 1						
10	CP108	PHNST - PREFERRED ALIGNMENT - GAP 1						
11	CP109	PHNST - PREFERRED ALIGNMENT - GAP 1						
12	CP110	PHNST - PREFERRED ALIGNMENT - GAP 1						
13	CP111	PHNST - PREFERRED ALIGNMENT - GAP 1						
14	CP200	PHNST - PREFERRED ALIGNMENT - GAP 2 OVERALL						
15	CP201	PHNST - PREFERRED ALIGNMENT - GAP 2						
16	CP202	PHNST - PREFERRED ALIGNMENT - GAP 2						
17	CP203	PHNST - PREFERRED ALIGNMENT - GAP 2						
18	CP204	PHNST - PREFERRED ALIGNMENT - GAP 2						
19	CP300	PHNST - PREFERRED ALIGNMENT - GAP 3 OVERALL						
20	CP301	PHNST - PREFERRED ALIGNMENT - GAP 3						
21	CP302	PHNST - PREFERRED ALIGNMENT - GAP 3						
22	CP303	PHNST - PREFERRED ALIGNMENT - GAP 3						
23	CP304	PHNST - PREFERRED ALIGNMENT - GAP 3						





HERITAGE (PHNST) G

007078 FEB 2025 PROJ.#: SHEET

GI001









































Potential Impacts Alternative 2.1



# **Appendix C- Project Costs**

C.1 – Cost Summary by Alignment

**C.2** – Detailed Cost Comparison by Alignment

**C.3** – Phased Cost Estimates

Appendix C.1

Gap 2								
	Overall Trail							
Length (LF) Cost Cost/LF								
Alignment 1	5,110	\$ 3,567,213.71	\$	698.08				
Alignment 2	4,820	\$ 3,784,239.63	\$	785.11				
Alignment 3	5,150	\$ 12,751,944.38	\$	2,476.11				

Appendix C.2 - Potomac Heritage National Scenic Trail Feasibility Study -- Cost Comparisons

Gap 2	Alianmo	nt 1 (Overall length = 5110')		ent 2 (Overall length = 4820')	•	nent 3 (Overall length = 5150')	
Construction (CN) Phase:	Quantity Unit	Unit Cost Extended Cost	Quantity Unit	Unit Cost Extended Cost	Quantity Unit	Unit Cost Extended Cost	
Mobilization/Constr Survey	Qualitity Offic	Onit Cost Extended Cost	Qualitity Offic	Onit Cost Extended Cost	Qualitity Offic	Cilit Cost Extended Cost	
513SD20-0001 Mobilization	1 LS	\$ 141,000.00 \$ 141,000.00	1 LS	\$ 148,000.00 \$ 148,000.00	1 LS	\$ 430,000.00 \$ 430,000.00	20
517SD20-0001 Mobilization 517SD20-0001 Constuction Surveying	1 LS	\$ 23,000.00 \$ 23,000.00	1 LS	\$ 24,000.00 \$ 24,000.00	1 LS	\$ 80,000.00 \$ 80,000.00	
padway	1 10	Ψ 23,000.00 Ψ 23,000.00	1 1.5	Ψ 24,000.00 Ψ 24,000.00	1 113	ψ 00,000.00 ψ 00,000.00	50
315SD20-0002 Asphalt Concrete TY. SM-12.5D Const	370 TON	\$ 250.00 \$ 92,500.00	370 TON	\$ 250.00 \$ 92,500.00	310 TON	\$ 250.00 \$ 77,500.00	20
308SD20-0002 Aggr. Base Matl. TY. 1 No. 21B	1650 TON	\$ 80.00 \$ 132,000.00	1640 TON	\$ 80.00 \$ 131,200.00	1250 TON	\$ 80.00 \$ 100,000.00	
510SX20-0011 Remove Sidewalk and Entrance	795 SY		1040 TON	\$ 45.00 \$ 4,500.00	385 SY	\$ 45.00 \$ 100,000.00	
502SD20-0001 Remove Sidewalk and Entrance 502SD20-0022 Comb. Curb & Gutter, Std CG-6	50 LF	\$ 45.00 \$ 35,775.00 \$ 60.00 \$ 3,000.00	860 LF	\$ 60.00 \$ 51,600.00	0 LF	\$ 45.00 \$ 17,325.00	JU
504SD20-0003 Hydr. Cement Concrete Sidewalk, 4"	1600 SY	\$ 95.00 \$ 152,000.00	1565 SY	\$ 95.00 \$ 148,675.00	890 SY	\$ 95.00 \$ 84,550.00	20
•	150 SY		90 SY	\$ 260.00 \$ 23,400.00	60 SY	\$ 260.00 \$ 15,600.00	
504SD20-0004 Hydr. Cement Concrete Sidewalk, 7"	30 SY		20 SY	\$ 660.00 \$ 23,400.00	15 SY	\$ 660.00 \$ 9,900.00	
504SD20-0002 CG-12 Detectable Warning Surface							
316SD20-0030 Concrete Entrance Pave. 7"	0 SY	\$ 180.00 \$ -	25 SY	\$ 180.00 \$ 4,500.00	40 SY	\$ 180.00 \$ 7,200.00	
504SD20-0015 Handrail HR-1, Type III	400 LF	\$ 320.00 \$ 128,000.00	400 LF	\$ 320.00 \$ 128,000.00	100 LF	\$ 320.00 \$ 32,000.00	
Roadway Defined Item Subtotal		\$ 602,075.00		\$ 597,575.00		\$ 344,075.00	JU
Hydraulics	55.15	h 100.00 h 10.450.00	55.15	h 100.00 h 10.450.00	0.15	ф. 100.00 ф	
302SD20-0201 18" Conc. Pipe	55 LF	\$ 190.00 \$ 10,450.00	55 LF	\$ 190.00 \$ 10,450.00	0 LF	\$ 190.00 \$ -	
302SD20-0030 18" End Section, ES-1	3 EA	\$ 2,100.00 \$ 6,300.00	3 EA	\$ 2,100.00 \$ 6,300.00	0 EA	\$ 2,100.00 \$ -	
502SD20-0004 Paved Ditch, PG-5	30 SY	\$ 275.00 \$ 8,250.00	30 SY	\$ 275.00 \$ 8,250.00	0 SY	\$ 275.00 \$ -	
303SD20-0030 Inlet Protection Type A	1 EA	\$ 570.00 \$ 570.00	1 EA	\$ 570.00 \$ 570.00	0 EA	\$ 570.00 \$ -	
303SD20-0031 Inlet Protection Type B	9 EA	\$ 525.00 \$ 4,725.00	2 EA	\$ 525.00 \$ 1,050.00	3 EA	\$ 525.00 \$ 1,575.00	
303SD20-0034 Temp. Silt Fence Type A	4280 LF	\$ 6.00 \$ 25,680.00	4455 LF	\$ 6.00 \$ 26,730.00	4110 LF	\$ 6.00 \$ 24,660.00	
303SX20-0022 NS Erosion Control (Tree Protection)	5020 LF	\$ 2.50 \$ 12,550.00	4175 LF	\$ 2.50 \$ 10,437.50	4680 LF	\$ 2.50 \$ 11,700.00	
Hydraulics Defined Item Subtotal		\$ 68,525.00		\$ 63,787.50		\$ 37,935.00	00
Traffic					1		
704SD20-0010 Type B Class I Pvmt Line Marking 24"	508 LF	\$ 16.00 \$ 8,128.00	372 LF	\$ 16.00 \$ 5,952.00	315 LF	\$ 16.00 \$ 5,040.00	
Traffic Defined Item Subtotal		\$ 8,128.00		\$ 5,952.00		\$ 5,040.00	00
Structures/Bridges	2000.05		2000.05		00500.05		
401SX20-0001 Wooden Bridge	2880 SF	\$ 235.00 \$ 676,800.00	2880 SF	\$ 235.00 \$ 676,800.00	28500 SF	\$ 235.00 \$ 6,697,500.00	
Retaining Wall	530 LF	\$ 700.00 \$ 371,000.00	670 LF	\$ 700.00 \$ 469,000.00	100 LF	\$ 700.00 \$ 70,000.00	
Structures/Bridges Defined Item Subtotal		. \$ 1,047,800.00		\$ 1,145,800.00		\$ 6,767,500.00	00
Earthwork/Geotech					1		
303SD20-0001 Regular Excavation	1700 CY	\$ 65.00 \$ 110,500.00	2200 CY	\$ 65.00 \$ 143,000.00	660 CY	\$ 65.00 \$ 42,900.00	
305SD20-0001 Borrow Excavation	1360 CY	\$ 50.00 \$ 68,000.00	1360 CY	\$ 50.00 \$ 68,000.00	1270 CY	\$ 50.00 \$ 63,500.00	
301SD20-0002 Clearing and Grubbing	1.9 AC	\$ 35,000.00 \$ 66,500.00	2.0 AC	\$ 35,000.00 \$ 70,000.00	2.6 AC	\$ 35,000.00 \$ 91,000.00	
303SD20-0006 Extra Excavation	150 CY	\$ 95.00 \$ 14,250.00	150 CY	\$ 95.00 \$ 14,250.00	140 CY	\$ 95.00 \$ 13,300.00	
Earthwork/Geotech Defined Item Subtotal		\$ 259,250.00		\$ 295,250.00		\$ 210,700.00	00
Defined bear Outstate (for All Control of the Contr		<b>*</b> 4 00= ==0 00		<b>*</b> 0 100 001 ==		<b>* = 22= 2</b> = 2=	20
Defined Item Subtotal (for Allowance Calculations)	00/	\$ 1,985,778.00	607	\$ 2,108,364.50	201	\$ 7,365,250.00	
Allowances Stormwater Management Allowance	2%	\$ 39,715.56	2%	\$ 42,167.29	2%	\$ 147,305.00	
MOT	7.5%	\$ 148,933.35	7.5%	\$ 158,127.34	5.0%	\$ 368,262.50	
Roadside Development (Minimal RD, Grass	•	\$ 29,786.67	1.5%	\$ 31,625.47	1.0%	\$ 73,652.50	
Signage	0.5%	\$ 9,928.89	0.5%	\$ 10,541.82	0.5%	\$ 36,826.25	
Construction Subtotal (for Mobilization and Constr Survey)		\$ 2,214,142.47		\$ 2,350,826.42		\$ 7,991,296.25	25
Construction Subtotal		\$ 2,378,142.47		\$ 2,522,826.42		\$ 8,501,296.25	25
Contingency	50%	\$ 1,189,071.24	50%	\$ 1,261,413.21	50%	\$ 4,250,648.13	13
Total		\$ 3,567,213.71		\$ 3,784,239.63		\$ 12,751,944.38	38

Appendix C.3 -Potomac Heritage National Scenic Trail Feasibility Study -- Cost Comparisons

Gap 2	Alignment 1 (Overall length = 5110')								
Construction (CN) Ph	ase:	Ext	tended Cost	Ph	ase 1	Phase 2			ise 3
Mobilization/Constr S	urvey								
513SD20-0001	Mobilization	\$	141,000.00	\$	53,580.00	\$	29,610.00	\$	57,810.00
517SD20-0001	Constuction Surveying	\$	23,000.00	\$	8,740.00	\$	4,830.00	\$	9,430.00
Roadway									
	Roadway Defined Item Subtotal	\$	602,075.00	\$	334,885.00	\$	175,145.00	\$	92,045.00
Hydraulics									
	Hydraulics Defined Item Subtotal	\$	68,525.00	\$	13,455.00	\$	34,070.00	\$	21,000.00
Traffic									
	Traffic Defined Item Subtotal	\$	8,128.00	\$	8,128.00	\$	-	\$	-
Structures/Bridges									
	Structures/Bridges Defined Item Subtotal	\$	1,047,800.00	\$	133,000.00	\$	238,000.00	\$	676,800.00
Earthwork/Geotech									
	Earthwork/Geotech Defined Item Subtotal	\$	259,250.00	\$	69,500.00	\$	79,050.00	\$	110,700.00
Allowances	Stormwater Management Allowance	\$	39,715.56	\$	15,091.91	\$	8,340.27	\$	16,283.38
	MOT	\$	148,933.35	\$	56,594.67	\$	31,276.00	\$	61,062.67
	Roadside Development (Minimal RD, Grass)	\$	29,786.67	\$	11,318.93	\$	6,255.20	\$	12,212.53
	Signage	\$	9,928.89	\$	3,772.98	\$	2,085.07	\$	4,070.84
Construction Subtotal		\$	2,378,142.47	\$	708,066.50	\$	608,661.54	\$	1,061,414.43
Contingency		\$	1,189,071.24	\$	354,033.25	\$	304,330.77	\$	530,707.22
Total		\$	3,567,213.71	\$	1,062,099.75	\$	912,992.31	\$	1,592,121.65



SPLIT GAP 2 INTO 3 PHASES:

PHASE 1 - BUILD EAST PORTION (FROM MAIN ST TO BATESTOWN RD)

CONNECT TO EXISTING TOWN SIDEWALKS

WIDEN EXISTING SIDEWALKS TO SHARED USE PATH WIDTH AND CONNECT USERS TO MAJOR POINTS OF INTEREST INCLUDING WEEMS-BOTTS MUSEUM, CHURCHES, HISTORICAL MARKERS, SCHOOL, CEMETARY, ETC

PHASE 2 - BUILD CENTER PORTION (FROM BATESTOWN RD TO VAN BUREN RD)
CONTINUE TRAIL FROM TOWN WEST ALONG BATESTOWN ROAD POTENTIAL ENVIRONMENTAL IMPACTS ALONG QUANTICO CREEK,
ANTICIPATED NEED FOR RETAINING WALLS AND/OR PARTIAL WOODED WALKWAY ALONG THE CREEK IN THIS AREA.

PHASE 3 - BUILD WEST PORTION (FROM VAN BUREN RD TO PARK)
HIGH/HIGHER COST ITEMS INCLUDING THE NEW PEDESTRIAN BRIDGE OVER

QUANTICO CREEK


CONNECT TO PRINCE WILLIAM FOREST PARK WOULD REQUIRE CLEARING AND GRADING FOR PATH CONSTRUCTION

COORDINATION WITH PARK FOR TRAIL CONNECTION

POTENTIAL NEED FOR RIGHT OF WAY

<u>LEGEND</u> PHASE 1 PHASE 2 PHASE 3

GAP 2 - PREFERRED ALIGNMENT - OVERALL PLAN



Gap 2	Gap 2			Alignment 1 (Overall length = 5110')						
Construction (CN) Ph	ase:	Ext	ended Cost	Pha	ise 1	Phase 2			ase 3	
Mobilization/Constr St	urvey									
513SD20-0001	Mobilization	\$	141,000.00	\$	53,580.00	\$	29,610.00	\$	57,810.00	
517SD20-0001	Constuction Surveying	\$	23,000.00	\$	8,740.00	\$	4,830.00	\$	9,430.00	
Roadway										
	Roadway Defined Item Subtotal	\$	602,075.00	\$	334,885.00	\$	175,145.00	\$	92,045.00	
Hydraulics										
	Hydraulics Defined Item Subtotal	\$	68,525.00	\$	13,455.00	\$	34,070.00	\$	21,000.00	
Traffic										
	Traffic Defined Item Subtotal	\$	8,128.00	\$	8,128.00	\$	-	\$	-	
Structures/Bridges										
	Structures/Bridges Defined Item Subtotal	\$	1,047,800.00	\$	133,000.00	\$	238,000.00	\$	676,800.00	
Earthwork/Geotech										
	Earthwork/Geotech Defined Item Subtotal	\$	259,250.00	\$	69,500.00	\$	79,050.00	\$	110,700.00	
Allowances	Stormwater Management Allowance	\$	39,715.56	\$	15,091.91	\$	8,340.27	\$	16,283.38	
	MOT	\$	148,933.35	\$	56,594.67	\$	31,276.00	\$	61,062.67	
	Roadside Development (Minimal RD, Grass)	\$	29,786.67	\$	11,318.93	\$	6,255.20	\$	12,212.53	
	Signage	\$	9,928.89	\$	3,772.98	\$	2,085.07	\$	4,070.84	
Construction St	ubtotal	\$	2,378,142.47	\$	708,066.50	\$	608,661.54	\$	1,061,414.43	
Contingency		\$	1,189,071.24	\$	354,033.25	\$	304,330.77	\$	530,707.22	
Total		\$	3,567,213.71	\$	1,062,099.75	\$	912,992.31	\$	1,592,121.65	

AUTHOR: CHECK: PROJ.#: DATE: 007078 FEB 2025

SHEET



VDOT Project No.:		UPC No:	UPC No:			Location: PWC			
Description: PHNST Gap Area Feasibility Studies (Areas 1, 2, 3)		HNST Gap Area Feasibility Studies (Areas 1, 2, 3)	Phase:			Design Originator: ATCS/Prince William Co. – Parks & Rec			
	Review Commo					Response		Final Disposition	
Item	Page	Name: Heidi Mitter Discipline: VDOT Transportation Planning Date: 9/19/2025	cipline: VDOT Transportation Planning Discipline: Planning Manager, PWC DPR		Manager, PWC DPR		Name: Discipline: Date:		
	No.	By VDOT Reviewer 1. Requirement 2. Recommendation 3. Clarification		Code	A. Agree with Comment (Document Will Be Revised) B. Comment To Be Evaluated (by Whom) C. Disagree with Comment (Provide Justification)		Code		
PHNST	Γ Gap Area	a 1 Study – Belmont Bay to Town of Occoquan							
1	23	Regarding Alt 1.3 not meeting access/mobility: new deve Annapolis Way/Destination PI. will have – or already have facilities that link residents to the PHNST/Route 123 - and P&R is not precluded with Alt. 1.3 - so it is unclear how p have nearby Trail access with Alt. 1.3.  The presence of facilities already built (or approved to be improve/modify the cost estimates (shown on page 36).	e- pedestrian/bike d a connection to the eople would not	3	Acknowledged. Evaluat based on consultant's a conditions. No change t	analysis of existing			
2	Regarding the sentence "Alternative 1.1 is adjacent to high volume roadways on Gordon Boulevard from Annapolis Way to Devils Reach Road.  Otherwise, it is on shared use paths or low volume roads." – if this is just referencing current conditions, please clarify (as it is noted there will be SUP there when current construction is finished).		3	Acknowledged. This is a conditions. No change to					
3	31	It <i>does</i> appear challenging to get the trail from under I-95 given the geographic/topographic constraints and private parcel(s).	to Swan Point Rd residential	3	Acknowledged. This is conditions. No change to				
4	33	Regarding "several sections will be constructed in the collapproved and funded County roadway improvement projects".		3	DPR acknowledges this does not believe it alter report. No change to re	s the final outcome of the			

Form Revised 7-15-2015 Page 1 of 4

DOT Project No.:	UPC No:	Location: PWC
201110,000111011	0. 0.10.	

Description: PHNST Gap Area Feasibility Studies (Areas 1, 2, 3) Phase: Design Originator: ATCS/Prince William Co. – Parks & Rec

		Review Comment	Response		Final Disposition		
Item	Page No.	Name: Heidi Mitter Discipline: VDOT Transportation Planning Date: 9/19/2025		Name: Patti Pakkala Discipline: Planning Manager, PWC DPR Date: 10/8/2025	Name: Discipline: Date:		
	110.	By VDOT Reviewer 1. Requirement 2. Recommendation 3. Clarification	Code	A. Agree with Comment (Document Will Be Revised) B. Comment To Be Evaluated (by Whom) C. Disagree with Comment (Provide Justification)			
5	33	Regarding the selection of Alt 1.1 as the recommended alignment but showing Alt 1.2 as the long-term vision and showing it as the alignment in the comprehensive plan: this will likely create confusion. As capital projects come along, they will consult the Comprehensive Plan alignment, which is the document for long-range plans for trails/roads. This study is saying there's a difference between the preferred alignment and the long-range plan/vision. Please clarify how that will work. (Will the comp plan be updated in the next round to show Alt 1.1?)	1	Acknowledged. The scope of this report was to identify a route that is currently most feasible, which is the recommended alignment. For this gap the "Long Term Recommendations" paragraph was added at the direction of the DPR Director to address stakeholder desires to continue to pursue waterfront opportunities in this area of the County should they arise in the future. DPR will work with County Planning staff to clarify how this is shown in future updates of the Comprehensive Plan. No change to report.			
6	34	Regarding the use of cost estimating materials: Thank you for consulting the VDOT cost estimating manual and procedures. It is noted that VDOT (at least transportation planning) will not be verifying any cost estimating work.	3	Acknowledged. Cost estimates were done as part of the scope of work for this project and are intended to be purely for planning purposes. No change to report.			
7	36	The study could consider a narrower/lighter facility for Poplar Lane than a shared use path given the low speed/low volume residential context	2	Acknowledged. This will be evaluated further when DPR/County pursue completion of the PHNST through this area (design and construction). A shared use path was evaluated in this study in an effort to provide trail consistency, to the greatest extent possible. No change to report.			
8	Gen	Prince William Co. DOT's planned Old Bridge Road/Route 123 interchange project may impact some of the trail concept, like at Sea Ray Lane.	3	Acknowledged. This is an evaluation of current conditions. Additional analysis will be undertaken with each phase of implementation. No change to report.			

PHNST Gap Area 2 Study – Town of Dumfries

Form Revised 7-15-2015 Page 2 of 4

VDOT Project No.:		UPC No:	UPC No:			Location: PWC			
Description: PHNST Gap Area Feasibility Studies (Areas 1, 2, 3)		Phase:			Design Originator: ATCS/Prince William Co. – Parks & Rec				
		Review Comment				Response		Final Disposition	
Item	Page No.	Name: Heidi Mitter Discipline: VDOT Transportation Planning Date: 9/19/2025			Name: Patti Pakkala Discipline: Planning I Date: 10/8/2025	Manager, PWC DPR		Name: Discipline: Date:	
	No.	By VDOT Reviewer 1. Requirement 2. Recommendation 3. Clarification		Code	Revised)	nent (Document Will Be Evaluated (by Whom) mment (Provide	Code		
1	General	Please consult VDOT IIM-TE-384.1 for future crossings a locations, especially at locations like crossing Route 1	t unsignalized	1	Acknowledged. All pertinent roadway design standards will be considered as DPR/County pursue completion and build-out of the recommended alignment (i.e. formal design and construction). This is simply a feasibility study. No change to report.				
PHNST	⊺Gap Area	a 3 Study – Interstate 95 and Joplin Road							
1	19	Regarding the construction of the pedestrian tunnel: This further evaluated by VDOT Structure & Bridge section if/v moves forward.	would have to be when this design	1		consultant and Ige additional review will ase moves through Design			
2	20	Please clarify how a shared use path would fit alongside 95 considering the sloping bridge abutments, drainage fe constrained space. Has a 'raised walkway' per the conce before in this setting?	atures, and	3	Consultant is familiar with a similar "raised walkway" enhancement made at the I-90/State Rt 18 interchange in Washington State and believes similar modifications could be made along Joplin Rd to accommodate the trail alignment. No change to report.				
3	20	Regarding crossings at/around I-95 ramps: Paths built in of-way, like interstate right of way, may have to go throug process for a change in the limited access line.	limited access right- h a CTB approval	2	Acknowledged. DPR/Conecessary approvals as development proceeds.	each phase of			

Form Revised 7-15-2015 Page 3 of 4

VDOT Project No.:	UPC No:	Location: PWC
Description: PHNST Gap Area Feasibility Studies (Areas 1, 2, 3)	Phase:	Design Originator: ATCS/Prince William Co. – Parks & Rec

		Review Comment		Response	Final Disposition	
Item	Page No.	Name: Heidi Mitter Discipline: VDOT Transportation Planning Date: 9/19/2025		Name: Patti Pakkala Discipline: Planning Manager, PWC DPR Date: 10/8/2025		Name: Discipline: Date:
	NO.	By VDOT Reviewer 1. Requirement 2. Recommendation 3. Clarification	Code	A. Agree with Comment (Document Will Be Revised)     B. Comment To Be Evaluated (by Whom)     C. Disagree with Comment (Provide Justification)	Code	
4	Gen	Please consult VDOT IIM-TE-384.1 for future crossings at unsignalized locations, including for mitigations or other features may need to be included.	1	Acknowledged. All pertinent roadway design standards will be considered as DPR/County pursue completion and build-out of the recommended alignment (i.e. formal design and construction). This is simply a feasibility study. No change to report.		

Form Revised 7-15-2015 Page 4 of 4