

# PROJECT ADMINISTRATORS HANDBOOK



#### Introduction

#### Project Administrator's Handbook

This handbook is a reference guide for those members of Prince William County staff, who are involved in the process of managing and contributing to the completion of Capital Improvement Projects. Its purpose is to provide a ready reference to all project managers to ensure that projects are properly coordinated and that no steps of the process are missed. Its focus is global to meet the needs of the seasoned project administrator as well as the new-comer to the Prince William County way of project administration. The handbook includes details of the steps that are to be followed as staff plans for a project, coordinates with organizations within the County government, involves citizens, and selects and works with designers, engineers, general contractors, and others in the construction process. The handbook is meant to satisfy the needs of all types of projects including roads, buildings, and landscaping and provides some clarification as to the differences in administration between the types of projects.

The handbook consists of four sections. The first section is the Process List. This is a sequential listing of each process used in the overall administration of a Capital project, including areas of commonality between transportation projects and facility construction projects. Section Two provides detailed descriptions of each process. Section Three contains an appendix with a glossary, list of abbreviations, agency structures, external contracts, list of forms, and list of other materials. Section Four is a list of the most recent revisions of each section of the Handbook.

The Handbook is a living document and is subject to frequent updating to keep current with changing budget, purchasing, legal guidance, and construction codes. Users of the manual, noting inconsistencies, should highlight concerns and submit them to the Department of Transportation, Mail Code DS990, (addressed to the Project Administrators Handbook Team) for revision.



## **Project Administrators Handbook**Table of Contents

Section 1
Process List



Section 2 Process Descriptions

Section 3 Appendix

Section 4
Revision List



**Project Administrators Handbook** 

#### **Capital Projects Process List**

| Process   | Buildings | Parks                                 | Roads    | Section |
|---|-----------|---------------------------------------|----------|---------|
| Project Kick-off  |           |                                       |          |         |
| Kick-off  | √         | <b>√</b>                              | <b>√</b> | 2.1.1   |
| Planning Commission   | <b>√</b>  | <b>√</b>                              |          | 2.1.2   |
| Architectural Review Board  | <b>√</b>  |                                       |          | 2.1.3   |
| Appoint A/E Selection Committee   | <b>√</b>  | <b>√</b>                              | <b>√</b> | 2.1.4   |
| Design Scope of Work  | <b>√</b>  |                                       | <b>√</b> | 2.1.5   |
| Request for Proposal (RFP)  | <u>√</u>  | <u> </u>                              |          | 2.1.6   |
| Design  |           | · ·                                   | -        |         |
| Programming   | <b>√</b>  | <b>√</b>                              |          | 2.2.1   |
| Public Hearings   | <u>√</u>  |                                       | <b>√</b> | 2.2.2   |
|   | ✓         | ✓                                     |          | 2.2.3   |
| Public Information Meeting  | ✓         | ✓                                     | ✓        |         |
| Alternative Analysis  | ✓         | <u>√</u>                              |          | 2.2.4   |
| Contract Modifications  Design Field Insecretion                                    |           | <b>√</b>                              | <u>√</u> | 2.2.5   |
| Design Field Inspection   |           |                                       | <b>√</b> | 2.2.6   |
| Schematics 5  | <b>√</b>  |                                       |          | 2.2.7   |
| Environmental Impact Studies  | <u>√</u>  |                                       |          | 2.2.8   |
| Environmental Permitting  | <b>√</b>  |                                       | ✓        | 2.2.9   |
| Procure Interior Design   | <u>√</u>  |                                       |          | 2.2.10  |
| Task Order  | <u>√</u>  | <b>√</b>                              | ✓        | 2.2.11  |
| Interiors   | <b>√</b>  | <b>√</b>                              |          | 2.2.12  |
| Design Development (Buildings & Parks)  | ✓         | ✓                                     |          | 2.2.13  |
| Design Development (Roads)  |           |                                       | <b>√</b> | 2.2.14  |
| Site Permitting   | ✓         | √                                     |          | 2.2.15  |
| Survey  | √         | ✓                                     | ✓        | 2.2.16  |
| Plat Preparation  | ✓         | ✓                                     | ✓        | 2.2.17  |
| Construction Documents  | ✓         | ✓                                     | ✓        | 2.2.18  |
| Building Permit Review and Permitting   | √         | ✓                                     | ✓        | 2.2.19  |
| Invoices  | √         | ✓                                     | ✓        | 2.2.20  |
| Construction  |           |                                       |          |         |
| Invitation for Bid (IFB)  | √         | ✓                                     | ✓        | 2.3.1   |
| Change Order  | √         | <b>√</b>                              | ✓        | 2.3.2   |
| Request for Payment   | √         | <b>√</b>                              | <b>√</b> | 2.3.3   |
| Draw Downs for Bond or Lease-Funded Projects  | ✓         | <b>√</b>                              | <b>√</b> | 2.3.4   |
| Withholding and Releasing Retainage   | <b>√</b>  | <b>√</b>                              | ✓        | 2.3.5   |
| Withholding and Releasing Retainage (Design-Build)                                  |           |                                       | ✓        | 2.3.5-B |
| Construction Inspection   |           |                                       | <b>√</b> | 2.3.6   |
| Commissioning   | ✓         |                                       |          | 2.3.7   |
| Construct (Buildings & Parks)   | <b>√</b>  | <b>√</b>                              |          | 2.3.8   |
| Construct (Roads)   |           |                                       | <b>√</b> | 2.3.9   |
| Punchlist Walk Through (Buildings)  | √         | <b>√</b>                              |          | 2.3.10  |
| Punchlist Walk Through (Roads)  |           |                                       | <b>√</b> | 2.3.11  |
| Construction Information on Social Media  | <b>√</b>  | <b>√</b>                              | <b>√</b> | 2.3.12  |
| Procure & Install Furniture & Equipment   |           | · · · · · · · · · · · · · · · · · · · | -        | 2.3.13  |
| Procure & Install OIT Data and Telecom Wiring                                       |           | <b>√</b>                              |          | 2.3.14  |
| Internal Forces Road Construction   | •         | -                                     | <b>√</b> | 2.3.15  |
| Design-Build Two Phase Selection RFQ and RFP  |           |                                       |          | 2.3.16  |
| Active Construction Projects Lane Shift or Lane Closure Public Notification Process |           |                                       |          | 2.3.17  |



#### **Capital Projects Process List**

| Process   | Buildings | Parks    | Roads    | Section |
|---|-----------|----------|----------|---------|
| Close-out   |           |          |          |         |
| Final Occupancy   | ✓         | √        |          | 2.4.1   |
| Acquire Insurance   | ✓         | ✓        |          | 2.4.2   |
| Warranty Period   | ✓         | ✓        |          | 2.4.3   |
| VDOT Street Acceptance  |           |          | ✓        | 2.4.4   |
| Special Event/Ribbon Cutting                                    | ✓         | ✓        | ✓        | 2.4.5   |
| Plat Development  | ✓         | <b>√</b> |          | 2.4.6   |
| Release of Liens  | ✓         |          |          | 2.4.7   |
| Accounting Project Close-Out                                    | ✓         | <b>√</b> | ✓        | 2.4.8   |
| VDOT Audit  |           |          | ✓        | 2.4.9   |
| Transition of Operating Budget                                  | ✓         | ✓        |          | 2.4.10  |
| Utility Relocation  |           |          |          |         |
| Identify Existing Utilities and Conflicts                       |           |          | <b>√</b> | 2.5.1   |
| Negotiate Fee Arragement  |           |          | <b>√</b> | 2.5.2   |
| Acquire Easements   |           |          | <b>√</b> | 2.5.3   |
| Upgrades (Betterments)  |           |          | <b>√</b> | 2.5.4   |
| Request/Authorize Work  |           |          | <b>√</b> | 2.5.5   |
| Dispose of Old Material   |           |          | <b>√</b> | 2.5.6   |
| Relocation of Utilities   |           |          | <b>√</b> | 2.5.7   |
| Land Acquisition  |           |          |          |         |
| Land Acquisition Overview                                       |           |          | <b>√</b> | 2.6.1   |
| Title Search  |           |          | <b>√</b> | 2.6.2   |
| Receive Plat  |           |          | <b>√</b> | 2.6.3   |
| Secure Appraisal  |           |          | <b>√</b> | 2.6.4   |
| Make the Offer  |           |          | <b>√</b> | 2.6.5   |
| Negotiate   |           |          | <b>√</b> | 2.6.6   |
| Settlement  |           |          | √        | 2.6.7   |
| Condemnation (Quick-Take)                                       |           |          | √        | 2.6.8   |
| Court Preceeding  |           |          | √        | 2.6.9   |
| Project Administration  |           |          |          |         |
| Determining Debt Sale Amount and Timing                         | ✓         | <b>√</b> | <b>√</b> | 2.7.1   |
| Bond/Lease Sale   | <b>√</b>  | <b>√</b> | <b>√</b> | 2.7.2   |
| Arbitrage Process   | <b>√</b>  | <b>√</b> | <b>√</b> | 2.7.3   |
| Post-Sale Debt Maintenance                                      | √ ·       | <b>√</b> | <b>√</b> | 2.7.4   |
| Budget Transfer   | <b>√</b>  | <b>√</b> | <b>√</b> | 2.7.5   |
| Internal Payment for Development Service Fees (Journal Entries) |           |          | <b>√</b> | 2.7.6   |
| Other Administrative  |           |          |          |         |
| Board Agenda  | ✓         | <b>√</b> | <b>√</b> | 2.8.1   |
| Life Cycle Management   | <u>√</u>  | <u> </u> | -        | 2.8.2   |





# KICK-OFF OVERVIEW Kick-off Buildings Parks Roads ✓

## Process Owner Directors

Parks & Recreation Public Works Transportation

#### **Process Manager**

**Project Managers** 

Parks & Recreation
Public Works
Transportation

#### Description

This section provides an overview of the kick-off process, which initiates implementation of the project. The project has an approved budget and is ready to be implemented.

Prior to beginning the design process, the scope, budget, and other parameters of the project must be established . A contract must be negotiated with a consultant. This contract must be in compliance with County Purchasing rules and regulations. The consultant will be selected and approved by the user committee, submitted to purchasing for contract preparation and final review and subsequently awarded by the BOCS.

#### **Contacts & Roles: Organization, Entity, or Individual**

- ♦ County Department Project management.
- ♦ **Budget and Finance** Establish project budget.
- ♦ Citizens Customers, users.
- ♦ Employees Customers, users.
- ♦ A/E Consultant Supplier.
- ♦ Project Vendors Suppliers.
- ♦ **Boards and Commissions** Other involved governmental agencies (e.g., Library Board, Adult Detention Center, Courts, Sheriff).
- ♦ **Purchasing** Solicits and awards contracts.
- ♦ **BOCS** Approves contract.

#### **Timelines: Deadlines, Critical Path Items**

- ♦ **Project Budget** Budget must be established prior to kick-off.
- **♦ Scope of Work**
- ♦ Issue RFP (Proposal Evaluation)
- **♦ Award Contract**
- **♦ Hire A/E consultant**

#### Materials Forms

- ♦ Appointment letter
- ♦ Request for Proposal (RFP)


♦ Planning Level Cost Estimate



#### **Reference to Other Processes**

- ♦ Precedes 2.2.13 Design Development (Buildings and Parks)
- ♦ Precedes 2.2.14 Design Development (Roads)

#### **Process Notes**






| PLANNING COMMISS Kick-off                              | ION  | Buildings<br>Parks<br>Roads | <b>2.1.2</b> |
|--|--|-----------------------------|--------------|
| Process Owner Director                                 | <b>Description</b> As part of the initial CIP budget process, the Plan reviews projects to ensure they are included in the | •                           |              |
| Office of Planning                                     | Comprehensive Plan.  During the early phases of a project design, a request for a Public                                   |                             |              |
| <b>Process Manager</b>                                 | Facilities Determination (PFD) is sent to the Planr a location/site map and description of the facility                    | •                           |              |
| Project Manager  | determines that the facility is in conformance with  | •                           |              |
|  | comprehensive plan, no further action is needed. If the Planning Office  |                             |              |
| County Department                                      | does not approve the public facility review, it is then submitted to the   |                             |              |
| Planning Commission to amend the comprehensive plan.   |  |                             |              |
| ♦ Planning Office – Manages P                          | ganization, Entity, or Individual ublic Facilities Review (PFR) process.   |                             |              |
| ♦ County Department – Provid                           | • •  |                             |              |
| ◆ Planning Commission – Revi                           | ews public facilities for conformance to the compr   | ehensive plan.              |              |
| Timelines: Deadlines,  ♦ Permit – PFR must occur price |  |                             |              |
|  |  |                             |              |
| Materials  | Forms  |                             |              |
| None   | None   |                             |              |
|  | Public Facilities Review Application   |                             |              |
| Reference to Other P                                   | rocesses   |                             |              |

### **Process Notes**

♦ Precedes 2.2.7 Schematics

♦ Precedes 2.2.15 Site Permitting







| ARCHITECTUAL REVIEW Kick-off  | EW BOARD   | <b>2.1.3</b> Buildings ☑ Parks ☐ Roads ☐                          |
|---|--|---|
| Process Owner Director  Office of Planning  Process Manager Project Manager | Description  Use of the Architectural Review Board (ARB) is raprojects and is usually only done as a matter of conformation only. Projects are taken to the Architon a case-by-case basis and are generally present in special districts, are of special interest, or are less than the conformation of the Architecture of the conformation of the Architecture of the Carlotte of the Architecture of the Carlotte of the Ca | ourtesy for<br>tectural Review Board<br>ted for projects that lie |
| ♦ Department Project Manage   | ganization, Entity, or Individual<br>er – Prepares material for ARB.<br>– Reviews projects when deemed appropriate.  |   |
| Timelines: Deadlines,   | Critical Path Items on of RFP when deemed necessary.  Forms None   |   |
| Reference to Other P  • Precedes 2.1.6 Request for P                        | rocesses   |   |



| APPOINT A/E SELECTION COMMITTEE |           | 2.1.4                   |
|---------------------------------|-----------|-------------------------|
|                                 | Buildings | $\checkmark$            |
| Kick-off                        | Parks     | $\overline{\checkmark}$ |
|                                 | Roads     |                         |

#### **Process Owner County Executive**

Executive Management

#### **Process Manager Project Manager**

**Public Works** Parks & Recreation **Transportation** 

#### **Description**

Prior to the start of any CIP project, a team needs to be assembled to review architectural/engineering proposals submitted for the specific project and to recommend the selection of the consultant. The committee is made up of various members of county government who have a vested interest in the project, and depending on whether it's a Public Works project, includes the county architect or a Transportation Project. The Project Manager's role is to facilitate the process.

Names of potential committee members are forwarded via a letter to the County Executive for final approval and appointment. Once the list is approved, the Project Manager forwards a letter of appointment, along with a schedule of anticipated activities, to the selected members. Many of these members are often appointed as user members during the design process also.

#### **Contacts & Roles: Organization, Entity, or Individual**

♦ **Purchasing** – Where an RFP is required, a selection committee must be established.

#### Timelines: Deadlines, Critical Path Items

♦ A/E Selection Committee must be appointed prior to Solicitation.

#### **Materials Forms**


- ♦ Appointment letter
- ♦ Request letter
- ♦ Request for Proposal (RFP)

♦ Solicitation Committee CXO Memo

#### Reference to Other Processes

♦ Precedes 2.1.6 Request for Proposal







| DESIGN SCOPE OF WORK |           | 2.1.5                   |
|----------------------|-----------|-------------------------|
|                      | Buildings | $\checkmark$            |
| Kick-off             | Parks     | $\overline{\checkmark}$ |
|                      | Roads     | $\checkmark$            |

## Process Owner Director

Parks & Recreation Public Works Transportation

#### Process Manager Project Managers

Parks & Recreation
Public Works
Transportation

#### **Description**

During the CIP process, a preliminary Scope of Work (SOW) is developed for the project as part of the project description. Because a project can be in the CIP for a number of years before it begins, the scope needs to be thoroughly reviewed and modified prior to submitting to Purchasing for the formal Request for Proposal (RFP) by architects and/or engineers when estimated costs exceeds the purchasing regs for procurement through task order open ended contract.

This process includes reviewing the various stakeholders who will operate withing and maintain the facility and or the building, determining the special features the building may have (i.e., security systems, generators, etc.), identifying the site, and stating the needs that will be included in the project. Once this is completed, it is then forwarded to Purchasing along with a preencumbrance request andd Solicitation Information Form for the issuance of an RFP.

#### Contacts & Roles: Organization, Entity, or Individual

- Public Works Coordinate and gather information on various aspects and needs of the project. This will primarily include Buildings and Grounds, Property Management, Environmental Services and Fleet Management.
- ♦ **Transportation** Coordinate and gather information on various aspects and needs of the project. This will primarily include Planning & Programming, Capital Projects, Accounting and Fleet Management.
- ♦ **Users** Provide feedback to coordinating department on user needs.
- ♦ **VDOT and Utilities** Provide feedback to coordinating department on overall scope and utility impacts and relocation..
- ♦ A/E Consultant Consultants may be used in the process of creating the scope of work and preliminary concepts and plans.

#### **Timelines: Deadlines, Critical Path Items**

♦ Scope of Work (SOW) – SOW is needed for the issuance of a Request for Proposal (RFP) and task order. The Scope of Work is included in the RFP.

| Materials             | Forms |
|-----------------------|-------|
| ♦ Scope of Work (SOW) | None  |

#### **Reference to Other Processes**

♦ Precedes 2.1.6 Request for Proposal



| <b>Request for Proposal</b> | (RFP) |           | 2.1.6                   |
|-----------------------------|-------|-----------|-------------------------|
| •                           | ()    | Buildings | $\checkmark$            |
| Kick-off                    |       | Parks     | $\checkmark$            |
|                             |       | Roads     | $\overline{\checkmark}$ |
| D                           |       |           |                         |

#### Process Owner Purchasing

**Finance** 

#### **Process Manager Contract Specialist**

Purchasing, Finance

#### Description

A Request for Proposal (RFP) is a formal solicitation and is the purchasing mechanism used to acquire professional services where technical merit is the primary basis for award consideration. Factors such as quality, negotiated fees, availability, and offeror's capability can be award factors in the acquisition of services. An RFP is used for projects where an existing contract or open-ended professional cannot be utilized and for any project \$60,000 or above where an existing contract is not present. Existing County contracts have a threshold of \$500,000. EExisting open-ended professional County contracts have a threshold of \$2,000,000. [To acquire services under existing open-ended professional County contracts, go to the Task Order process (2.2.11).]

#### Contacts & Roles: Organization, Entity, or Individual

- ♦ **County Agency** Provide information as requested by Purchasing and distributes proposals.
- ◆ **Purchasing** Purchasing and contracts process oversight.
- ♦ **BOCS** Approves contract by resolution.

#### **Timelines: Deadlines, Critical Path Items**

#### **Materials Forms**


- ♦ Solicitation document
- ♦ Automated forms in ASCENDND

♦ Solicitation Information Form


#### Reference to Other Processes

- ♦ Follows 2.1.5 Design Scope of Work
- ♦ Precedes 2.2.1 Programming











| <b>Programming</b> Design                                 |  | Buildings<br>Parks<br>Roads | <b>2.2.1</b>      |
|---|--|-----------------------------|-------------------|
| <b>Process Owner</b>                                      | Description  |                             |                   |
| Public Works Parks & Recreation                           | The program lays out the levels of performance swhat it should do. It addresses the human physic influencing facility design. Also included are the    | cal and external external   | factors<br>ements |
| Process Manager Project Manager/Facilities Manager        | and standards, such as planning & zoning ordinal and other related regulations. It is during the prothe size and general character of the building are | gramming phas               | se that           |
| Public Works, Facilities Construction, Parks & Recreation |  |                             |                   |

#### **Contacts & Roles: Organization, Entity, or Individual**

- ♦ **Users** To provide specific information.
- ♦ **Buildings & Grounds (B&G)** May provide technical information on the building systems, and subsequent operations.
- ♦ Property Management To provide specific information on space standards, furniture, and interior finishes.
- ♦ A/E Consultant Provide technical expertise.
- ♦ Facilities Construction Management (FCM) Provide overall guidance and coordination with all user agencies and technical support.
- ♦ Office of Information Technology (OIT) Provide technical information with data and telephones.
- ♦ Environmental Services Provide information concerning Resource Protection Areas (RPA), etc.


#### **Timelines: Deadlines, Critical Path Items**

- **♦ Resource Protection Areas**
- **♦** Geotechnical Report

| Materials             | Forms |
|-----------------------|-------|
| ♦ Geotechnical Report | None  |
| ♦ Building Program    |       |

#### **Reference to Other Processes**







| Public Hearings Design                           |  | Buildings<br>Parks<br>Roads | 2.2.2<br>☑<br>☑ |
|--|--|-----------------------------|-----------------|
| Process Owner                                    | Description  |                             |                 |
| Clerk  | A Public Hearing is a meeting held by the County   | •                           |                 |
| BOCS<br>VDOT                                     | comment on proposed or ongoing projects. [For Public Hearing is required, see 'Process Notes' be |                             | hich a          |
| <b>Process Manager</b>                           |  |                             |                 |
| Project Managers                                 |  |                             |                 |
| Parks and Recreation Public Works Transportation |  |                             |                 |

#### **Contacts & Roles: Organization, Entity, or Individual**

- ♦ **Project Manager** prepares documentation for a public hearing.
- **♦** County department
- ♦ Clerk's Office
- ♦ BOCS authorizes and holds Public Hearing.

#### **Timelines: Deadlines, Critical Path Items**

- **♦ BOCS approves Public Hearing**
- **♦ Advertise Public Hearing**
- ♦ Draft BOCS Agenda Item to approve final design

| Materials                             | Forms |
|---------------------------------------|-------|
| ♦ BOCS Agenda Item for Public Hearing | None  |

#### **Reference to Other Processes**

Precedes 2.2.13 Design Development (Buildings and Parks)

Precedes 2.2.14 Design Development (Roads)


#### **Process Notes**

A Public Hearing may be required—

- ♦ when determined by the Planning Office as part of a Public Facilities Review;
- when an alternative selection is needed;
- when property acquisition is needed;
- ♦ when a utility needs to be relocated;
- or, when a Public Information Meeting has not been conducted. Not all CIP building projects require a Public information meeting. It is on a case-bycase basis.



#### Flow Chart (Process A – Locally Funded Project)





#### Flow Chart (Process B – State Funded Project)

| Task/Submittal/File                                      | Locality Responsibility               | VDOT Project                  | Submittal                    |
|--|---------------------------------------|-------------------------------|------------------------------|
| Documentation  |                                       | Coordinator                   | Timing/Recordkeeping         |
|  |                                       | Responsibility                | Requirements                 |
| Determination of public                                  | Prepare and submit to                 | Concur with locality decision | @ Scoping                    |
| participation requirements                               | Project Coordinator                   |                               |                              |
| Notice of Public Hearing in                              | Post and send notice to               | N/A                           | Not less than 30 days prior  |
| newspaper (2x) and posting                               | Project Coordinator                   |                               | to PH approximately one      |
|  |                                       |                               | week prior to Public Hearing |
| Notice of Willingness to                                 | Post and send notice to               | Project Coordinator reviews   | Not less than 15 days prior  |
| Hold a Public Hearing in                                 | Project Coordinator                   | for completeness. Support is  | to the expiration of         |
| newspaper (2x) and other                                 |                                       | available                     | willingness period and       |
| appropriate notifications                                |                                       |                               | approximately one week       |
|  |                                       |                               | prior to expiration date of  |
|  |                                       |                               | willingness.                 |
| Draft of Project information                             | Prepare and submit to                 | Project Coordinator Reviews   | 30 days prior to hearing     |
| Sheet(s) section 3.03 and                                | Project Coordinator                   | for completeness. Support is  |                              |
| Appendix A-1 of the Public                               |                                       | available from Public Affairs |                              |
| Involvement Manual                                       |                                       | office If needed.             |                              |
| includes a listing of the                                |                                       |                               |                              |
| suggested documents for                                  |                                       |                               |                              |
| Public Information                                       |                                       |                               |                              |
| session/Public Hearing.                                  | 21/2                                  |                               | 101                          |
| Draft Project Information                                | N/A                                   | Review and provide            | 10 business days             |
| Sheet(s)   |                                       | comments to locality.         |                              |
|  |                                       | Support is available from     |                              |
|  |                                       | Public Affairs office if      |                              |
| First Project Information                                | Donata de la colonia de la colonia de | needed.                       | E deve orden te beseine      |
| Final Project Information                                | Prepare for public hearing            | N/A                           | 5 days prior to hearing      |
| Sheet(s)   | N/A                                   | N/A                           | N/A                          |
| Conduct the Public Hearing-<br>Section 3.05 and Appendix | N/A                                   | IN/A                          | N/A                          |
| A-3 of the Public  |                                       |                               |                              |
| Involvement Manual                                       |                                       |                               |                              |
| provides guidance on                                     |                                       |                               |                              |
| holding a Public Hearing                                 |                                       |                               |                              |
| PH Transcript Appendix A-5                               | Prepare and submit to                 | Process in accordance with    | Prepared and submitted to    |
| (Transcript Submission) of                               | Project Coordinator                   | Tiered Project oversight      | VDOT Project Coordinator     |
| the Public   | 1 roject eooramator                   | process.                      | 15 days after close of       |
| the rabile   |                                       | process.                      | written comment period;      |
|  |                                       |                               | final comments provided to   |
|  |                                       |                               | LPA within 15 days of their  |
|  |                                       |                               | submittal                    |
| Location and/or design                                   | N/A                                   | Commonwealth                  | 45 days for Commonwealth     |
| approval in accordance with                              | ,                                     | Transportation Board for      | Transportation Board         |
| Tier 1/ Tier 2 processes and                             |                                       | location, Chief engineer for  | approval, 30 days for design |
| VDOT's Public Involvement                                |                                       | design                        | approval                     |
| Manual, Location and/or                                  |                                       |                               |                              |
| Design Approval Flow                                     |                                       |                               |                              |
| Charts.  |                                       |                               |                              |
| 1  | 1                                     | 1                             | 1                            |

Process retrieved from – LAP Manual, Project Development VDOT



| Public Information Meeting |           | 2.2.3                   |
|----------------------------|-----------|-------------------------|
|                            | Buildings |                         |
| Design                     | Parks     | $\checkmark$            |
|                            | Roads     | $\overline{\checkmark}$ |

## Process Owner Directors Description

The Public Information Meeting process is recommended when citizens are impacted by the project. The meeting is conducted to obtain citizens' feedback. Generally the meeting is held at about 30% and 60% of design completion. The District Supervisor attends the informational meeting.

# Process Manager Project Managers

Parks & Recreation, Public Works & Transportation

Parks & Recreation

Public Works &

#### **Contacts & Roles: Organization, Entity, or Individual**

- ♦ **District Supervisor** Attends the meeting.
- ♦ Public Works/Transportation Director Conducts the meeting.
- ♦ Citizens Provide feedback.
- ♦ A/E Consultant Explains the project.
- ♦ **Public Works/Transportation Staff** Attend the meeting to answer questions.

#### **Timelines: Deadlines, Critical Path Items**

#### Materials Forms


Letters to citizens

♦ Prince William Department of Transportation Web

#### **Reference to Other Processes**

Occurs throughout 2.2.13 Design Development (Buildings and Parks) Occurs throughout 2.2.14 Design Development (Roads)







| <b>Alternative Analysis</b> |             |           | 2.2.4                   |
|-----------------------------|-------------|-----------|-------------------------|
| •                           |             | Buildings | $\overline{\checkmark}$ |
| Design                      |             | Parks     |                         |
|                             |             | Roads     | $\overline{\mathbf{A}}$ |
| <b>Process Owner</b>        | Description |           |                         |

Parks & Recreation, Public Works & Transportation

Directors

#### Process Manager Project Managers

Parks & Recreation, Public Works & Transportation Alternative analysis is the opportunity for BOCS and the public to respond to alternatives in the project. In the case of roads, it may be a particular alignment; in the case of buildings, it may be location, scale, and character of the proposed facility. A number of variables can be

determined in the alternative analysis. Approval of a preferred alternative allows the architectural or engineering services to proceed to final design.

#### **Contacts & Roles: Organization, Entity, or Individual**

- ♦ A/E Consultant Provide design, recommendations, and any materials needed for BOCS decision.
- ♦ **BOCS** Makes selection of alignment for Roads, and determination of building character on caseby-case basis.
- ♦ Citizens Provide feedback at Public Information Meetings.
- ♦ **Utility Companies** Provide locations and impact of location on project.
- ♦ VDOT Provides technical support for road alignments.
- ♦ Other County Agencies Provide technical support as needed.
- ♦ **Developer –** Provides coordination as needed with prospective road alignments.

#### **Timelines: Deadlines, Critical Path Items**

- ♦ Conceptual Plan Conceptual plan(s) should be in a format that can be presented in a public forum.
- ♦ Conduct Public Hearing/Public Information Meeting (Roads) For road alignment either a Public Information Meeting or Public Hearing must be conducted prior to BOCS selection of the alternative.
- ♦ BOCS Approval BOCS approval required for road alignment, but is optional for building character.
- ♦ Final Plans Submitted to VDOT (Roads) Once an alternative is selected the Project Manager can send plans to VDOT for approval.

| Materials                          | Forms |  |
|------------------------------------|-------|--|
| ♦ BOCS Staff Report and Resolution | None  |  |
| ♦ Transmittals                     |       |  |


#### **Reference to Other Processes**

Occurs throughout 2.2.2 Public Hearings
Occurs throughout 2.2.3 Public Information
Meeting Occurs throughout 2.8.1 Board Agenda



#### **Process Notes**

- ♦ Project should already have determined beginning and end.
- ♦ Project Manager should analyze project.
- ♦ Project Manager should come up with 3-4 possible alternatives.
- ♦ Project Manager should analyze all of the possible alternatives for traffic, right-of-way impact, etc.
- ♦ Project Manager should conduct Public Hearing.
- ♦ Project Manager should gather citizen input.
- ♦ Project Manager should present recommended alternative to BOCS.





| <b>Contract Modificatio</b> | ns  |           | 2.2.5                   |
|-----------------------------|---|-----------|-------------------------|
| Design                      |   | Buildings | $\overline{\mathbf{A}}$ |
| Design                      |   | Parks     | $\overline{\mathbf{V}}$ |
|                             |   | Roads     | $\overline{\checkmark}$ |
| <b>Process Owner</b>        | Description   |           |                         |
| Director                    | Changes to a contract for professional services are done through a  |           |                         |
| Finance                     | contract modification. Contract modifications occur when the consultant and County agree that additional work or compensation is  |           |                         |
| Process Manager             | needed to successfully design the project. Changes may occur as a result of a change in the original scope of work, specific unforeseen obstacles which require variation from the original plan, or the addition |           |                         |
| Project Manager             |   |           |                         |
| . roject manager            | of other features or options to the project.  | •         |                         |
| Parks & Recreation          |   |           |                         |

#### **Contacts & Roles: Organization, Entity, or Individual**

- ♦ A/E Consultant Requests and negotiates scope and cost of contract modification.
- ♦ **Departmental accounting staff** Verify availability of funds, processes the modification, and coordinates with Purchasing.
- ♦ Purchasing Review documentation, process, and approve purchase order increase and modification.
- ♦ **Project Manager** Initiates contract modification & sends to purchasing for courtesy review. Once approved, routed through contractor/consultant and then purchasing.

#### **Timelines: Deadlines, Critical Path Items**

- **♦** Purchasing approval
- **♦ BOCS approval**

Public Works & Transportation

| Materials                          | Forms                        |
|------------------------------------|------------------------------|
| ♦ Contract Modification            | ♦ Contract Modification Form |
| ♦ BOCS Staff Report and Resolution |                              |

#### **Reference to Other Processes**

Precedes 2.2.13 Design Development (Buildings) Precedes 2.2.14 Design Development (Roads) Occurs throughout 2.8.1 Board Agenda



- ♦ Any changes in design that are outside of the original scope of work need to be modified in writing.
- ♦ The Project Manager must obtain an estimate for the modifications.
- ♦ If approved, Project Manager sends to Purchasing.
- ♦ Purchasing will make the modifications to the County Formatted Modifications with all signature blocks.
- ♦ If the amount of the modification is within 25% of the original contract, then the Director or authorized designee may approve the modification.
- ♦ If the amount of the modification is more than 25% of the original contract, then it needs to go to BOCS.
- ♦ Every time there is a contract modification, the original amount will change to the original+ the modification amount or the original + any previous modification amounts + the new modification. So, 25% should be based on that amount which is original + all modifications unless a higher amount is approved by the BOCS.




#### **Flow Chart** Project Manager gets estimate for modifications Negotiate scope and costs of contract modifications. Are modifications No agreeable with County and consultant? Yes Send to Purchasing. Purchasing makes modifications to the County formatted modifications with all signature blocks. Amount of the Yes No modification is less than 25% of the original contract? Director or authorized designee Requires BOCS approval. approves. 2.8.1 Original amount changes to reflect addition of modification amount



| <b>Design Field Inspection</b> Design               | on  | Buildings<br>Parks<br>Roads | 2.2.6<br>_<br>_<br>_ |
|---|---|-----------------------------|----------------------|
| Process Owner Director Transportation               | <b>Description</b> When the design on a state and/or federal road complete all involved parties are invited to form As part of the review a field visit is conducted. |                             | project.             |
| Process Manager Project Manager                     |   |                             |                      |
| Transportation                                      |   |                             |                      |
| ♦ A/E Consultant – Works with                       | ganization, Entity, or Individual department staff to review design status. ith A/E consultant to review design status.   |                             |                      |
| Timelines: Deadlines,                               | Critical Path Items   |                             |                      |
| Materials  ♦ Transmittals                           | <b>Forms</b><br>None  |                             |                      |
| Reference to Other P Concurrent 2.2.14 Design Devel |   |                             |                      |







| <b>Schematics</b> Design        |  | Buildings<br>Parks<br>Roads  | <b>2.2.7</b> |
|---------------------------------|--|--|--------------|
| Process Owner Director          | <b>Description</b> The schematics phase takes the programming into | formation, issue   | es or        |
| Parks & Recreation Public Works | design goal, this incorporates internal functions,                 | stions, and puts them into a graphic/special study. By establishing a ign goal, this incorporates internal functions, human/vehicular and terial flow patterns, space allocations, analysis of operating |              |

#### **Process Manager**

**Facilities Construction Management Project** Manager **Public Works Facilities Manager** Parks & Recreation

functions, adjacencies, special facilities and equipment, material handling, flexibility and expandability. Schematic plans often include 1 to 2 alternate designs.

The primary objective of the schematics phase is to arrive at a clearly defined, feasible concept and present it in a way that the client can understand. A professional cost estimate is prepared as part of the approval process to ensure the project is within budget. If the budget is exceeded, then the schematic plans must be adjusted to comply with the approved budget.

#### Contacts & Roles: Organization, Entity, or Individual

- ♦ **Planning** To review & advise on possible (site) conflicts.
- ♦ **Building Development** To review & advise on building code issues.
- ♦ **Property Management (PM)** Reviews & approves for FFE application.
- ♦ Buildings & Grounds (B&G) Reviews and approves for operational issues.
- ♦ Facilities Construction Management (FCM) County architect reviews for compliance to standards and architectural aesthetics.
- ♦ Office of Information Technology (OIT) Reviews the technological aspects of the plan.
- ♦ Environmental Services Reviews schematic design for interference with RPA.

#### **Timelines: Deadlines, Critical Path Items**

♦ Review time – In-house review by users: Buildings & Grounds, Property Management, Environmental Services and Facilities Construction Management.


| Materials               | Forms |  |
|-------------------------|-------|--|
| Drawings by consultants | None  |  |
| ♦ Building Program      |       |  |

#### **Reference to Other Processes**

Precedes 2.2.2 Public Hearings



Schematics 2.2.7





| Design Buildings | <b>Environmental Impact Studies</b> |           | 2.2.8                   |
|------------------|-------------------------------------|-----------|-------------------------|
| Parks            | ·                                   | Buildings | $\checkmark$            |
|                  | Design                              | Parks     | $\overline{\checkmark}$ |
| Roads ☑          |                                     | Roads     | $\overline{\checkmark}$ |

## Process Owner Directors Description

Parks & Recreation Public Works & Transportation Environmental impact studies must be performed by the consultant to determine the impact of the project on streams, rivers, wild life, wetlands and other environmentally sensitive ecosystems.

#### **Process Manager**

**Project Managers** 

Parks & Recreation, Public Works & Transportation

#### **Contacts & Roles: Organization, Entity, or Individual**

- **♦ VDOT**
- **♦** Transportation
- **♦ Department of Environmental Quality (DEQ)**
- **♦ BOCS**
- **♦ Citizens**
- **♦ Developers**
- **Ounty Agencies**

#### **Timelines: Deadlines, Critical Path Items**

- **♦ VDOT/Transportation Review**
- ♦ 60% Plans
- **♦ NEPA Process**


**♦** Transmittals

**♦ Environmental Resource Survey** 

# Materials ♦ NEPA Permit ♦ VDOT

#### **Reference to Other Processes**







| <b>Environmental Permitting</b> |           | 2.2.9                   |
|---------------------------------|-----------|-------------------------|
|                                 | Buildings | $\checkmark$            |
| Design                          | Parks     | $\overline{\checkmark}$ |
|                                 | Roads     |                         |
|                                 |           |                         |

# Process Owner Directors Description

This section outlines a process for merging the elements of the NEPA permitting process relating to all County road bond and Capital Improvements Projects (CIP). This process assures the environmentally sound and effective development of major county, state or federally funded projects.

## Process Manager Project Managers

Parks & Recreation
Public Works &
Transportation

# **Contacts & Roles: Organization, Entity, or Individual**

- ♦ VDOT Review and approve.
- ♦ **Transportation** Review and approve.
- ♦ **Department of Environmental Quality (DEQ)** Review and approve.

# **Timelines: Deadlines, Critical Path Items**


- ♦ NEPA (National Environmental Policy Act) Preparation
- ♦ Prepare Finding of No Signification Impact (FONSI)
- ♦ Prepare Categorical Exclusion
- ♦ Prepare Environmental Impact Study (EIS)
- ♦ Prepare Record of Decision (ROD)

# Materials ♦ EIS None ♦ FONSI ♦ NEPA Permit ♦ ROD ♦ Transmittals

#### **Reference to Other Processes**

Precedes 2.2.8 Environmental Impact Studies







| Procure Interior Desi<br>Design      | gn  | Buildings<br>Parks<br>Roads | <b>2.2.10</b> |
|--------------------------------------|---|-----------------------------|---------------|
| Process Owner                        | Description   |                             |               |
| Director                             | Interior Design services are procured and are con   | •                           |               |
| Parks & Recreation Public Works      | A/E services (preferred). An alternate means of procuring services is use of Property Management's interior design contracts.s. |                             | vices is      |
| Process Manager                      |   |                             |               |
| Property Management Project Managers |   |                             |               |
| , ,                                  |   |                             |               |
| Parks & Recreation Public Works      |   |                             |               |

- ♦ **Property Management** Review and evaluate bids if contracted separately. If interior design is procured through FMC Architect/Engineer, Property Management is involved throughout the design.
- ♦ **Users** Provide feedback.
- ♦ Facilities Construction Management (FCM) Coordinates process with architect.
- ♦ Office of Information Technology (OIT) Review needs.
- ♦ Buildings & Grounds (B&G) Review needs.

# **Timelines: Deadlines, Critical Path Items**

**♦ Schematic Design** 

| Materials | Forms   |
|-----------|---|
| None      | ♦ Cost Proposal form for Interior Design Services |

#### **Reference to Other Processes**

Follows 2.2.1 Programming Occurs throughout 2.2.4 Alternative Analysis Follows 2.2.7 Schematics



| Task Order |           | 2.2.11                  |
|------------|-----------|-------------------------|
|            | Buildings | $\overline{\checkmark}$ |
| Design     | Parks     | $\overline{\checkmark}$ |
|            | Roads     | $\overline{\checkmark}$ |

# Process Owner Directors

# A task order open-ended

# Parks & Recreation, Public Works & Transportation

A task order is a mechanism used to acquire services from an established open-ended professional services contract, briefly noting highlighted information, and/or scope of work. The forms are then forwarded to the department's Accounting staff to prepare the purchase order. The forms are then forwarded to Purchasing for approval.

# **Process Manager**

**Project Managers** 

Parks & Recreation, Public Works & Transportation Task orders can be issued for other services, such as commissioning, materials testing, special inspections, third party inspections, cost estimating, etc. These are just some of the types of services used during the design/construction of a CIP project.

# **Contacts & Roles: Organization, Entity, or Individual**

Description

♦ Purchasing – Approves task order.

# **Timelines: Deadlines, Critical Path Items**

- **♦ Scope of Work**
- **♦ Design Development**
- **♦ Cost Proposal**
- ♦ Performance Period

# Materials

- ♦ A/E consultant's proposal
- Utility Service Work Order (for task orders done for utility relocation and installation)

### ♦ Task Order Form

**Forms** 

#### Reference to Other Processes

Occurs throughout 2.2.13 Design Development (Buildings and Parks)

Occurs throughout 2.2.14 Design Development (Roads)

Occurs throughout 2.5.2 Negotiate Fee Arrangement


Occurs throughout 2.5.7 Utility Relocations

Occurs throughout 2.5.5 Request/Authorize Work

Occurs throughout 2.7.5 Budget Transfer



Task Order 2.2.11





| Interiors<br>Design  |  | Buildings<br>Parks<br>Roads                       | <b>2.2.12</b> |
|--|--|---|---------------|
| Process Owner Director Public Works  | Description  Public Works project team meets with users to d furniture needs for the entire building. Some exa personnel are to be moved in? Where? What despecific or special needs exist? The Public Works explain space and furniture standards to the user | mples are: How<br>partments? Wh<br>project team w | v many<br>at  |
| Process Manager Property Management Facilities Construction Management (FCM) Project Managers  Parks & Recreation Public Works |  |   |               |

- ♦ **Property Management –** Facilitate, advise, coordinate, and review the process.
- ♦ Facilities Construction Management (FCM) Facilitate, advise, coordinate, and review the process.
- ♦ Office of Information Technology (OIT) Facilitate, advise, coordinate, and review the process.
- ♦ **County users** Review and provide customer requirements.
- ♦ Buildings & Grounds (B&G) Facilitate, advise, coordinate, and review the process.

# **Timelines: Deadlines, Critical Path Items**

- **♦ Schematic of Furniture Layout**
- **♦ Approval of Schematic**

# Materials Forms

 Building permit application (AKA space permit application; simply building permit application marked 'Interiors')


None

#### Reference to Other Processes

Concurrent 2.2.13 Design Development (Buildings)



Interiors 2.2.12





| Design Development (Buildings & Parks)  Design |   | Buildings<br>Parks<br>Roads | 2.2.13<br>☑ ☑ □ |
|--|---|-----------------------------|-----------------|
| <b>Process Owner</b>                           | Description   |                             |                 |
| Director                                       | Design Development (DD) for buildings defines and describes all important aspects of the project so that all that remains is the format documentation (construction documents). |                             |                 |
| Parks & Recreation Public Works                |   |                             | formal          |
| Process Manager Project Managers               | The DD phase produces drawings and specification describe the size and character of the project, condeveloped floor plans, interior and exterior elevations.                    | mprised of ful              | lly             |
| Parks & Recreation                             | plans, wall and building sections, and basic electrical, mechanical, plumbing and fire protections system.  |                             | cal,            |

- ♦ Facilities Construction Management (FCM) Manage, facilitate, and coordinate with the consultants, users, and building officials.
- ◆ Project Manager Manage, facilitate, and coordinate with the consultants, users, and building officials, Property Management and Environmental Services.
- ♦ **Buildings & Grounds (B&G)** Performs design reviews for building maintainability and control systems.
- ♦ OIT Manage, facilitate, and coordinate with the consultants, users, and building officials.
- ♦ **Users** Provide information about the building needs.

# **Timelines: Deadlines, Critical Path Items**

- ♦ **50% Review** Internal review by FCM, PM, B&G, and OIT for compliance to standards and needs.
- ♦ 100% Review Internal review by FCM, PM, B&G, and OIT for compliance to standards and needs.
- ♦ Cost Estimate If over budget, project needs to be revised to fit budget or additional funding identified.

| Materials                    | Forms |  |
|------------------------------|-------|--|
| ♦ Design drawings            | None  |  |
| ♦ Professional cost estimate |       |  |

#### **Reference to Other Processes**

Follows 2.2.7 Schematics



#### **Flow Chart Design Development Develop Drawings** Security Systems Preliminary Civil Plans/ Identify Мар Preliminary Programming Specification Programming **Specs Security** Programming finish meeting if needed meeting materials Detailed Casework Design/ Details Make Revisions No No 50% Submission Yes 100% approved? Review by PW Make revisions Ok? Yes Cost estimate **Work Session** Final Review submitted by A/E. Schedule Kick-off Meeting Prepare Task Order FCM determine: Is No and Encumbrance budget sufficient? Set up Scope of Work Yes Sign off approval of plans Conduct value engineering



| <b>Design Development</b> Design      | (Roads)  | Buildings<br>Parks<br>Roads | <b>2.2.14</b> □ □ □ |
|---------------------------------------|--|-----------------------------|---------------------|
| <b>Process Owner</b>                  | Description  | '                           |                     |
| <b>Director</b> <i>Transportation</i> | Design Development (DD) for road projects is the process from having hired professional services to develop an approved set of plans ready for construction. |                             |                     |
| Process Manager                       |  |                             |                     |
| Project Managers                      |  |                             |                     |
| Transportation                        |  |                             |                     |

- ♦ **VDOT** Provide technical support.
- ♦ **BOCS** Provide input and design alternative selection.
- ♦ Citizens Provide alternatives and impact feedback.
- ◆ Developers Provide coordination with proffered improvements in close proximity to the County project.
- ♦ A/E Consultants Provide coordination.
- ♦ County Project Managers Review project and provide comments.

# **Timelines: Deadlines, Critical Path Items**

- ♦ **Public Information meeting** Public Information meetings are sometimes necessary when citizen involvement or concern is high.
- ♦ **BOCS design approval** BOCS makes alternative selection.
- ♦ 70% submission to VDOT –70% submission is the first opportunity to receive feedback from VDOT. Approval at 70% is not necessary, but incorporation of comments is required.
- ♦ 100% submission to VDOT Submission is required before plans can be constructed.


| Materials                          | Forms |  |
|------------------------------------|-------|--|
| ♦ BOCS Staff Report and Resolution | None  |  |
| ♦ Contract & Transmittals          |       |  |
| ♦ VDOT                             |       |  |

#### **Reference to Other Processes**

Follows 2.1.6 Request for Proposal
Occurs throughout 2.2.4 Alternative Analysis
Precedes 2.3.1 Invitation for Bid (IFB)
Concurrent 2.5.1 Identify Existing Utilities and Conflicts
Concurrent 2.6.1 Land Acquisition Overview



#### **Process Notes**





| Site Permitting Design             |   | Buildings<br>Parks<br>Roads                        | <b>2.2.15</b>            |
|------------------------------------|---|--|--------------------------|
| <b>Process Owner</b>               | Description   |  |                          |
| Parks & Recreation Planning Office | Site permitting is a separate permitting action from However, a site plan must be approved prior to the building permit. Because of the timing and the value permit goes through, the site plans are typically stated by the building permit. | the issuance of<br>arious phases<br>submitted in a | f a<br>a site<br>idvance |
| Process Manager Plan Reviewer      | of the building permit process. The review is concurrent with the completion of the building construction drawings.   |  | ne                       |
| Parks & Recreation                 |   |  |                          |

- ♦ Facilities Construction Management (FCM) Project management.
- ♦ Property Management (PM) Project management.
- ♦ Buildings & Grounds (B&G) Project management.
- ♦ Office of Planning Site plan review and coordination with other review agencies.
- ♦ Other departments (Transportation, Environmental Services, VDOT, DEQ, etc.) Site plan review.

  Office of Planning is the lead for coordinating all comments from the review agencies.
- ♦ A/E Consultant Responsible for design and resolution of issues.

# **Timelines: Deadlines, Critical Path Items**

♦ **Approval of site plan** – Must be approved to obtain building permit.

#### **Materials**

- ♦ SOP 1.007.1 Reference Guide for Facilities Projects
- ♦ Permit letter
- ♦ Site plan application
- ♦ Transmittals


#### **Forms**

♦ Public Facilities Determination (PFD)

### **Reference to Other Processes**

Precedes 2.2.20 Building Permit Review and Permitting







| <b>Survey</b><br>Design       |   | Buildings<br>Parks<br>Roads      | 2.2.16<br>☑ ☑ ☑ ☑ |
|-------------------------------|---|----------------------------------|-------------------|
| Process Owner Directors       | <b>Description</b> An important part of the design process is the su  | rvey. An accurat                 | te                |
| Public Works & Transportation | record of the impacted land is necessary for the project. The point at which the survey is between building and road projects. For design | completion of a<br>done may diff | ny<br>er          |

procures and manages those services as part of their contract.

# **Process Manager**

**Project Managers** 

Parks & Recreation Public Works & Transportation

# **Contacts & Roles: Organization, Entity, or Individual**

- ♦ Transportation (Right-of-Way) Titles will be needed...
- ♦ **Public Works** Provide coordination for building projects.
- ♦ **Purchasing** Approve the consultant if procured using the open-end professional contracts.
- ♦ A/E Consultant Provide the survey.

# **Timelines: Deadlines, Critical Path Items**

♦ Confirm that survey is part of Design Contract – Task Order only needed if survey services are not included in A/E contract.

| Materials                | Forms |
|--------------------------|-------|
| ♦ Contract               | None  |
| ♦ Task Order (if needed) |       |

#### **Reference to Other Processes**

Precedes 2.1.6 Request for Proposal

Concurrent 2.2.11 Task Orders

Precedes 2.2.13 Design Development (Buildings & Parks)

Precedes 2.2.14 Design Development (Roads)


#### **Process Notes**

For Bond only:

- ♦ Survey can be done under task order.
- ♦ Survey could be part of design contract.
- ♦ If done as a task order, follow the task order process.



Survey 2.2.16





| Plat Preparation |           | 2.2.17       |
|------------------|-----------|--------------|
| •                | Buildings |              |
| Design           | Parks     | $\checkmark$ |
|                  | Roads     | $\checkmark$ |

# Process Owner Directors Description

Parks & Recreation
Public Works &
Transportation

## Process Manager Project Managers

Parks & Recreation
Public Works &
Transportation

Legal documentation of property is required for all projects. The drawing of the property is known as the plat. The plat includes all dedications, easements or right-of-ways or other encumbrances on the site. The plat also locates buildings and associated support structures on the site, along with roads, storm water management and utilities.

# Contacts & Roles: Organization, Entity, or Individual

- ♦ **BOCS** Approves plats if there are dedications, easements, or right-of-ways.
- ♦ A/E Consultant Responsible for preparing plats.
- ♦ **Public Works and Transportation** Manage the plat review and approval process.
- ♦ County Attorney Prepare deeds and record plats.
- ♦ Clerk of the Court Records deeds.
- ♦ **Utility Companies** Conduct field inspections...

# **Timelines: Deadlines, Critical Path Items**

❖ Plan completion at 70% to 100% – Transportation projects initiate plat preparation at 70%. Building projects initiate plat preparation prior to submission for site permitting. Revisions may be necessary as part of construction based on utility installations. CIP building projects require submission of the plat and site plan at approximately 50% of design or post design developement..

| Materials | Forms |
|-----------|-------|
| ♦ Plat    | None  |
| ♦ Titles  |       |

#### **Reference to Other Processes**


Precedes 2.2.13 Design Development (Buildings)

Precedes 2.2.14 Design Development (Roads)

Precedes 2.2.16 Survey

- All right-of-way take, permanent and temporary easements, and utility easements need to be determined before any plats can be prepared.
- Plats are prepared as part of Design Contract.







| Construction Documents |           | 2.2.18                  |
|------------------------|-----------|-------------------------|
|                        | Buildings | $\overline{\checkmark}$ |
| Design                 | Parks     | $\overline{\checkmark}$ |
|                        | Roads     | $\overline{\checkmark}$ |

# Process Owner Directors Description

Parks & Recreation
Public Works &
Transportation

# Process Manager Project Managers

Parks & Recreation Public Works & Transportation Construction Documents (CDs) are prepared by the A/E and reviewed by the CIP team to ensure the building and its elements meet the County's needs. They establish the contractual obligations of the owner and contractor to each other during the project; identify the responsibilities of all parties (A/E, GC, Owners); communicate the quantity, quality and relationship of all work required to construct the project; and provide the medium to solicit a firm cost for construction. CDs include, but are not limited to, bid requirements, contract forms, contract conditions, specifications, drawings, addenda and contract modifications.

# Contacts & Roles: Organization, Entity, or Individual

- ♦ A/E Consultant Prepares construction documents and obtains final cost estimate.
- ♦ Citizens Special provisions are occasionally annotated in the construction documents for road projects.
- ♦ **VDOT** Special provisions and notes from VDOT are incorporated into the construction documents.
- ♦ **Project Manager** coordinates design reviews with Property Management, Buildings & Grounds, Environmental Services, and others as necessary.

# **Timelines: Deadlines, Critical Path Items**

- ♦ **100% plans** Required for permitting.
- ♦ **VDOT Approvals** VDOT approves 100% plans for road projects.
- ♦ Cost Estimates Provided by an outside consultant and validate CIP estimates.
- ♦ Specifications Required for permitting and provide written documentation supporting the design.

| Materials                | Forms |
|--------------------------|-------|
| ♦ Construction documents | None  |

#### **Reference to Other Processes**

Follows 2.1.1 Kick-off

Follows 2.2.13 Design Development (Buildings)

Follows 2.2.14 Design Development (Roads)

Follows 2.2.17 Plat Preparation

Precedes 2.3.1 Invitation for Bid (IFB)



## **Process Notes**

# **Flow Chart** Construction documents 50% submission of drawings for building. FCM, PM, OIT, and B&G review. Comments forwarded to A/E. Consultant makes changes. 95% submission of drawings for building. Submit for building plan review. 2.2.19 Prepare pre-encumbrance and Scope of Prepare cost estimate. Work for Purchasing. Verify costs with Budget. Forward front-end documents to Purchasing. Final sign-off by County. Prepare front-end specs and forward to consultant. No Any consultant changes? 100% submission of drawings for building.



County review

| <b>Building Review and Permitting</b> |           | 2.2.19                  |
|---------------------------------------|-----------|-------------------------|
|                                       | Buildings | $\checkmark$            |
| Design                                | Parks     | $\checkmark$            |
|                                       | Roads     | $\overline{\checkmark}$ |

|   |   | Paiks | V                       |
|---|---|-------|-------------------------|
|   |   | Roads | $\overline{\checkmark}$ |
| <b>Process Owner</b>  | Description   |       |                         |
| Building Official   | All construction plans are prepared in accordance with the  |       |                         |
| Parks & Recreation<br>Public Works  | International Building Code (IBC) as adopted by Virginia. (Please note that this code is updated every 3 years, but not used until adopted by the State.) The architect or County Project Manager submits the initial plans to the Public Works for review. Comments generated by the |       |                         |
| <b>Process Manager</b> reviewers are then forwarded to the A/E for resolution. Or comments are addressed, submitted and approved by the |   |       | rs. a                   |
| Plan Reviewer   | building permit is issued for the project. No construction can begin on a   |       |                         |
| Duilding Davidanmant  | project without having an approved permit.  |       |                         |

For road projects, building permits are issued for structural and electrical components.

## **Contacts & Roles: Organization, Entity, or Individual**

- ♦ **Public Works** FCM, PM, and B&G facilitate and coordinate the submission, review comments, and completion of all tasks by consultant.
- ♦ A/E Consultant Respond to review comments.
- ♦ **Planning Office** Approve site plan as part of the overall building permit process.
- ♦ Transportation Facilitate submission of plans.

# **Timelines: Deadlines, Critical Path Items**

**♦ Timely response to review comments** 

| Materials  | Forms |  |
|--|-------|--|
| <ul><li>◇ Building permit application</li><li>◇ Transmittals</li><li>◇ Watershed documents</li></ul> | None  |  |

#### **Reference to Other Processes**

Follows 2.2.18 Construction Documents

#### **Process Notes**


Building Development Parks & Recreation

**Public Works** 

The reviews are completed in sequential order. Failure of any of the reviews (building, mechanical, electrical, etc.) results in a negative assessment of the construction plans. Comments are then sent to A/E, which revises the plans. The revised plans cycle through the review process again, skipping those reviews which were positive previously. This process continues until all reviews are positive.




# Flow Chart (Process A – Buildings)





# **Chart (Process B – Transportation)**





| Invoices |           | 2.2.20                  |
|----------|-----------|-------------------------|
|          | Buildings | $\overline{\checkmark}$ |
| Design   | Parks     | $\overline{\checkmark}$ |
|          | Roads     | $\checkmark$            |
|          |           |                         |

# Process Owner Directors Description

Parks & Recreation Public Works Transportation

Process Manager Project Managers

Parks & Recreation Public Works & Transportation Invoices on Capital Improvement Program Projects are typically paid from a Purchase Order, unless they are project expenses under \$5,000, which can be paid through a direct purchase. The review of invoices is essential for maintaining proper financial controls and project management.

# Contacts & Roles: Organization, Entity, or Individual

- ♦ Transportation Receive and review invoices against a Purchase Order for accuracy and completeness.
- ♦ **Public Works** Receive and review invoices against a Purchase Order for accuracy and completeness.
- ♦ Accounts Payable Final approval of invoices.
- ♦ A/E Consultants Provide the invoices.

# **Timelines: Deadlines, Critical Path Items**


- ♦ **Project Manager Signature** The Project Manager must sign the invoice, attesting that it is in accordance with the contract and the billable items are accurate.
- ♦ **Department approval** Approval paths may differ across departments; however, it is the responsibility of the managing department to ensure that proper financial controls are used.
- ♦ Accounts Payable approval Accounts payable will have final electronic approval on all invoices.

| Materials | Forms                               |
|-----------|-------------------------------------|
| None      | ♦ Pre-Ascend Request Form - Invoice |

#### Reference to Other Processes



Invoices 2.2.20





| Invitation for Bids (IF Construction | B)   | Buildings<br>Parks<br>Roads | 2.3.1<br>☑ ☑ ☑ |
|--------------------------------------|--|-----------------------------|----------------|
| Process Owner Director Finance       | <b>Description</b> An Invitation for Bids (IFB) is a formal solicitation and is the purchasing mechanism used to acquire construction services. It is initiated by the |                             | •              |
| Process Manager                      | using department and processed by the Director of Finance in accordance with established rules and regulations.  |                             |                |
| Purchasing<br>Finance                |  |                             |                |

- ♦ **VDOT** Provide latest special provisions for road projects.
- ♦ **Transportation** Provide information for the IFB.
- ♦ **BOCS** Approve the contract award.
- ♦ **Public Works** Provide information for the IFB.
- ♦ **State Administrator** Reviews and approves IFB documents for contract when federal or state funding involved.
- ♦ **Project Manager** Completes Project Information Form and provides necessary supporting documentation for the contract.
- ♦ **Purchasing** To review the Project Information Form and issue the IFB.

# **Timelines: Deadlines, Critical Path Items**

- ♦ If not greater than or equal to \$30,000 3-quote process
- ♦ Is funding sufficient?
- **♦** Greater than \$100,000?
- ♦ Is solicitation approved?


| Materials | Forms                               |
|-----------|-------------------------------------|
| None      | ♦ Capital Projects Information Form |

#### **Reference to Other Processes**


#### **Process Notes**

For federal projects or grant funding, the state administrator must review and approve the bid documents (e.g. TEA-21).











| Change Order Construction |   | Buildings<br>Parks<br>Roads | 2.3.2<br>☑<br>☑ |
|---------------------------|---|-----------------------------|-----------------|
| <b>Process Owner</b>      | Description   |                             |                 |
| Finance                   | A Change Order is a document which is signed by contractor, A/E, and owner which authorizes an addition, deletion, or revision in the work or an adjustment in the contract price or the contract terms, issued on or |                             |                 |
| <b>Process Manager</b>    | after the effective date of the agreement. Changes may occur as a result of a change in the original scope of work, specific unforeseen   |                             |                 |
| Construction Managers     | obstacles which require variation from the origin of other features or options to the project.  | •                           |                 |
| Project Managers          |   |                             |                 |
| Public Works &            |   |                             |                 |
| Transportation            |   |                             |                 |

- ♦ **Transportation** Negotiate the terms of the Change Order.
- ♦ DOT Director & Purchasing Mgr Approve change orders <25% of original contract value or < \$50,000.</p>
- ♦ **BOCS** Approve Change Order if over 25% of the original amount or \$50,000, whichever is greater.
- ♦ **Contractor** Negotiate the terms of the Change Order.
- ♦ **Public Works/Transportation** Negotiate the terms of the Change Order.

# **Timelines: Deadlines, Critical Path Items**


- **♦ Project Manager gets estimates**
- ♦ Contractor and County successfully negotiate terms of the Change Order
- ♦ Transportation Director/Purchasing Mgr approve change orders less than 25% of contract value or less than \$50,000
- **♦ BOCS approves Change Order (when required)**
- ♦ Changes to the original contract made

| Materials | Forms                                |  |
|-----------|--------------------------------------|--|
| None      | Change Order (AIA Document G701)     |  |
|           | Proposal Request (AIA Document G709) |  |
|           | County Change Order Form             |  |
|           |                                      |  |

#### **Reference to Other Processes**

Follows 2.3.1 Invitation for Bids (IFB) Concurrent 2.3.9 Construct (Roads) Concurrent 2.3.8 Construct (Buildings) Concurrent 2.8.1 Board Agenda







| Request for Payment |           | 2.3.3                   |
|---------------------|-----------|-------------------------|
| Construction        | Buildings | $\overline{\checkmark}$ |
| Construction        | Parks     | $\overline{\checkmark}$ |
|                     | Roads     | $\overline{\checkmark}$ |
| Description         |           |                         |

# Process Owner Directors Directors Description Requests for payment

Parks & Recreation Public Works Transportation

## Process Manager Construction Managers

Parks & Recreation
Public Works
Transportation

Requests for payment (also known as construction invoices or application for payment) on Capital Improvement Program projects are typically paid from a Purchase Order, unless they are project expenses under \$1,000, which can be paid through a direct voucher. The review of requests for payment is essential for maintaining proper financial controls and project management. Requests for payment can provide an indication of the project progress.in building CIP projects, all requests for payment that include stored materials or prepayment for materials/services must have proof of purchase and storage as applicable. This can include, but is not limited to, photographs of the materials in storage, affidavits of purchase/storage, bills of laden and/ or FCM staff observance of the materials.

# Contacts & Roles: Organization, Entity, or Individual

- ◆ Transportation Receive and review requests for payment against a Purchase Order for accuracy and completeness.
- ♦ Public Works Receive and review requests for payment against a Purchase Order for accuracy and completeness.
- ♦ Accounts Payable Final approval of requests for payment.
- ♦ **Vendor** Provide the requests for payment.

# **Timelines: Deadlines, Critical Path Items**

- ♦ **Construction Manager signature** The Construction Manager must sign the request for payment, attesting that the request is in accordance with the contract and the billable items are accurate.
- ♦ **Department approval** Approval paths may differ across departments; however, it is the responsibility of the managing department to ensure that proper financial controls are used.
- ♦ Accounts Payable approval Accounts payable will have final electronic approval on all requests for payment.


# Materials ♦ Copies of invoices and/or internal charges ♦ Application and Certificate for Payment (AIA Document G702) – for buildings ♦ Request for Payment – for roads ♦ Pre-Ascend Request Form - Invoice

#### **Reference to Other Processes**

Concurrent 2.3.8 Construct (Buildings) Concurrent 2.3.9 Construct (Roads)



#### **Process Notes**



<sup>\*</sup> Approval process and payment shall not exceed 30 days.



| Draw Downs for Bo<br>Construction | nd- or Lease-Funded Projects  | Buildings<br>Parks<br>Roads | <b>2.3.4</b> |
|-----------------------------------|---|-----------------------------|--------------|
| <b>Process Owner</b>              | Description   |                             |              |
| Treasury Manager                  | Some Capital Improvement Projects are funded through debt, also know as bond sales. The County uses cash from the General Fund to pay for expenses as they occur. Periodically, County agencies are required to complete draw downs (also known as cashdraws) for projects so that the revenues from debt can supplant general fund |                             |              |
| Finance                           |   |                             |              |
| <b>Process Manager</b>            |   |                             |              |
| <b>Fiscal Services Manager</b>    |   |                             |              |
| Finance                           | revenues.   |                             |              |

- ♦ **Department Project Managers** Approve invoices and payments, which are the basis for, and incorporated into, draw downs. Certify information contained in draw down request.
- ♦ **Department Accounting Staff** Prepares the draw down request.
- ♦ **Fiscal Services Manager** Reviews draw down request after it is submitted by department. Submits the completed draw down to the internal portfolio managers.
- ♦ Internal Portfolio Manager Submits the draw down data to external portfolio manager.
- ♦ External (Third-Party) Portfolio Manager Releases bond proceeds cash to the County bank account.

# **Timelines: Deadlines, Critical Path Items**

- ♦ 6-month IRS milestone 10% of expenses.
- ♦ **12-month IRS milestone** 45% of expenses.
- ♦ **18-month IRS milestone** 75% of expenses.
- **♦ 24-month IRS milestone –** 95% of expenses.
- ♦ **36-month IRS milestone** 100% of expenses.

# Materials Forms ♦ Copies of invoices and/or internal charges None

- ♦ Letter to Trustee/Portfolio Manager
- ♦ Summary of expenses

#### **Reference to Other Processes**

Follows 2.7.2 Bond/Lease Sale Concurrent with 2.7.3 Arbitrage

#### **Process Notes**

External portfolio manager reports semi-annually based on closing date:



#### Arbitrage

- ♦ If all milestones are met County keeps all interest and does not perform arbitrage calculation.
- ♦ Milestones (spend & draw):
  - o 6 months 10%
  - o 12 months 45%
  - o 18 months 75%
  - o 24 months 95%
  - o 36 months 100%
- ♦ If one milestone is missed, the County performs arbitrage calculation.
- ♦ If one milestone is missed and the County earns more interest than it pays, the difference goes to the IRS.

Several things must be completed before initiating a bond draw down:

- ♦ BOCS must approve the project appropriations that include bond/lease financing support.
- ♦ Expenditures being drawn must have been paid and related processing completed.
- ♦ It is preferred that the supporting bond sale has been completed.
- ♦ The project expenditure must be appropriate for bond financing support, i.e., that it is a capital improvement and has a 20-year practical, useful life. You should not draw for operating expenses, for equipment that is not part of the facility, or for equipment/other items that do not have a 20-year useful life.

It is recommended that as each vendor payment, or direct County expense is incurred, a copy of the invoice(s) is set aside into a draw down file (filed by project by bond sale).

At regular intervals a Public Works/Transportation processor (clerk, accountant, Project Manager) should gather a full set of the invoices and signed copies of internal charges which have occurred since the last draw down was executed. (The frequency for preparing a project's draw downs depends on its rate of expenditures – draw downs should be monthly, if the project is active and expending funds frequently or at least quarterly if the project is moving slowly.)

The Public Works/Transportation processor prepares a summary of the payments/ invoices/charges the draw down will be reimbursing. The processor then prepares a cover letter to the external Portfolio Manager or Trustee as appropriate. The cover letter should be addressed to the correct person (ie. the Portfolio Manager's or Trustee's representative). The cover letter also should identify the portfolio manager's correct account number, the amount to be drawn, the cumulative total of all prior draw downs for this project, the outstanding direct proceeds balance for this project, and the remaining balance of the direct proceeds for this project after the draw down is completed. The certification of expenses should be signed by the Project Manager or by the department Director.

The cover letter, summary of the invoices, and the full set of the invoice copies and copies of signed internal charges should be assembled into one package constituting the draw down. The Public Works/Transportation manager reviews the draw down, and if correct, sends it to the department Director (or designee) for signature. Once the department Director has signed the draw down, the draw down is forwarded to Finance for review.

After reviewing the draw down Finance either returns the draw down to its originator for correction, or




# Draw Downs for Bond- or Lease-Funded Projects

2.3.4


sends it to the external Portfolio Manager or trustee for their processing and for their release of the bond proceeds to the County. The external Portfolio Manager or the Trustee transfers the cash reimbursement to the County concentration account (County's primary checking account).

Note: By policy approved by the BOCS, interest earned on bond proceeds is normally transferred to the County's Capital Reserve. These transfers of interest earnings are executed periodically during the fiscal year if appropriate, and at least one time per year after the fiscal year closes. An exception can be made to this use of interest earning if and when the BOCS directly budgets and appropriates some or all of the actual interest earnings in a specific amount to a specific project.











| Withholding and Releasing Retainage |           | 2.3.5                   |
|-------------------------------------|-----------|-------------------------|
|                                     | Buildings | $\checkmark$            |
| Construction                        | Parks     | $\overline{\checkmark}$ |
| Only on County & State Projects     | Roads     |                         |

## Process Owner Director

#### Finance

#### Process Manager Project Managers

Parks & Recreation
Public Works
Transportation

## **Description**

The County, as owner, retains a portion of the contractors' funds with each payment, per Prince William County Purchasing regulation (Section 600.12). The typical amount is 5% of each payment. Those funds are encumbered and held in a separate account for payout at the completion of the project. Retainage provides the leverage to assure work has been completed 100% per the contract documents. It also provides funds in the event work is not completed per the contract, or is deficient. The retainage is held until the final payment is made and all punchlist work is complete.

Partial release of retainage can be made following substantial completion, provided that the value of the outstanding work is less than the remaining retainage being held. Approval for partial payment requires County Architect's approval.

## Contacts & Roles: Organization, Entity, or Individual

- ♦ Project Manager Approves retainage.
- ♦ **Department Accounting Staff** Processes Requests for Payment and withholds retainage.
- ♦ **General Contractor** Submits Requests for Payment.

#### **Timelines: Deadlines, Critical Path Items**

- ♦ **50% completion** Make determinations about withholding retainage.
- ♦ Contractor 10% Behind If contractor is 10% behind on CPM schedule reinstate the 5% retainage.
- ♦ Receipt of Request for Payment Contractor submits Request for Payment to the County.
- ♦ **Punchlist** All items on the punchlist must be complete prior to release of retainage.
- ♦ **Road acceptance** Road must be accepted by VDOT prior to release of retainage.
- ♦ Liquidated damages Contractor can be assessed penalties, also known as liquidated damages, if project is not completed on or before the contract completion date.
- ♦ **Occupancy Permit** Occupancy Permit must be issued prior to release of retainage for buildings.
- ♦ Final Request for Payment Retainage cannot be released before final Request for Payment is received.




| Materials | Forms  |
|-----------|--|
| None      | Request for Payment – for roads  |
|           | <ul> <li>Application and Certificate for Payment (AIA<br/>Document G702) – for buildings</li> </ul>            |
|           | <ul> <li>Consent of Surety to Reduction in or Partial<br/>Release of Retainage (AIA Document G707A)</li> </ul> |
|           | <ul><li>Consent of Surety Company to Final Payment<br/>(AIA Document G707)</li></ul>                           |

## **Reference to Other Processes**


Follows 2.3.3 Request for Payment

## **Process Notes**











#### 2.3.5-B Withholding and Releasing Retainage (Innovative **Buildings Delivery Transportation Projects/PPTA** Parks Projects/Design-Build) $\overline{\mathbf{V}}$ Roads Construction **Description Process Owner** Director The withholding and releasing of retainage for Innovative Delivery Transportation Projects, PPTA Projects and Design-Build Projects will be **Finance** determined during project negotiations. **Process Manager Project Managers** If negotiated, the withholding and releasing of retainage for the Innovative Transportation, PPTA, and Design-Build Projects can follow Public Works & the standard Design-Bid-Build process for retainage.

## **Contacts & Roles: Organization, Entity, or Individual**

♦ **Project Manager** – Approves retainage.

**Transportation** 

- ♦ **Department Accounting Staff** Processes Requests for Payment and withholds retainage.
- ♦ **General Contractor** Submits Requests for Payment.

#### **Timelines: Deadlines, Critical Path Items**

- ♦ % of completion Make determinations about withholding retainage.
- ♦ **Receipt of Request for Payment** Contractor submits Request for Payment to the County.
- ◆ **Punchlist** All items on the punchlist must be complete prior to release of retainage.
- ♦ **Road acceptance** Road must be accepted by the county and VDOT prior to release of retainage.
- ♦ Liquidated damages Contractor can be assessed a cost, also known as liquidated damages, if project is not completed on or before the contract completion date.
- ♦ Occupancy Permit Occupancy Permit must be issued prior to release of retainage for buildings.
- ♦ Final Request for Payment Retainage cannot be released before final Request for Payment is received.

| Materials | Forms  |
|-----------|--|
| None      | Request for Payment – for roads  |
|           | <ul> <li>Application and Certificate for Payment (AIA<br/>Document G702) – for buildings</li> </ul>            |
|           | <ul> <li>Consent of Surety to Reduction in or Partial<br/>Release of Retainage (AIA Document G707A)</li> </ul> |
|           | <ul><li>Consent of Surety Company to Final Payment<br/>(AIA Document G707)</li></ul>                           |



#### **Reference to Other Processes**

Follows 2.3.3 Request for Payment Follows 2.3.5 Withholding and Releasing Retainage (Design-Bid-Build).

#### **Process Notes**



| Construction Inspection (Roads) Construction |   | Buildings<br>Parks<br>Roads | <b>2.3.6</b> □ □ □ |
|--|---|-----------------------------|--------------------|
| Process Owner                                | Description   |                             |                    |
| <b>Director</b> Transportation               | During construction, the County either provides or hires an inspector to monitor the day-to-day activities of project construction. Usually there will be a general construction inspector and a geotechnical |                             | ıally              |
| Process Manager Project Manager              | inspector.  |                             |                    |

- ♦ Contractors Provide bi-weekly schedule.
- ♦ **VDOT** Randomly inspect and give feedback about the project to County Project Manager.
- ♦ **Transportation** Project Manager resolves issues and ensures the project is moving on schedule.
- ♦ Citizens Provide feedback.
- ♦ **Public Works** Provide Storm Water Management feedback.
- ♦ **Project inspector –** Manages field operations.

## **Timelines: Deadlines, Critical Path Items**

- ♦ Testing inspection On call tests all project materials.
- ♦ **Review quantities from GC** Project inspector reviews and approves daily quantities.
- ♦ Maintenance or traffic control Contractor contact VDOT and request a lane closure approval.

| Materials       | Forms   |
|-----------------|---|
| ♦ Daily Tickets | <ul><li>◇ Daily Reporting</li><li>◇ Daily Testing</li><li>◇ Work Zone Safety Assistance</li></ul> |

#### **Reference to Other Processes**

Concurrent with 2.3.9 Construct (Roads)



#### **Process Notes**

Below are basic job descriptions, qualifications, experience and general duties and responsibilities of the Inspector.

General Construction Inspector's Role and Responsibilities

- ♦ Inspection of clearing, grading, excavation and placement of embankments and all other required activities as proposed by the County.
- ♦ Inspection of drainage pipes, structures and stormwater management facilities, including pipe jacking.
- ♦ Inspection of curbing and paving.
- ♦ Inspection of incidental items.
- ♦ Review and monitoring of maintenance of traffic.
- ♦ Inspection of signal, signing and marking installation.
- ♦ Inspection of waterline and sanitary sewer relocations required under this contract.
- ♦ Tracking of project quantities and review of contractor invoices.
- ♦ Review of project schedules and attend the weekly project coordination meetings.
- ♦ Maintaining daily field logs.
- ♦ Inspection of Bridge and structures.
- ♦ The Construction Inspector Senior requires frequent contact with engineers and department personnel to discuss and resolve field construction issues and to obtain technical guidance in specialty areas of engineering and inspections. This position requires frequent external contact with general construction contractor personnel in an effort to schedule and coordinate project inspections and resolve problems; including local government and law enforcement agencies; to explain work under construction and coordinate traffic control with suppliers and monitor receipt of materials; including utility companies to coordinate relocation and installation; and with the public to provide information and resolve issues.

#### Additional duties will include:

- ♦ Monitor the work of contractors and subcontractors to ensure quality control and contract compliance for roadway, structure, and bridge construction projects of moderate to considerable complexity.
- ♦ Maintain a diary of the project and accurate time line of events.
- ♦ Independently coordinates and directs all phases of construction inspection of projects that are typically complicated by extensive traffic control, sensitive political or environmental concerns, or significant project coordination with property owners, utility companies, and local and federal government representatives.
- ♦ Verifies lines, grades, dimensions and elevations using survey and field engineering equipment.
- ♦ Coordinates and schedules phases of construction with the prime contractor and department personnel; reviews and monitors contractors' plan of operation; and advises contractors of violations and recommends adjustments to operations.
- ♦ Request clarification to construction plans; makes field measurements of pay items and conducts daily diaries, materials notebooks, as-built plans, pay quantity records, progress schedules, change orders, and monthly estimates.
- ♦ Testing Services Contact on call geo firm to perform testing.



#### **Process Notes Continued**

Geotechnical Inspector's Role and Responsibilities


- ♦ Inspect, test and monitor excavations, bedding, drainage facilities, backfilling, soil compaction/placement and undercut.
- ♦ Test and monitor asphalt pavement, reinforcement steel, concrete pouring, formwork and structures.
- ♦ All boring logs, testing location, classification and any results of geotechnical investigation should be represented in a report.
- ♦ Verify lines and dimensions to ensure compliance with plans.
- ♦ Perform sampling and testing on construction materials as per project standards.
- ♦ Provide daily diaries, as-built plans, log in testings.
- ♦ Advise the Engineer of violations and recommends adjustment to operations to meet project requirements.
- ♦ Provide consultation, investigations, evaluations and written documentation in the analysis of subsurface, site conditions and other Geotechnical issues as requested by the Construction Manager.

The knowledge skills and abilities of the Construction inspector and Engineering staff personnel shall include, but not limited to, the following:

- ♦ 3 years of inspection experience including a working knowledge of roadway and structure construction methods, materials, standards, construction symbols and terminology.
- ♦ Knowledge experience in mathematics including algebra, geometry, and trigonometry.
- ♦ Ability to read and interpret roadway, structure and specifications.
- ♦ Communicate effectively with County representatives and Contractor personnel.
- ♦ Expected to hold VDOT or equivalent certifications in the following disciplines:
- ♦ Soil and Aggregate Field Compaction
- ♦ Soil Classification and Structure Foundation
- ♦ Asphalt Field
- ♦ Hydraulic Cement Concrete Field
- ♦ Erosion and sediment control inspection certification
- ♦ Engineering support staff is expected to be Virginia Licensed P.E. Having 10 years of experience in the practice of Engineering defined as where the principles and methods of Engineering are applied to consultation, investigation and evaluation of structures, processes and transportation systems.
- ♦ A materials technician will be required on site at all times when the Contractor is placing embankment, backfilling structures or drainage items and during all concrete pours. The County has provided herein in this section the requirements to be met for Test and Inspections.
- ♦ It shall be the testing firm's responsibility to ensure that Testing and Inspections are provided in accordance with requirement contained in this section.

Prior to any Testing and Inspection services, the testing firm shall provide the County with the Technicians resumes confirming the qualifications of the assigned Technicians providing these services.







| Commissioning Construction |                 |  | Buildings<br>Parks<br>Roads | <b>2.3.7</b> |
|----------------------------|-----------------|--|-----------------------------|--------------|
| <b>Process Owner</b>       | Des             | cription   |                             |              |
| Director                   | Comm            | issioning is a systematic process of assurin   | g that a buildin            | g's          |
| Public Works               | operat<br>plumb | ns perform in accordance with the design in<br>ional needs. This can include systems such<br>ing, and electrical. The County has utilized<br>corder to manage commissioning. | as HVAC, secu               | rity,        |
|                            | The Co          | ounty has set 6 primary goals for the comm   | nissioning proce            | ess:         |
| Process Manager            | <b>♦</b>        | Provide safe and healthy workplaces.   |                             |              |
| Project Manager            | <b>♦</b>        | Optimize energy performance.   |                             |              |
| Construction Manager       | <b>♦</b>        | Reduce operations costs.   |                             |              |
|                            | <b>♦</b>        | Improve orientation and training of oper   | ational/ mainte             | enance       |
| Public Works, Facilities   |                 | staff.   |                             |              |
| Construction Management    | <b>♦</b>        | Provide improved project documentation   | n.                          |              |
| (FCM)                      | <b>♦</b>        | Provide a facility that meets the owner's  | needs.                      |              |

- ♦ **Utility companies** Project Manager coordinates with utility companies throughout process.
- Buildings & Grounds (B&G) Provides feedback as it relates to maintaining systems upon completion of the project. Actively participates in installation and future maintenance issues. Manages building control system through third party contract.
- ♦ Facilities Construction Management (FCM) Manages the third party commissioning contract. Facilitates sustainability concepts of the design.
- ♦ **Property Management** Coordinates impact of systems and/or furniture on design.
- ♦ **Building Development** Inspects projects and provides feedback on code compliance.

## **Timelines: Deadlines, Critical Path Items**

- ♦ **Design Development –** Must begin in early part of the design process to be totally effective.
- ♦ **Construction** Ongoing inspections are conducted during construction.
- ♦ **Substantial Completion** Before occupancy, the commissioning agent must evaluate the systems to ensure they are in conformance with the contract documents and that all systems are functional.
- ♦ **Final Completion** Prior to issuing the certificate of final completion, a full and comprehensive report must be delivered to the owner.

| Materials              | Forms |
|------------------------|-------|
| ♦ Commissioning Report | None  |
| ♦ Intermediate Reports |       |



#### **Reference to Other Processes**

Precedes 2.2.11 Task Order

Occurs throughout 2.2.13 Design Development (Building & Parks)

Occurs throughout 2.2.18 Construction Documents (Buildings & Parks)

Occurs throughout 2.3.8 Construct (Buildings & Parks)

Concurrent 2.3.10 Punchlist Walk Through (Buildings & Parks)

Follows 2.4.1 Final Occupancy

#### **Process Notes**

The County implements commissioning in two phases – installation verification and functional performance testing. These two processes verify and document conformance with the design intent, contract documents and optimal building performance. The commissioning process is essential to the final acceptance of the building and culminates with optimal performance and operational sustainability of the facility.







| Construction (Buildin Construction   | gs & Parks)  | Buildings<br>Parks<br>Roads  | <b>2.3.8</b> |
|--|--|--|--------------|
| <b>Process Owner</b>   | Description  |  |              |
| Director   | The construction of a building occurs in basic phases, many of which   |  |              |
| Public Works   | Works overlap or take place concurrently with each other. This includes clearing and grading, site work, foundations, structure and infra- |  |              |
| Parks & Recreation structure build out, interior finish work and final cleaning of the |  |  |              |
|  | completed building. The architect's role during this period is to  |  |              |
| Process Manager  | interpret the intent of the construction documer   | interpret the intent of the construction documents, provide additional |              |

information as needed, observe progress in the field, issue change

contractor in completing the physical work as depicted in the

orders and complete all inspections to ensure the performance of the

#### Process Manager Project Managers

Parks & Recreation
Public Works

## **Contacts & Roles: Organization, Entity, or Individual**

♦ Facilities Construction Management – Manage the project and process, maintain budget.

construction documents.

- ♦ Buildings & Grounds (B&G) Manage the project and process, maintain budget.
- ♦ **Property Management** Manage the project and process, maintain budget.
- ♦ **Building Development** Perform building inspections.
- ♦ Fire Marshall's Office Perform building inspections.
- ♦ Contractor Perform work.
- ◆ **Purchasing** Support staff and contractual issues.
- ♦ **Environmental Services** Perform site inspections.

## **Timelines: Deadlines, Critical Path Items**

♦ Individualized; varies from project to project.

| Materials                                   | Forms   |
|---|---|
| ♦ Supplemental instruction (Provided by A/E | ♦ Change Order (AIA Document G701)  |
| architect)                                  | <ul> <li>Construction Change Directive (AIA Document<br/>G714)</li> </ul> |
|   | Application and Certificate for Payment (AIA                              |
|   | Document G702)  |
|   | Proposal Request (AIA Document G709)                                      |




#### **Reference to Other Processes**

Occurs throughout 2.3.2 Change Order
Occurs throughout 2.3.3 Request for Payment
Occurs throughout 2.3.7 Commissioning
Precedes 2.3.10 Punchlist Walk Through (Buildings & Parks)
Precedes 2.4.1 Final Occupancy

#### **Process Notes**







| Construction (Roads) Construction     |  | Buildings<br>Parks<br>Roads | 2.3.9<br>□<br>□ |
|---------------------------------------|--|-----------------------------|-----------------|
| Process Owner                         | Description  |                             |                 |
| <b>Director</b> <i>Transportation</i> | After plan approval by VDOT and completion of a bid package, construction is advertised and the lowest responsive and respon |                             | sible           |
| Process Manager                       | bidder is awarded the construction contract.   |                             |                 |
| Project Managers                      | Sometimes during the course of road construction are required for traffic control/routing due to Lar                         |                             |                 |
| Transportation                        | _  |                             |                 |

- ♦ **Contractor** Constructs the job.
- ♦ **VDOT** Conduct periodic inspections. Review and approve changes to the construction plans.
- ♦ Citizens Make special requests that may be accommodated with the project.
- ♦ Transportation Project management and inspection.
- ♦ Consultants Assist in Project Management.
- ♦ Safety/Police Department Work Zone Safety Assistance.

#### **Timelines: Deadlines, Critical Path Items**

- ♦ **Pre-construction meeting** Notice to Proceed (NTP) given and contract executed.
- ♦ Construction deadlines Deadlines need to be met as prescribed in the contract.

# MaterialsForms♦ Transmittals♦ Work Zone Safety Assistance

#### **Reference to Other Processes**

Occurs throughout 2.2.18Construction Documents

Follows 2.6.1 Land Acquisition Overview

Follows 2.5.7 Relocation of Utilities

Occurs throughout 2.3.3 Request for Payment

Occurs throughout 2.3.6 Inspection

Precedes 2.3.11 Punchlist Walk Through (Roads)


Occurs throughout 2.2.11 Task Order

Precedes 2.4.5 Special Events/Ribbon Cutting

Occurs with 2.3.17 Lane Shifts or Lane Closure

#### **Process Notes**







| Punchlist Walkthrough (Buildings & Parks) Construction                     |  | Buildings<br>Parks<br>Roads | 2.3.10<br>☑ ☑ □              |
|--|--|-----------------------------|------------------------------|
| Process Owner  | Description  |                             |                              |
| Parks & Recreation Public Works  | The contractor initially proposes to the owner and architect that construction is "substantially complete", meaning that all insperare completed, a punch list of outstanding work is done and that building can be used by the owner for it's intended use.  The contractor prepares a comprehensive list of all work items are remain to be done. This list, called a punch list, is given to the A or Engineer of record to review and revise as needed. A/E will we site with the GC and owners representatives and review all item remaining. Any item noted that is not complete, substandard or place per the terms of the contract is included on the list. Once completed, the list is signed off on by the GC, A/E, and owner, a |                             | tions                        |
|  |  |                             |                              |
| Process Manager Project Manager Facilities Construction Facilities Manager |  |                             | alk the<br>s still<br>not in |

♦ **Buildings & Grounds (B&G)** – Reviews the building for operational issues and maintenance, long-term care.

incorporated into the Certificate of Substantial Completion.

- ♦ Property Management Observe the facility prior to move-in, in order to coordinate furniture installation and subsequent occupancy by users.
- ♦ **Contractor** Conducts the punchlist walkthrough and completes identified work.
- ♦ **Users** Review to ensure that the space meets their needs.
- ♦ **A/E Consultant** Architect generates the punchlist and arbitrates disputes during the walkthrough.
- ♦ **Environmental Services** Reviews site for proper drainage and environmental compliance.

## **Timelines: Deadlines, Critical Path Items**

**♦ Conduct walkthrough** 

Parks & Recreation
Public Works

- **♦** Issue formal punchlist
- ♦ **Completed work** Within the contract-specified timeframe and prior to move-in.

| Materials | Forms   |
|-----------|---|
| None      | <ul> <li>Certificate of Substantial Completion</li> </ul> |
|           | ♦ Punchlist   |
|           | ♦ Adjacent Property Owners Affidavit                      |



#### **Reference to Other Processes**


Concurrent with 2.3.7 Commissioning
Follows 2.3.8 Construct (Buildings & Parks)
Precedes 2.3.13 Procure & Install Furniture & Equipment
Concurrent with 2.3.14 Procure & Install OIT Data and Telecom Wiring
Precedes 2.4.1 Final Occupancy

#### **Process Notes**

The Owner's representation during this walkthough is critical, since it is the official documentation of outstanding items and establishes the baseline and distinguishes between remaining work and warranty work. The Owner's team includes the Facilities Construction Management Project Manager, a representative from B&G (usually the building engineer assigned to the building) and a representative from Property Management, who is the lead for installing systems furniture and stand alone furniture in the space. At the conclusion of the walkthrough, these three groups initial off on the punchlist.

The time to complete the punchlist items is determined by contract and is generally 60 to 90 days, depending on the complexity of the project, from the date of the walkthrough. Once all of that work is completed, any items noted are considered a warranty item or latent defect, which is a different process and part of the construction contract.







| Punchlist Walkthroug Construction | gh (Roads)  | Buildings<br>Parks<br>Roads | 2.3.11<br>□<br>□ |
|-----------------------------------|---|-----------------------------|------------------|
| <b>Process Owner</b>              | Description   |                             |                  |
| <b>Transportation</b>             | Punch list issues are items that are not constructed on the project properly, and they must be addressed by the contractor prior to being accepted by VDOT.   |                             |                  |
|                                   | Near the completion of construction, the Project construction inspector, and the contractor walk to prepare a list of all items that need to be address       | he project and              |                  |
| <b>Process Manager</b>            | The contractor addresses all the problems.  | •                           |                  |
| Project Managers  Transportation  | The Project Manager, construction inspector, and the project with a VDOT representative and prep that still need to be fixed or addressed. The conti problems | are a list of all i         | tems             |
|                                   | VDOT walks the project again and certifies that a   | ll issues are res           | olved.           |

- ♦ **VDOT** Inspects and certifies the completion of punch list items.
- ♦ **Transportation** Provides project management and inspects.
- ♦ Contractor Completes punch list items.

## **Timelines: Deadlines, Critical Path Items**

- ♦ **Construction complete** Construction must be substantially complete prior to punch list walkthrough.
- ♦ VDOT first walkthrough Create punchlist.
- ♦ All punch list items addressed Contractor and Project Manager address punch list items.
- ♦ **VDOT final walkthrough** Insures that punch list items have been addressed.
- ♦ **Project Manager** Issue C-5

| Materials | Forms |
|-----------|-------|
| None      | ♦ C-5 |

#### **Reference to Other Processes**

Follows 2.3.6 Inspection


Follows 2.3.9 Construct (Roads)

Precedes 2.4.4 VDOT Street Acceptance

Precedes 2.3.5 Withholding and Releasing Retainage



#### **Process Notes**





| Construction Information  | ition on Social Media   | Buildings<br>Parks<br>Roads | 2.3.12<br>☑<br>☑ |
|---|---|-----------------------------|------------------|
| Process Owner Director of Communications  Office of Executive Management  Process Manager Project Managers  Public Works Transportation | Description  The County's Communications Department utiliz notify citizens of important information due to C Utilizing social media may reduce frustration to t and may also provide for a safer work zone. | ounty constru               | ction.           |

- ♦ Project Manager Drafts message to be posted.
- ♦ **Communications Department** Approves message and posts on social media.

#### **Timelines: Deadlines, Critical Path Items**

♦ Timeliness of Message Posting – Messages should be posted prior to citizens experiencing inconveniences. A good practice is to post the message at least one week prior to an event and then throughout the duration of the construction.

| Materials | Forms |
|-----------|-------|
| None      | None  |


#### **Reference to Other Processes**

Occurs throughout 2.3.8 Construct (Buildings & Parks)
Occurs throughout 2.3.9 Construct (Roads)

#### **Process Notes**

Communication requests that items be submitted at least 10 business days in advance of posting through the Online Communications Manager.







| Procure & Install Furn<br>Construction | niture & Equipment  | Buildings<br>Parks<br>Roads | <b>2.3.13</b> |
|--|---|-----------------------------|---------------|
| Process Owner                          | Description   |                             |               |
| Property Management Division Chief     | Upon completion of construction, the Project Manager p request to office installers and office movers for cost esti |                             | to pick-      |
| Public Works                           | up and installs stand alone and systems furniture   | e, as required.             |               |
| <b>Process Manager</b>                 |   |                             |               |
| <b>Property Management</b>             |   |                             |               |
| Project Managers                       |   |                             |               |
| Public Works                           |   |                             |               |

♦ Property Management Project Managers – Prepare documents and implement tasks to accomplish project goals.

## **Timelines: Deadlines, Critical Path Items**

♦ **Completion of building construction** – Prior to moving in furniture.

| Materials | Forms                        |
|-----------|------------------------------|
| None      | ♦ Project Estimate Worksheet |

## **Reference to Other Processes**

Follows 2.2.10 Procure Interior Design Follows 2.3.8 Construct (Buildings)

#### **Process Notes**

Contact needs to be maintained with facilities construction and Buildings & Grounds to verify moving in of furniture.



| Procure & Install OIT Construction  | Data and Telecom Wiring   | Buildings<br>Parks<br>Roads | <b>2.3.14</b> ☑ ☑ |  |
|-------------------------------------|---|-----------------------------|-------------------|--|
| Process Owner                       | Description   |                             |                   |  |
| Project Manager                     | Project Manager submits a work request to pull data and telecom |                             |                   |  |
| OIT                                 | wiring.   |                             |                   |  |
| Process Manager<br>Project Managers |   |                             |                   |  |
| OIT                                 |   |                             |                   |  |
|                                     | l   |                             |                   |  |

- ♦ Property Management Project Managers Prepare documents and implement tasks to accomplish project goals.
- ♦ **OIT Project Manager** Prepare documents and implement tasks to accomplish project goals.

#### **Timelines: Deadlines, Critical Path Items**

♦ **Completion of building construction** – Prior to installation of data and telecom.

| Materials | Forms                        |
|-----------|------------------------------|
| None      | ♦ Project Estimate Worksheet |

## **Reference to Other Processes**

Follows 2.2.10 Procure Interior Design Follows 2.3.8 Construct (Buildings)

#### **Process Notes**

Contact needs to be maintained with facilities construction, Buildings & Grounds, and Property Management to begin installation of data and telecom.



| Internal Forces Road<br>Construction     | Construction   | Buildings<br>Parks<br>Roads | <b>2.3.15</b> □ □ □ |
|--|--|-----------------------------|---------------------|
| Process Owner Director of Transportation | <b>Description</b> After the plan has been approved by the County  |                             |                     |
| Process Manager Project Managers         | engineer's estimate is less than two million dollars, the Director of Transportation will review the scope of work, complexity of the project and anticipated completion date to determine if work can be completed by the Department of Public Works Construction Services. |                             | e project,          |
| Public Works & Transportation            |  |                             |                     |

- ♦ **Transportation** Project management and inspection.
- ♦ **Public Works** Provide a cost estimate and schedule.
- ♦ **DOT**: Conduct periodic inspections. Review and approve changes to the construction plans.

#### **Timelines: Deadlines, Critical Path Items**

- ♦ Project Manager prepares an estimate
- **♦ Public Works provide their estimate of the work**
- Director approves work (when required)
- ♦ Pre-construction metering: Notice to proceed (NTP) given and agreement signed.
- ♦ Construction deadlines: Deadlines need to be met as prescribed in agreement.

#### **Reference to Other Processes**

Follows 2.3.1 Invitation for Bids (IFB)

Follows 2.6.1 Land Acquisition Overview

Follows 2.56.7 Relocation of Utilities

Occurs throughout 2.3.3 Request for payment.

Occurs throughout 2.3.6 Inspection.


Precedes 2.3.11 Punch list Walk Through(Roads)

Occurs throughout 2.2.11 Task order

Precedes 2.4.5 Special Events/Ribbon Cutting

#### **Process Notes**







| Design-Build Two Ph<br>Request for Qualifica<br>Request for Proposa<br>Construction | ations (RFQ) and   | Buildings<br>Parks<br>Roads                                  | <b>2.3.16</b> □ □ ☑     |
|---|--|--|-------------------------|
| Process Owner Director Finance  | <b>Description</b> The two-phase selection process consists of an R Statement of Qualifications (SOQ) is used to creathree (3) highest-ranked Offerors. Only the Offer   | ite a Short-List o   | f the                   |
| Purchasing Finance  | will be invited to submit a Proposal in response t<br>phase selection process is used for complex or re<br>so the number of Offerors submitting a Proposal<br>down to those most highly qualified Offerors. It i<br>department and processed by the Director of Fin<br>with established rules and regulations. | elatively large pro<br>can be narrowe<br>is initiated by the | ojects<br>ed<br>e using |
| Contacts & Roles: Org   | cial provisions for road projects.   |  |                         |


- ♦ **BOCS** Approve the contract award.
- ♦ **Public Works** Provide information for RFQ and RFP.
- ♦ State Administrator Reviews and approves RFQ and RFP documents for contract when federal or state funding involved.
- ♦ **Project Manager** Completes Solicitation Information Form and provides necessary supporting document for the contract.
- ♦ **Purchasing** To review Solicitation Information Form and issue RFQ and RFP.

## **Timelines: Deadlines, Critical Path Items**


♦ RFQ and RFP

| Materials | Forms   |
|-----------|---|
| None      | <ul> <li>Solicitation Information Form for Construction</li> </ul>    |
|           | Projects  |
|           | <ul> <li>Solicitation Information Form for RFP Professiona</li> </ul> |
|           | Engineering   |









|                      | Projects Lane Shift or<br>Notification Process  | Buildings<br>Parks<br>Roads  | 2.3.17<br>□<br>□ |
|----------------------|---|--|------------------|
| <b>Process Owner</b> | Description   |  |                  |
| Director             | This process is to get approval for lane shifts, lane closures or detours   |  |                  |
| Transportation       | from Virginia Department of Transportation (VDOT) due to roa sidewalk construction. It is also to inform the public, County |  |                  |
| Process Manager      | Supervisors' office and Management of closures.   | •  |                  |
|                      |   | If work zone safety assistance is required (traffic control), the form |                  |
|                      | must be completed. If personnel are requested an automatic 2 hour charge.   | and canceled, th   | iere is          |
| Transportation       |   |  |                  |

- ♦ **Contractor** Request lane closure approval from VDOT.
- ♦ VDOT Provide approved lane closures/detours.
- Construction Manager Provide copy of approved lane closures/detours and notify all interested parties.

#### **Timelines: Deadlines, Critical Path Items**

- ♦ The contractor shall be guided by the approved plan's authorized lane closure hours and contract special previsions.
- ♦ Prince William County (PWC) Department of Transportation Construction Managers must stress full compliance with VDOT's Virginia Work Area Protection Manual and Manual on Uniform Traffic Control Devices and all applicable lane closure implementation instructions at the pre-construction meetings and on progress meetings ahead of lane closure/shift events.
- ♦ The contractor shall request lane closure approval from VDOT's Lane Closure Advisory Management System (LCAMS).
- ♦ The County Construction Manager shall provide a copy of the approved detours two weeks prior to the detour date to the VDOT permit manager and to the County Transportation Management Analyst I to add to VDOT and County websites.
- ♦ Contractor shall place variable message boards to inform the traveling public one week prior to detour date.
- ♦ VDOT permit manger will add the detour plans to their website.
- ♦ The County Construction Manager shall notify the County Supervisor's office with lane closures and detours.
- ♦ Construction managers must notify PWC communications two weeks ahead of lane closure/shift events.
- ♦ Update PWC communication and media notifications as needed.



- ♦ Issue a press release at least a one week in advance and post on the PWC and Transportation websites. Post advance notices in place per VDOT policies.
- ♦ The contractor shall call VDOT LCAMS when the first lane closure cone/barrel has been placed.
- ♦ The contractor shall call VDOT LCAMS when the last cone/barrel has been removed and the road is reopened back to travelling public.

#### **Materials**

#### **Forms**

♦ None

♦ Work Zone Safety Assistance

#### **Reference to Other Processes**

Can Occur throughout 2.3.9 Construction (Roads)



| Final Occupancy Close Out                  |   | Buildings<br>Parks<br>Roads | <b>2.4.1</b>         |
|--|---|-----------------------------|----------------------|
| Process Owner                              | Description   |                             |                      |
| Director  Parks & Recreation  Public Works | The contractor initially decides that the construction work is complete, including all punch list items, and is ready for a final inspection by the owner and architect. The final application for payment, along with supporting data, must accompany the contractor's request for final inspection. The supporting data includes an Affidavit of Payment of Debts and Claims (AIA form G706), Affidavit of Release of Liens (AIA form G706A), Consent of Surety (AIA form G707) and a statement of insurance turnover. Also required are all as-built drawings and site plan for the project. |                             |                      |
| Process Manager County Architect           |   |                             |                      |
| Parks & Recreation<br>Public Works         | When the architect determines that the work is acceptable and in conformance with the contract documents, the architect will promptly issue a Certificate of Final Completion. Upon issuance of this document, agreement that the work is finally complete, final payment and release of all remaining retainage is made.   |                             | omptly<br>cument, or |

♦ **General Contractor** – Submits request for final inspection.

#### **Timelines: Deadlines, Critical Path Items**

- ♦ Contractor makes request for final inspection and application for payment Work must be complete before Certificate of Final Completion can be issued.
- ♦ Certificate of Final Completion Architect issues Certificate of Final Completion if determined that work is acceptable.

| Materials                         | Forms  |
|-----------------------------------|--|
| ♦ Statement of Insurance Turnover | <ul> <li>Contractor's Affidavit of Payment of Debts and<br/>Claims (AIA Document G706)</li> <li>Contractor's Affidavit of Release of Liens (AIA</li> </ul> |
|                                   | Document G706A)  ♦ Consent of Surety Company to Final Payment (AIA Document G707)  |


#### **Reference to Other Processes**

Follows 2.3.8 Construct (Buildings and Parks)
Follows 2.3.10 Punchlist Walkthrough (Buildings and Parks)

Precedes 2.4.2 Acquire Insurance



#### **Process Notes**






| Acquire Insurance<br>Close Out  |  |                    | Buildings<br>Parks<br>Roads | <b>2.4.2</b> |
|---|--|--------------------|-----------------------------|--------------|
| Process Owner Director  Finance  Process Manager Risk Management Division Chief   | Description  During construction, the contr However, once the facility has County can occupy the buildin insurance policy. | reached substantia | al completion and           | d the        |
| Finance  Contacts & Roles: Org  ◇ Risk Management – Acquire  ◇ Public Works – Provides buil  ◇ Insurer – Adds new facility to | s insurance.<br>ding data to Risk Management.  |                    |                             |              |
| Timelines: Deadlines,  ♦ Acquire insurance prior to o  Materials  ♦ Letter from GC to County sta                              | Critical Path Items  | Forms<br>None      |                             |              |
| Reference to Other P  | rocesses   |                    |                             |              |



Concurrent 2.4.1 Final Occupancy





| Warranty Period<br>Close Out          |  | Buildings<br>Parks<br>Roads | <b>2.4.3</b> |
|---------------------------------------|--|-----------------------------|--------------|
| Process Owner                         | Description  |                             |              |
| Director                              | The warranty period begins upon satisfactory con   | •                           |              |
| Parks & Recreation Public Works       | by the County. Documents supporting maintenant   | nce and operati             | ions are     |
| Process Manager                       | provided. Contacts are established to support the Building Engineer assigned to the site holds t | •                           |              |
| Buildings & Grounds Division<br>Chief | supporting the warranty.   |                             |              |
| Parks & Recreation Public Works       |  |                             |              |

- ♦ **General Contractor, Subs, Architect** Transition of responsibilities from contractor to County.
- ♦ Buildings & Grounds (B&G) Receives the warranty, operates in its parameters for the specified time, and facilitates the transition of responsibilities from contractor to County. Occasionally performed via a third party contract.
- ♦ **Building occupants** Receivers of the support efforts and maximize contractual agreements.
- ♦ Public Works Maximize contractual agreements. Notifies General Contractor of areas of non-compliance.
- ♦ Purchasing Maximize contractual agreements.

## **Timelines: Deadlines, Critical Path Items**

- **♦** Construction complete
- **♦ Maintenance and Operations Documents**

| Materials                                  | Forms |
|--|-------|
| ♦ Binder of all warranties from contractor | None  |

#### **Reference to Other Processes**

Follows 2.3.8 Construct (Buildings)

Follows 2.3.10 Punchlist Walkthrough (Buildings)

Precedes 2.4.2 Acquire Insurance




#### **Process Notes**

The general contractor warrants to the owner and architect that all materials and equipment will be of good quality and new (unless otherwise stated) and that the work will be free from defects and will conform to the requirements stated in the contract documents.

At the time of substantial completion, the GC will provide to the owner a complete list of all written warranties and related documents. These are listed in the specification portion of the contract documents. The warranty period begins on the date of issuance of the Certificate of Substantial Completion, unless otherwise noted.

The warranty period is 12 months, unless modified by contract. If, during that time, any work is found to be not in accordance with the contract documents, the contractor is responsible to correct it promptly when notified by the owner. In some instances or situations, extended warranties may be issued for parts of the work or included in the contract. Generally, this is for items of work or equipment that may have been replaced or repaired in the punchlist phase or during the warranty phase or may be questionable in terms of its performance. This is no a typical situation and is done on an as-needed basis, with assistance from the County Attorney's office.







| VDOT Acceptance<br>Close Out                     |  | Buildings<br>Parks<br>Roads | <b>2.4.4</b> □ □ □ |
|--|--|-----------------------------|--------------------|
| Process Owner Manassas Resident Engineer  VDOT   | <b>Description</b> Roads constructed by the County are turned ove operation and maintenance through the street a | cceptance process           | s. The             |
| Process Manager Project Managers  Transportation | County contractor is responsible for maintenance accepted by VDOT.   | e until the road is         |                    |

- ♦ **BOCS** Requests VDOT to accept the road into the state secondary system.
- ♦ Contractors Correct deficiencies.
- ♦ VDOT Prepares final street acceptance documents and assumes maintenance responsibilities for the road.
- ♦ **Transportation** Project Manager Schedule's documentation review with VDOT and prepares the BOCS resolution and staff report.
- ♦ Design Manager Reviews Plats and Plans

## **Timelines: Deadlines, Critical Path Items**

- ♦ All plats recorded Clerk of the Court records the plats.
- ♦ All legal documents recorded County Attorney records legal documents.
- ♦ **As-Built Plans** Provided by the contractor.
- ◆ **Agreement for structures** County and state agree on maintenance of any structures.

# Materials ♦ Bond Acceptance documents ♦ Transmittals Forms ♦ VDOT Street Acceptance Checklist

## **Reference to Other Processes**

Precedes 2.8.1 Board Agenda Follows 2.3.11 Punchlist Walk Through (Roads and Buildings) Follows 2.3.9 Construct (Roads)



#### Flow Chart Note: a) Project Manager ensures all Project completed (County utilities' land use permits are in order, Comprehensive Inspection Program). and all easements within proposed right of way are quick claimed, before project completion. b) BOCS resolutions should be Design Manager reviews plats and plans, initiated 60 days prior to anticipated identifies streets eligible for acceptance, date of acceptance. and prepares BOCS draft resolution. Project Manager schedules documentation review with VDOT per LAP requirements. VDOT reviews County documentation. Yes The Contractor corrects Deficiencies? deficiencies. No Project Manager inspects site with Prince William County contractor to identify deficiencies. Virginia DOT Contractor corrects all deficiencies. The County installs route numbers. Deficiencies No corrected within 30 The County schedules final inspections days? with VDOT. VDOT conducts final inspection and accepts all documents from the County. The County requests VDOT to perform preliminary inspection of streets with the County and assigns route numbers. The County provides a copy of BOCS approved resolution to VDOT. VDOT conducts preliminary inspection of streets with the County and assigns VDOT prepares final street acceptance route numbers. package and forwards to Central Office Local Assistance Division (LAD). No Deficiencies? **VDOT** assumes maintenance Yes responsibility of new street. The County requests developer to correct deficiencies. LAD accepts streets into Secondary System. VDOT Deficiencies Yes notifies the County and enters No corrected within 30 streets into listing. days?



| Special Event/Ribbon Cutting |           | 2.4.5                   |
|------------------------------|-----------|-------------------------|
| •                            | Buildings | $\overline{\checkmark}$ |
| Close Out                    | Parks     | $\overline{\checkmark}$ |
|                              | Roads     | $\square$               |
|                              |           |                         |

## Process Owner Director

## **Description**

Office of Executive Management Upon completion of a capital project, a special event may be held to mark the conclusion of the project. These are usually conducted at the request or decision of the BOCS. Special events are organized and run by the Office of Communications. Department staff must provide necessary information to the Office of Communications for special events.

## Process Manager Public Information Specialist

Office of Executive Management, Communications

## **Contacts & Roles: Organization, Entity, or Individual**

- ♦ **BOCS** Requests, attends, or participates in special event.
- ◆ **Project Manager** Prepares event checklist and coordinates with Communications staff.
- ♦ Communications staff Confirm event date with BOCS, County Executive Office, and participants. Organize special event.
- ♦ **Contractors, subcontractors** Invited to attend special event.
- ♦ Other special guests Invited to attend special event.
- ♦ Police Provide traffic safety.

## Timelines: Deadlines, Critical Path Items


♦ **Project Completion** – Project must be substantially complete and free from user risk.

| Materials | Forms                      |
|-----------|----------------------------|
| None      | ♦ Special Events Checklist |

#### **Reference to Other Processes**

Follows 2.3.9 Construct (Roads) Follows 2.3.8 Construct (Buildings)








| Plat Development<br>Close Out   |  | Buildings<br>Parks<br>Roads | <b>2.4.6</b> |
|---|--|-----------------------------|--------------|
| Process Owner Director  Parks & Recreation Public Works  Process Manager Project Managers  Parks & Recreation | <b>Description</b> Upon completion of infrastructure construction, plat preparation from the A/E consultant. | Public Works red            | quests       |
| ♦ <b>Users</b> – Express specific need  | preparation of plats with A/E consultant.  |                             |              |
| Timelines: Deadlines,  ♦ Project complete  ♦ Plat sent to County Attorney                                     | Critical Path Items y – County Attorney prepares and records deeds.  |                             |              |
| Materials<br>None   | <b>Forms</b><br>None   |                             |              |
| Reference to Other P  | rocesses   |                             |              |

## **Process Notes**

Follows 2.3.8 Construct (Buildings)







| Release of Liens                |   |                     | 2.4.7                   |
|---------------------------------|---|---------------------|-------------------------|
| Close Out                       |   | Buildings           | $\overline{\checkmark}$ |
| Close Out                       |   | Parks               |                         |
|                                 |   | Roads               |                         |
| Process Owner                   | Description   |                     |                         |
| Directors                       | •   | معنمام ممسمسطمس     |                         |
|                                 | A lien on a project is defined as any financial encu<br>financial security interest placed on a material su |                     |                         |
| Public Works & Finance          | for materials and/or work performed, but not yet  | •                   | actor                   |
|                                 | General Contractor. Per the County Code/Code of   | •                   | e not                   |
|                                 | permissible on county jobs since payments are or  | -                   |                         |
|                                 | actually performed. The Code also stipulates that   | •                   |                         |
|                                 | paid to a GC and owed to a supplier or subcontract  | •                   |                         |
|                                 | appropriate party within 7 days of receipt of fund  | s                   |                         |
|                                 |   |                     |                         |
| Drocoss Managar                 | A release of liens is a document that states all pay  | ments, barring a    | ny                      |
| Process Manager                 | other arrangements between the GC/Supplier/Su   |                     |                         |
| Project Manager                 | been made and there are no outstanding financia   | _                   | n                       |
| D. Idlanda                      | though not required by Code, releases are reques  | -                   |                         |
| Public Works                    | categories of work or high dollar items to ensure   |                     |                         |
|                                 | and suppliers are being paid in accordance to the   |                     | _                       |
|                                 | can be either during the project as part of the pay   | •                   | 5                       |
|                                 | completion of the project. This will be outlined in   |                     | :+                      |
|                                 | documents between the GC and the County and c   | can vary from pro   | ject                    |
|                                 | to project.   |                     |                         |
|                                 |   |                     |                         |
| Contacts & Roles: Org           | anization, Entity, or Individual  |                     |                         |
| ♦ Project Managers – Manage     | •   |                     |                         |
|                                 | list may request forms for review in situations whe   | re there may be     | a                       |
| dispute.                        |   |                     |                         |
| ♦ Contractor – Supplies the rel | ease of liens.  |                     |                         |
|                                 |   |                     |                         |
| <b>Timelines: Deadlines,</b>    | Critical Path Items   |                     |                         |
| ♦ Release of Liens – Must be re | eceived before a final payment can be made.   |                     |                         |
|                                 |   |                     |                         |
| Materials                       | Forms   |                     |                         |
| None                            | ♦ Contractor's Affidavit of Re  | places of Lione (A  | IΛ                      |
| NOHE                            | Document G706A)   | ciease oi Lieils (A | IA                      |

## **Reference to Other Processes**

Precedes 2.4.1 Final Occupancy



| Process Owner Director Once a project is completed and all revenue and expenditures have been recorded in ASCEND, the Project (if applicable) needs to be closed so no further transactions can be posted to the project.  Process Manager Accounting Division Chief | Accounting Project Cose Out               | lose-Out   | Buildings<br>Parks<br>Roads | <b>2.4.8</b> |
|--|---|--|-----------------------------|--------------|
| Finance  | Process Manager Accounting Division Chief | Once a project is completed and all revenue and been recorded in ASCEND, the Project (if applica | ble) needs to be            |              |

- ♦ **Transportation** Coordinate with Finance to close Project. Complete the Closure Checklist.
- ♦ **Public Works** Coordinate with Finance to close Project. Complete the Closure Checklist.
- ♦ Parks & Recreation Coordinate with Finance to close Project. Complete the Closure Checklist.
- ♦ **Finance** Complete final review and close project in accounting system.
- ♦ **Budget** Reviews closure of Project.

## **Timelines: Deadlines, Critical Path Items**


♦ Completion of the ASCEND OCA Closure Checklist – Project Manager ensures that all project revenues and expenditures are finalized.

| Materials | Forms  |
|-----------|--|
| None      | ♦ Project Closure Checklist ASCEND           |
|           | ♦ Project Closure Checklist (Transportation) |

#### **Reference to Other Processes**

Occurs throughout 2.3.4 Draw Downs for Bond- or Lease-Funded Projects Occurs throughout 2.3.5 Withholding and Releasing Retainage







| VDOT Audit<br>Close Out        |  | Buildings<br>Parks<br>Roads   | <b>2.4.9</b><br>□<br>□      |
|--------------------------------|--|---|-----------------------------|
| Process Owner                  | Description  |   |                             |
| Federal Highway Administration | This process may be necessary when administeri funded projects, in which case a random audit of and project records may be conducted to verify of federal and state laws and regulations and any reproject agreement. Project records must be main not less than three years following Federal Highway (FHWA) acceptance of the final youcher, and the | f basic construct<br>compliance with<br>equirements with<br>ntained for a pe<br>vay Administrat | tion  thin the riod of cion |
| Process Manager                | such records available to VDOT upon request.   | ,   |                             |

- ♦ **VDOT** Requests, conducts, and approves audit.
- ♦ **Transportation** Provides necessary documentation.

## **Timelines: Deadlines, Critical Path Items**

♦ **Project completion** – Follows VDOT acceptance.

#### **Materials**

- ♦ Project Acceptance Letter
- ♦ Source of Materials C-25
- ♦ Certification Statement TL-131
- ♦ Materials Notebook TL-142
- ♦ Electronic Plans As Built Plans

#### **Forms**

♦ Road Notification Inventory Form M4.01 Official Start & End Dates C-5

## **Reference to Other Processes**

Follows 2.4.4 VDOT Street Acceptance

#### **Process Notes**

Additional information can be found *Guide for Local Administration of Virginia Department of Transportation Projects* and the Office of Management and Budget's Circular No. A-133.

http://www.virginiadot.org/business/locally administered projects manual.asp http://www.whitehouse.gov/omb/circulars/a133 compliance supplement 2012



VDOT Audit 2.4.9

The following forms/resources and processes are to be followed only for Federal/State Projects:

#### **CONTRACT DOCUMENTS**

LPA to send VDOT a copy of LPA's written project acceptance letter.

LPA to prepare and submit C-5 to VDOT. (To include start and end dates).

LPA to prepare and submit M4.01 (Road Notification Inventory Form) to VDOT.

LPA to prepare and submit final (As Built Plans) Electronic Plans to VDOT in PDF format.

LPA to submit final C-25 source of material's form to VDOT.

LPA to submit final Materials Notebook (TL-142) to VDOT.

LPA to submit Materials Certification Statement (TL-131) to VDOT.

#### FINAL INVOICING

LPA to establish final contract value and provide a document to VDOT indicating that all parties are in agreement with the final contract value.

LPA to prepare final invoice and have it reviewed by an independent reviewer not affiliated with the project. LPA to submit final invoice to VDOT as well as documentation of invoice verification.



| Transition of Operation Close Out                               | ng Budget   | Buildings<br>Parks<br>Roads | <b>2.4.10</b> |
|---|---|-----------------------------|---------------|
| Process Owner   | Description   |                             |               |
| Director  | This process covers the shift of operational respo  | •                           |               |
| Parks & Recreation Public Works                                 | structure from the contractor to the County. This staffing, utility responsibilities, and all services. Ir identified in CIP development with annual review | nitial funding is           | ;             |
| Process Manager   | the budget process.   |                             |               |
| Buildings & Grounds or<br>Property Management<br>Division Chief | NOTE: CIP designation must convert to the Gener<br>costs, identified in the CIP, must be approved thr<br>budget process prior to completion of the facility | ough the annu               |               |
| Parks & Recreation Public Works                                 |   |                             |               |

- Buildings & Grounds (B&G) Coordination of funding shift during budget cycle approximating completion. Internal shift of funding. Reports and track the funding to the General Fund. Manage funding transfer.
- ♦ **Property Management** Manage the utility costs. Provide an estimate of the utility costs for the Parks facility, which is the basis for the General Fund budget request.

## **Timelines: Deadlines, Critical Path Items**

- ♦ CIP Established Operating and one time costs are calculated on the best available information at the time of submission of the CIP project.
- ♦ Cost Reviews Conducted annually during the CIP budget process to update operating and one-time costs.
- ♦ Establishment of General Fund Budget Time is critical to have funding in place and for obtaining staff, supplies, and one time items in advance of construction completion. Staffing/hiring is complex and is usually started 12 months in advance of anticipated construction completion to support building inspection, training, project management, and occupancy.


| Materials                     | Forms |
|-------------------------------|-------|
| ♦ CIP forms                   | None  |
| ♦ Budget (General Fund) forms |       |

### **Reference to Other Processes**

Precedes 2.8.2 Life Cycle Management



## **Process Notes**





| <b>Identify Existing Utili</b> Utility Relocation  | ties and Conflicts  | Buildings<br>Parks<br>Roads | <b>2.5.1</b> □ □ □ |
|--|---|-----------------------------|--------------------|
| Process Owner Director  Transportation  Process Manager Project Managers  Transportation | Description  During design, all utilities and conflicts within the identified by the consulting engineer. Utilities are coordination with utility companies, reviewing ollocation by a utility locating contractor. Usually performs of the consulting contractor of the consulting contractor. | e identified thro           | ough<br>eld        |

- ♦ **Utilities Companies** Identify and mark utilities.
- ♦ Service Authority (PWCSA) Identify utilities.
- ◆ Transportation Coordinates with utility companies and Service Authority team. Schedules and conducts UFI meeting.
- ♦ A/E Consultants Complete UT-9's

## **Timelines: Deadlines, Critical Path Items**

- **♦ Determine potential conflicts**
- **♦** Coordinate with utility companies
- ♦ Order test holes Determine exact location of the utilities.

| Materials      | Forms  |
|----------------|--------|
| ♦ UFI          | ♦ UT-9 |
| ♦ Transmittals |        |


#### **Reference to Other Processes**

Precedes 2.2.14 Design Development (Roads)

- 2.5.1 UFI meeting is held and utility companies are provided with project plans by the consultant engineer.
- 2.5.2 After review of plans, utility companies submit easement requests. Based on their request, A/E consultant prepares plats. Once all easements are finalized, utility companies submit a completed plan and estimate.
- 2.5.2 The A/E Consultants reviews and approves the plan and estimate and completes the P&E checklist (UT-9). Based on the approved plan and estimate, purchase orders are set up for each utility company.



- 2.5.3 Right-of-way team works on acquiring easements. Once easements are acquired, a letter is sent to utility company authorizing them to initiate relocation. If the utility company is abandoning any easement, then a "quit claim" must be processed.
- 2.5.5 If both contractor and utility company are expected to be on the project at the same time, a special provision must be added to the bid documents that denotes coordination between the contractor and utility company.
- 2.5.1 Determining Potential Conflicts—Possible conflicts are identified on the plans and verified by performing utility test holes. Usually pipe and culvert crossing are potential conflict areas.





| Process Owner Director Utility companies will check the UT-9 from the A/E Condetermine priority rights. Depending on the findings of the percent obligation of the utility company and Transportation | 'E Consultant to        |
|---|-------------------------|
| Process Manager Project Managers  Transportation  | ngs this form will show |

- ♦ **Utility companies** Review UT-9. Provide a cost and time estimate for relocation.
- ♦ **Transportation** Project Manager consults with A/E consultant to review and approve estimates.
- ♦ A/E Consultant Prepares Appendix 21.

## **Timelines: Deadlines, Critical Path Items**


- ♦ 60% Plans Project Manager schedules UFI.
- ♦ A/E Consultant prepares Appendix 21
- ♦ Utility company reviews Appendix 21
- ♦ Determination of responsibilities between County and utility company.

| Materials | Forms         |
|-----------|---------------|
| None      | ♦ Appendix 21 |

#### **Reference to Other Processes**

Precedes 2.5.1 Identify Existing Utilities and Conflicts







| Acquire Easements Utility Relocation |   | Buildings<br>Parks<br>Roads | <b>2.5.3</b> □ □ □ |
|--------------------------------------|---|-----------------------------|--------------------|
| Process Owner Director               | <b>Description</b> The County must acquire all necessary easement | s, temporary or             |                    |
| Transportation                       | permanent, for utility relocations.                               |                             |                    |
| Process Manager                      |   |                             |                    |
| Project Managers                     |   |                             |                    |
| Transportation                       |   |                             |                    |

- ♦ **Transportation** Project Manager receives and approves the easement requests submitted by the utility company.
- ♦ A/E Consultant Provide plans, which determine the easement requirements; submit temporary and permanent construction easements.
- ♦ **Title search company** Provide title report.
- ♦ Appraisal company Provides appraisals.
- ♦ **Utility companies** Submit easement requests.
- ♦ Property owner Reviews and negotiates compensation for easements with County Right-of-Way agent.
- ♦ Right-of-Way agent Negotiates compensation for easements with property owners; prepares BOCS report.
- ♦ **BOCS** Authorizes Public Hearings and condemnations of land for easements; grant easements and transfer to utility companies.
- ♦ County Attorney Prepares COT (Certificate of Taking) and records deeds.
- ♦ Circuit Court Hold easement compensation until agreement is reached with property owner.

## **Timelines: Deadlines, Critical Path Items**

- ♦ **70% plans** Given to utility companies to determine conflicts and relocations.
- ♦ Order Plats From A/E consultant.
- ♦ **Negotiations** Right-of-Way agent begins negotiations with property owner. The County must make a bona fide offer before preceding with COT.
- ♦ **Settlements** If the County and the owner can successfully negotiate compensation, the County proceeds to settlement.
- ♦ **COT** If settlement cannot be reached, the County proceeds with COT, which necessitates BOCS action.

| Materials | Forms |
|-----------|-------|
| None      | None  |



## **Reference to Other Processes**

Concurrent with 2.2.14 Design Development (Roads)

Concurrent with 2.4.6 Plat Development

Concurrent with 2.6.4 Secure Appraisal

Concurrent with 2.6.5 Make the Offer


Concurrent with 2.6.6 Negotiate

Concurrent with 2.6.7 Settlement

Concurrent with 2.6.8 Condemnation

Precedes 2.6.9 Court Proceeding







| Upgrades (Betterment Utility Relocation  | nts)  | Buildings<br>Parks<br>Roads | <b>2.5.4</b> □ □ □ |
|--|---|-----------------------------|--------------------|
| Process Owner Director  Transportation  Process Manager Project Managers  Transportation | Description  Upgrade of the utilities occurs when an existing I and there is a road project that will relocate utilidecides that they will pay for upgrade. |                             |                    |

- ♦ **BOCS** Approves betterment agreement.
- ♦ **Transportation** Project Manager provides information to A/E consultant.
- ♦ Service Authority (PWCSA) Requests betterments and approves plans.
- ♦ A/E Consultant Incorporates betterments in the plans.

## **Timelines: Deadlines, Critical Path Items**

- ♦ **Appendix 21** Documents water or sewer conflicts.
- ♦ PWCSA checks and recommends upgrades PWCSA must approve upgrades prior to incorporation in the design plans.
- ♦ A/E consultant changes plans Upgrades must be incorporated into the design plans prior to construction.

| Materials | Forms         |
|-----------|---------------|
| None      | ♦ Appendix 21 |

#### **Reference to Other Processes**


Concurrent 2.2.14 Design Development (Roads)

Precedes 2.5.7 Relocation of Utilities

Precedes 2.3.9 Construct (Roads)

Concurrent 2.8.1 Board Agenda







| Request/Authorize W<br>Utility Relocation | /ork  | Buildings<br>Parks<br>Roads | <b>2.5.5</b> □ □ □ |
|---|---|-----------------------------|--------------------|
| Process Owner Director                    | <b>Description</b> Transportation needs to send a letter to the utility | ty companies to             | )                  |
| Transportation                            | request work to start with relocations.                                 |                             |                    |
| <b>Process Manager</b>                    |   |                             |                    |
| <b>Project Managers</b>                   |   |                             |                    |
| Transportation                            |   |                             |                    |

- ♦ Utility companies Provide utility relocation plans and estimates and request Notice to Proceed (NTP).
- ♦ **Transportation** Project Manager will provide UT-9 for to utility company, review and negotiate cost estimate, checks on task order status, and if approved, sends NTP.

## **Timelines: Deadlines, Critical Path Items**


- ♦ **Task order** Task order must be approved before NTP can be sent.
- ♦ Notice to Proceed (NTP) Project Manager sends NTP.

| Materials | Forms  |
|-----------|--|
| None      | VDOT Utility Manual (Appendix No. 4 UT-9 Utility Field Inspection)           |
|           | VDOT Utility Manual (Appendix No. 5 UT-9A<br>Underground Utility Data Sheet) |
|           | VDOT Utility Manual (Appendix No. 21 Plan and                                |
|           | Estimate Check List)   |

#### **Reference to Other Processes**

Precedes 2.5.2 Negotiate Fee Arrangements Follows 2.2.11 Task Order







| Dispose of Old Mater   | rial  |                    | 2.5.6 |
|------------------------|---|--------------------|-------|
| Utility Relocation     |   | Buildings<br>Roads |       |
| <b>Process Owner</b>   | Description   |                    |       |
| Director               | All utility companies are responsible for removal and disposal of all   |                    |       |
| Transportation         | material as a result of relocations. They are responsible to inform Miss Utility of Virginia about abandoned lines and location of new lines. |                    |       |
| <b>Process Manager</b> | othicy of virginia about abandoned lines and loca   | ation of new line  | 3.    |
| Project Managers       |   |                    |       |
| Transportation         |   |                    |       |
|                        | ganization, Entity, or Individual   | remaining mate     | rial  |

- Transportation Project Manager informs utility companies about removal of remaining material.
- ♦ **Utility company** Remove remaining material.


## **Timelines: Deadlines, Critical Path Items**

- **♦** Relocation is complete
- **♦ Remove old material**
- **♦ Abandon lines**
- ♦ Inform Miss Utility

| Materials | Forms |
|-----------|-------|
| None      | None  |

## **Reference to Other Processes**







| Relocation of Utilitie Utility Relocation | S   | Buildings<br>Parks<br>Roads | <b>2.5.7</b> □ □ □ |
|---|---|-----------------------------|--------------------|
| Process Owner Director                    | Description  Existing utilities must be relocated to accommodate improvements to the roadway. Easements must be acquired prior to relocation. Utilities may include phone lines, cable, water and wastewater, storm sewer, gas, and electric. |                             |                    |
| Transportation                            |   |                             |                    |
| Process Manager                           |   |                             | ewer,              |
| Project Managers                          |   |                             |                    |
| Transportation                            |   |                             |                    |

- ♦ **Transportation** Project Manager oversees relocation operations.
- ♦ **Utility companies** Provides relocations.

## **Timelines: Deadlines, Critical Path Items**


- ♦ Notice to Proceed (NTP) Work may begin when a formal notice is given to proceed.
- **♦ Utility company performs work**

| Materials | Forms |
|-----------|-------|
| None      | None  |

## **Reference to Other Processes**

Follows 2.5.3 Acquire Easements Follows 2.5.5 Request/Authorize Work Precedes 2.3.9 Construct (Roads)







| Land Acquisition Overview Land Acquisition |  | Buildings<br>Parks<br>Roads | 2.6.1<br>□<br>□ |
|--|--|-----------------------------|-----------------|
| Process Owner                              | Description  |                             |                 |
| Director                                   | Acquisition is the process of acquiring real property (real estate) or some interest therein. In the course of building roads, often the County must acquire property from private owners. This section provides an overview of the acquisition process. More detailed information about individual aspects of land acquisition is found in the remaining sections |                             |                 |
| Transportation                             |  |                             |                 |
| <b>Process Manager</b>                     |  |                             |                 |
| Right-of-Way Agent                         |  |                             |                 |
| Transportation                             | of 2.6.  |                             |                 |
| Transportation                             |  |                             |                 |

- ♦ **Engineering and Construction Firms** Supply plans and plats.
- ♦ Citizens Supply feedback on road alignment, which determines property requirements.
- ♦ **Departmental Accounting** Prepares purchase order.
- ♦ Finance Reviews acquisition.
- ♦ **Budget** Reviews acquisition.
- ♦ County Attorney Reviews acquisition.
- ♦ **County Executive** Approve certificates of take and settlements \$300,000 \$500,000.
- ♦ **BOCS** Approve certificates of take and settlements over \$500,000.
- ♦ Appraisers Provide appraisals.
- ♦ **Title search company** Provide title report.
- ♦ **Project Manager** Coordinate property acquisition with the construction schedule.

## **Timelines: Deadlines, Critical Path Items**

- ♦ **GPIN parcel listings** Receive from Project Manager.
- ♦ **Title Search** Contractor.
- ♦ Plat Contractor.
- **♦ Appraisal** Contractor.
- ♦ Purchase Order Department Accounting.


| Materials             | Forms |
|-----------------------|-------|
| ♦ GPIN parcel listing | None  |
| ♦ Project plans       |       |
| ♦ Appraisal           |       |



## **Reference to Other Processes**

Occurs throughout 2.8.1 Board Agenda Follows 2.2.11 Task Order Precedes 2.3.1 Invitation for Bid (IFB) Occurs throughout 2.2.2 Public Hearings Occurs throughout 2.3.9 Construct (Roads)







| Title Search Land Acquisition         |   | Buildings<br>Parks<br>Roads | 2.6.2<br>□<br>□ |
|---------------------------------------|---|-----------------------------|-----------------|
| Process Owner Director                | Description  The purpose of this process is to produce a title report for the acquisition of land from private property owners. The title report determines ownership of all property interests to be acquired. |                             |                 |
| Transportation                        |   |                             | rt              |
| Process Manager<br>Right-of-Way Agent | determines ownership of all property interests to   | o be acquired.              |                 |
| Transportation                        |   |                             |                 |

# Contacts & Roles: Organization, Entity, or Individual

- ♦ Project Manager Provides GPIN listing.
- ♦ **Title Search Company** Produces a title report.

# **Timelines: Deadlines, Critical Path Items**

- ♦ **GPIN parcel listing** Supplied by Project Manager.
- ♦ **Task and Purchase Orders** Completed by Transportation Accounting.
- ♦ **Quote for service** Supplied by title search company.

| Materials  | Forms |
|--|-------|
| <ul> <li>Vendor contract list (located on Purchasing<br/>website)</li> </ul> | None  |

#### **Reference to Other Processes**


Concurrent 2.2.11 Task Order Precedes 2.6.3 Receive Plat

#### **Process Notes**

Right-of-Way agent works with project manager to select title search company using the on-call vendor list.



Title Search 2.6.2





| Receive Plat Land Acquisition   |   | Buildings<br>Parks<br>Roads | <b>2.6.3</b> □ □ □ |
|---|---|-----------------------------|--------------------|
| <b>Process Owner</b>  | Description                                       |                             |                    |
| Director  | The purpose of this process is to produce a plat. | •                           | ary for            |
| Transportation  | the acquisition of land from private property own | ners.                       |                    |
| <b>Process Manager</b>  |   |                             |                    |
| Right-of-Way Agent  |   |                             |                    |
| Transportation  |   |                             |                    |
| Contacts & Roles: Organization, Entity, or Individual  ♦ Project Manager – Coordinates distribution and approval of the plat.  ♦ GIS Specialist – Reviews plat for accuracy.  ♦ Engineering Firm – Produces plat. |   |                             |                    |
| <ul> <li>◇ Right-of-Way – Uploads title report; reviews and approves plat.</li> </ul>   |   |                             |                    |

# **Timelines: Deadlines, Critical Path Items**

♦ **Title Report** – Received from title Search Company.

| Materials | Forms |
|-----------|-------|
| None      | None  |


## **Reference to Other Processes**

Follows 2.6.2 Title Search Precedes 2.6.4 Secure Appraisal

## **Process Notes**



Receive Plat 2.6.3





| Secure Appraisal Land Acquisition                 |  | Parks<br>Buildings<br>Roads | 2.6.4<br>□<br>□ |
|---|--|-----------------------------|-----------------|
| Process Owner Director Transportation             | Description  The purpose of this process is to acquire a real property (real estate) appraisal. The appraisal is the basis for determining the amount the County will offer to acquire land from a property owner. |                             | •               |
| Process Manager Right-of-Way Agent Transportation |  |                             |                 |
| Contacts & Roles: Or                              | ganization. Entity, or Individual  |                             |                 |

- ♦ Purchasing Supplies a vendor contract list.
- ♦ **Transportation Accounting** Creates task order and purchase order.

## **Timelines: Deadlines, Critical Path Items**

- ♦ **Title Report** Supplied by the title search company.
- ♦ **Plat** Supplied by the engineering firm.

#### **Materials Forms**

♦ GPIN parcel listing

- None
- ♦ Vendor contract list (located on the Purchasing website)
- ♦ Construction plan
- ♦ Purchase Order


#### **Reference to Other Processes**

Concurrent with 2.2.11 Task Order Follows 2.6.3 Receive Plat Precedes 2.6.5 Make the Offer

#### **Process Notes**




# Flow Chart (Process A – In-House)





# Flow Chart (Process B – 3<sup>rd</sup> Party/Vendor)





| Make the Offer<br>Land Acquisition    |   | Buildings<br>Parks<br>Roads | <b>2.6.5</b> □ □ □ |
|---------------------------------------|---|-----------------------------|--------------------|
| Process Owner                         | Description   |                             |                    |
| Director                              | This section explains the process for submitting an offer letter settlement of the acquisition of real property (real estate) or sinterest therein. |                             |                    |
| Transportation                        |   |                             |                    |
| Process Manager<br>Right-of-Way Agent | interest therein.   |                             |                    |
| Transportation                        |   |                             |                    |

#### Contacts & Roles: Organization, Entity, or Individual

- ♦ **Property Owner** Accepts or rejects offer; provides information for negotiation.
- ♦ **Director of Transportation** Monitors settlement.
- ♦ Magisterial District Supervisor Monitors settlement.
- ♦ County Attorney Reviews the offer, assists with negotiations, and provides information on any applicable tax leans against the property.

#### **Timelines: Deadlines, Critical Path Items**

- ♦ If no response from property owner within 30 days of mailing the offer letter, a second letter is **distributed** – Copies of all first letter documents are included in the second offer letter.
- ♦ Negotiations end six months after a project is complete Court proceedings will then determine compensation.

#### **Materials Forms**

- ♦ Appraisal
- ♦ Construction Drawing
- **♦** Easements
- ♦ Title Report
- ♦ Plat
- ♦ Right of Entry
- ♦ Mortgage Information Sheet
- ♦ Agreement

- ♦ Settlement Checklist (Property Owners)
- ♦ Settlement Checklist (Churches)
- ♦ Settlement Checklist (Corporations)
- ♦ W9 Form

#### **Reference to Other Processes**

Follows 2.6.2 Title Search Follows 2.6.3 Receive Plat Follows 2.6.4 Secure Appraisal

Precedes 2.6.6 Negotiate




Make the Offer 2.6.5

#### **Process Notes**

The offer letter consists of the appraisal, title report, plat and agreement. In addition to sending the offer letter to the property owner, sections of the offer letter are sent to the Transportation Director, impacted District Supervisor, and County Attorney. Following receipt of the offer letter, the County may enter into negotiations with the property owner in order to reach a signed agreement.


# Flow Chart (Process A - In-House)





Make the Offer 2.6.5

# Flow Chart (Process B – 3<sup>rd</sup> Party)





| Negotiate<br>Land Acquisition |  | Buildings<br>Parks<br>Roads | <b>2.6.6</b> □ □ □ |
|-------------------------------|--|-----------------------------|--------------------|
| <b>Process Owner</b>          | Description  |                             |                    |
| Director                      | This section explains the process of reaching an a | agreement for               | the fair           |
| Transportation                | market value of real estate property.              |                             |                    |
| <b>Process Manager</b>        |  |                             |                    |
| Right-of-Way Agent            |  |                             |                    |
| Transportation                |  |                             |                    |

# **Contacts & Roles: Organization, Entity, or Individual**

- ♦ **Property Owner** Presents information and a counter offer.
- ♦ Appraiser Provides the value of a property.
- ♦ **Right-of-Way** Reviews counter offers for acceptance or rejection. Negotiates with the property owner to reach a fair settlement.

#### **Timelines: Deadlines, Critical Path Items**

- ♦ **Condemnation** This process allows the right of entry to a property as the negotiation process proceeds.
- ◆ Review of a counter offer There is no set formula to the determination of a counter offer being accepted as reasonable. Right-of-Way's decision to approve a counter offer does not acknowledge a commitment by the County. Further review and approval of a counter offer occurs during the settlement process.

| Materials                | Forms |
|--------------------------|-------|
| ♦ Offer letter documents | None  |

## **Reference to Other Processes**


Follows 2.6.5 Make an Offer Precedes 2.6.7 Settlement Concurrent with 2.6.8 Condemnation

#### **Process Notes**

If the initial offer is not agreed to, the County and property owner enter into negotiations to reach a settlement. The property owner presents pertinent information to the County, which was not considered during the appraisal. The County considers the information and, if the request is reasonable, the County amends its offer and settles with the property owner. If the request is unreasonable, the County condemns the property, and negotiations about the property value continue.



Negotiate 2.6.6





| Settlement Land Acquisition           |  | Buildings<br>Parks<br>Roads | 2.6.7<br>□<br>□ |
|---------------------------------------|--|-----------------------------|-----------------|
| Process Owner                         | Description  |                             |                 |
|                                       | This section explains the process of settlement a documentation. | pproval, payme              | ent, and        |
| Transportation                        |  |                             |                 |
| Process Manager<br>Right-of-Way Agent |  |                             |                 |
| Transportation                        |  |                             |                 |

# Contacts & Roles: Organization, Entity, or Individual

- ♦ **Transportation Accounting** Prepares Purchase Order.
- ♦ County Attorney Records and enter a deed.
- ♦ **Right-of-Way –** Prepares all reports; oversees the settlement process.
- ♦ **Settlement Attorney** Prepares the HUD1 form.

#### **Timelines: Deadlines, Critical Path Items**

- ♦ **Signed Agreement** Agreement on the compensation amount must be signed prior to the preparation of the Acquisition Report.
- ♦ **HUD1 Form** Prepared by a settlement attorney.
- ♦ Approved Right-of-Way Acquisition Report The report is approved by the County Attorney, Director of Finance, Budget Director, Director of Transportation, and if needed the County Executive.
- ♦ **Deed** Recorded by the County Attorney.

| Materials                    | Forms                           |
|------------------------------|---------------------------------|
| ♦ Request for Proposal (RFP) | Right-of-Way Acquisition Report |
|                              | ♦ HUD1                          |

#### Reference to Other Processes


Concurrent 2.6.6 Negotiate

#### **Process Notes**

Once the property owner and the County representative agree on the amount of compensation, right-of-way staff produce an Acquisition Report, which is reviewed by the County Attorney, Finance, Budget, and the Director of Transportation (and the ACXO and CXO, if the compensation amount is greater than \$300,000, but less than \$500,000). All settlements over \$500,000 require approval by BOCS. Right-of-Way then begins the process of producing a check for the property owner and filing pertinent records.




Settlement 2.6.7





Settlement 2.6.7





| Condemnation (Quick-Take) Land Acquisition |  | Buildings<br>Parks<br>Roads | <b>2.6.8</b> □ □ □ |
|--|--|-----------------------------|--------------------|
| Process Owner                              | Description  |                             |                    |
| <b>Director</b> Transportation             | Condemnation or eminent domain is a power of the BOCS. If settlement with the property owner cannot be reached after the init offer, the County can condemn the property and continue negotiati with the property owner. |                             | initial            |
| Process Manager Right-of-Way Agent         |  |                             | iations            |
| Transportation                             |  |                             |                    |

#### **Contacts & Roles: Organization, Entity, or Individual**

- ♦ County Attorney Files condemnation papers with the Court.
- ♦ **Transportation Accounting** Processes payment of the property value to court.
- ♦ **Clerk to BOCS** Coordinates Public Hearings and condemnation proceedings.

#### **Timelines: Deadlines, Critical Path Items**

- ♦ **Appraisal** The amount of compensation filled with the courts is based on an independent appraisal.
- ♦ Offer letter The offer letters have been sent to all known address of the property owner.
- ♦ **Public Hearing** Must be advertised two weeks prior to BOCS authorizing condemnation.

| Materials         | Forms |
|-------------------|-------|
| ♦ BOCS Resolution | None  |

#### **Reference to Other Processes**


Follows 2.6.5 Make the Offer Concurrent with 2.6.6 Negotiate Precedes 2.6.9 Court Proceeding Follows 2.2.2 Public Hearings Concurrent with 2.8.1 Board Agenda

#### **Process Notes**

BOCS can only condemn a property by resolution after a public hearing is conducted. Condemnation can have benefits for the County and the property owner. If the property owner feels that the offer was unacceptable then the Court can determine the value of the property. Condemnation allows additional time for negotiation and for consideration of the offer while the County maintains the project's schedule.



Condemnation 2.6.8






| Court Proceedings Land Acquisition              |   | Buildings<br>Parks<br>Roads | 2.6.9<br>□<br>□<br>☑ |
|---|---|-----------------------------|----------------------|
| Process Owner County Attorney                   | <b>Description</b> If settlement cannot be reached, the condemnat   | Ü                           |                      |
| Process Manager County Attorney                 | Evidence is presented on the value of the proper testimony and viewing the property, the court w value of the property. | ,                           |                      |
| ♦ Transportation Right-of-War                   |   | o reach a settlen           | nent.                |
| Materials<br>None                               | Forms<br>None   |                             |                      |
| Reference to Other P Follows 2.6.8 Condemnation | rocesses  |                             |                      |

# **Process Notes**







| <b>Determining Debt Sale Amount and Timing</b> |           | 2.7.1                   |
|--|-----------|-------------------------|
|  | Buildings | $\checkmark$            |
| Project Administration                         | Parks     | $\overline{\checkmark}$ |
|  | Roads     | $\checkmark$            |
|  | 1         |                         |

|                           |   | Parks<br>Roads  | <b>☑</b> |
|---------------------------|---|-----------------|----------|
| Process Owner             | Description   |                 |          |
| Treasury Manager  Finance | Timely and accurate debt sales ensure a judiciou assets. This process prevents the County from ex   | ceeding debt c  |          |
| Process Manager           | avoids payments, and allows projects to proceed   | I on schedule.  |          |
| Fiscal Services Manager   | Project Managers are responsible for determining Capital Project and providing this analysis quarte   | _               |          |
| Finance                   | Department and to Budget at least annually throand when requested in preparation for a bond so cashflow analysis to Finance, who determines the of debt sales | ale. Budget pro | vides    |

# Contacts & Roles: Organization, Entity, or Individual

- ♦ **Project Managers (with debt-funded projects)** Provide cashflow analysis annually and as needed.
- ♦ **BOCS** Approve all debt sales.
- ♦ **Finance** Reviews cashflows, and schedules and executes debt sales.
- ♦ **Budget** Reviews cash flow and programs cash flow in the CIP.

# **Timelines: Deadlines, Critical Path Items**

- ♦ CIP Must be reviewed and updated annually to revise the 5-year plan.
- ♦ Bond Sale Preparation Cash flow estimates must be reviewed and revised as needed/requested to assist in signing and timing bond sales.

| Materials                     | Forms |
|-------------------------------|-------|
| ♦ Project cash flow worksheet | None  |

#### Reference to Other Processes

Precedes 2.7.2 Bond/Lease Sale

#### **Process Notes**

Project cashflow is key to determining the amount and timing of a financing lease or bond sale. Project cash flow estimates applies to both project revenue and expenditure cashflows.

Individual project cashflow estimates should be performed by the Project Managers at each annual CIP update and at other times as requested, including ongoing CIP meetings.

The cashflow should identify and use as a starting point the actual revenues and expenses that have been received or incurred by the project from its inception up to the date the cashflow is prepared. The




cashflow estimates should be as accurate as possible, they should not be conservative or aggressive estimates.

Public Works/Transportation managers should accumulate the cashflow schedules of all the projects for which they are responsible and place them in the appropriate package of project materials being sent to the Budget Office as part of the annual CIP update, or in response to other requests for this data.

Budget and Finance both review the project updates included in the annual CIP submission. Finance also compares these submissions to reports from the accounting system which reflect actual expenses and revenues. These project reviews, performed in connection with development of the CIP, become the means of initially establishing and scheduling the future bond sales during the CIP period and especially the bond sales in the next 12 to 16 months. These project updates and the reviews of them are also essential for determining the County's position relative to its debt capacity limits.

Finance periodically performs a fiscal comparison of project expenditures shown in the accounting system, the current budget and on the current CIP as key components in setting the timing and size of the next bond/lease sale. Finance may request interim project cashflow updates in preparation for estimating the size and date of the next bond/lease sale series.





| Bond/Lease Sale        |           | 2.7.2                   |
|------------------------|-----------|-------------------------|
| •                      | Buildings | $\checkmark$            |
| Project Administration | Parks     | $\overline{\checkmark}$ |
|                        | Roads     | $\overline{\checkmark}$ |

# **Process Owner**

#### **Treasury Manager**

#### **Finance**

# **Description**

There is a set of specific actions that must take place for a bond sale or a lease sale to be initiated. Before describing these actions a brief discussion of the difference between the two financing types is appropriate:

Bond Sales—A bond sale is borrowing in which a legal commitment is made by the County to repay the borrowed money plus interest to the purchasers of the County's bonds (the bondholders) at specific times and in specific amounts. These payments are normally made from tax revenues.

# Process Manager Fiscal Services Manager

**Finance** 

Lease Sales—A lease sale involves the borrowing of funds which are collateralized by some specific asset belonging to the County; the County pledges the asset as collateral for the life of the financing. The financing documents arrange for the County to lease the asset back during the life of the financing in exchange for repaying the bondholders' money plus interest at specific times and in specific amounts agreed upon in the financing documents. Should the County fail to make payment when due, the asset can be taken from the County and leased or sold to someone else and the resulting money is given to the bondholders as repayment of their loan to the County. "Conduit sales" through the Virginia Resources Authority (VRA) use a slightly modified version of a lease sale.

# Contacts & Roles: Organization, Entity, or Individual

- ♦ **Treasury Management** Executes sale. Notifies departments when sales occur and provides them with account numbers and holders.
- ♦ **Transportation** Prepare draws against the sale proceeds.
- ◆ **Public Works** Prepare draws against the sale proceeds.
- ♦ **Bond Council** External specialty attorney firm provides guidance/assistance to Finance Department and makes legal the declaration regarding tax exempt nature of the financing.
- ♦ Accounting Processes draws and reconciles cash accounts and ASCEND.
- ♦ Credit Raters Establish the formal credit rating of the County.
- ♦ Trustee Investment Bank Holds bond proceeds.

# **Timelines: Deadlines, Critical Path Items**

♦ Vary depending on project cashflow rates/timing.



Materials Forms
None None

#### **Reference to Other Processes**

Precedes 2.3.4 Draw Downs for Bond- or Lease-Funded Projects Precedes 2.7.3 Arbitrage

#### **Process Notes**


General process for issuing bonds/leases—There are several BOCS Approvals that must be secured before any type of financing can be completed, and the specific requirements overlap but vary between financings executed through Bond Sales, and financings executed through Lease Sales. These approvals and their related documents are arranged or organized by Finance with assistance from others. The essential approvals and documents are the following:

|   | Bonds     | Leases    |
|---|-----------|-----------|
| A sale must be included by the BOCS in the annual CIP.                                | <b>◊</b>  | <b>◊</b>  |
| One or more project budgets must have BOCS approved revenue appropriations            | <b>◊</b>  | <b>•</b>  |
| from the sale, or mutiple sales.  |           |           |
| General Obligation (GO) Bonds require authorization by the County's citizens at a     | <b>◊</b>  |           |
| general election before the BOCS can initiate a GO sale.                              |           |           |
| Lease financings require the selection of an underwriter based on responses to a      |           | <b>◊</b>  |
| Request For Proposal. (In VRA "conduit sales" the VRA may select the underwriter.)    |           |           |
| Lease financings require the selection of a trustee based on Request For Proposal     |           | <b>◊</b>  |
| (RFP) or Request for Bid responses. (In VRA "conduit sales", the VRA selects the      |           |           |
| Trustee.)   |           |           |
| Lease financings require preparation of a series of leasing documents that must be    |           | <b>◊</b>  |
| approved by the BOCS. These documents are prepared by the Financial Advisor,          |           |           |
| Bond Counsel, County Attorney & Finance. [Finance/Treasury Management and the         |           |           |
| administrative staff of Transportation or Public Works should jointly review the      |           |           |
| financing at this time to set up or modify any accounting structure that should be    |           |           |
| established at this time.]  |           |           |
| A preliminary and a final Official Statement (O/S) must be prepared for any type of   | <b>◊</b>  | <b>◊</b>  |
| financing the County executes.  |           |           |
| The BOCS can approve a revenue bond sale without voter approval following a           | <b>\Q</b> |           |
| Public Hearing.   |           |           |
| The BOCS can approve lease type financings without voter approval following a         |           | <b>\Q</b> |
| Public Hearing.   |           |           |
| The staff report for the DOCC approval of any time of financine will include appoint  | <b>◊</b>  | <b>\Q</b> |
| The staff report for the BOCS approval of any type of financing will include specific |           |           |
| amounts to be provided to one or more specifically named projects.                    |           |           |
|   | <b>◊</b>  | <b>◊</b>  |
| Once approved by the BOCS a credit rating must be obtained for the financing being    |           |           |
| executed. These credit ratings are obtained from Standard and Poor's, Moody's and     |           |           |
| Fitch, credit rating agencies based in New York City. This requires development and   |           |           |
| delivery of an extensive presentation on the County.                                  |           |           |
|   |           |           |
|   |           |           |




| Competitive financings are announced to the financial market and bids are taken on the designated sale day.   | <b>◊</b> |          |
|---|----------|----------|
| Negotiated financings are announced in the financial market and the preselected underwriter sells the bonds or lease obligations to bondholders.  |          | <b>•</b> |
| Closing documents are prepared to memorialize and formalize and legalize all aspects of the financing.  | <b>•</b> | ٥        |
| At the sale's closing, the cash proceeds of the financing are transferred to the County's external portfolio manager for retention and investment of the bond proceeds. [Finance/Treasury Management and the administrative staff of Transportation or Public Works should jointly review the portfolio and cashdraw process for the financing at this time.] | <b>•</b> | •        |
















| Arbitrage              |           | 2.7.3                   |
|------------------------|-----------|-------------------------|
|                        | Buildings | $\checkmark$            |
| Project Administration | Parks     | $\overline{\checkmark}$ |
|                        | Roads     | $\overline{\checkmark}$ |
| _                      | -         |                         |

# Process Owner

**Treasury Manager** 

**Finance** 

# Process Manager Fiscal Services Manager

**Finance** 

# **Description**

The U.S. Internal Revenue Service (IRS) has established a set of rules regulating the use of interest earned on the proceeds of all tax-exempt financings; both bonds and lease financing proceeds are subject to these regulations. (Many County road and facility construction projects are supported by tax-exempt financings.) The IRS is particularly concerned with the reinvestment of tax exempt bonds into investment instruments that generate more interest than the borrower is paying on the tax-exempt bonds; this practice is called 'arbitrage'. Arbitrage is the net cash earned on the bond proceeds as a result of the difference between the two interest rates.

# **Contacts & Roles: Organization, Entity, or Individual**

- **♦ Trustees**
- ♦ Internal Portfolio Manager
- ♦ Project Manager associated with debt-funded projects
- **♦ IRS**
- **♦ External Portfolio Manager**

# **Timelines: Deadlines, Critical Path Items**

- ♦ 6-month IRS milestones 10% of expenses.
- ♦ **12-month IRS milestones** 45% of expenses.
- ♦ 18-month IRS milestones 75% of expenses.
- ♦ **24-month IRS milestones** 95% of expenses (100% if there is no retainage).
- ♦ **36-month IRS milestone** 100% of expenses (Note: To avoid paying the IRS when arbitrage is earned all of these expenditures milestones must be met).

| Materials | Forms |
|-----------|-------|
| None      | None  |

#### **Reference to Other Processes**

Follows 2.7.2 Bond/Lease Sale

Concurrent with 2.3.4 Draw Downs for Bond- or Lease-Funded Projects

#### **Process Notes**

There are circumstances in which the IRS requires the tax exempt borrower to pay the IRS any arbitrage



Arbitrage 2.7.3

earnings the borrower makes on the reinvestment of tax exempt financing proceeds.

The County may avoid paying the IRS anything and avoid doing arbitrage obligation calculations if the County complies with the IRS rules for the use of tax exempt proceeds. The key IRS rule in connection with arbitrage is this: the County must spend the bond sale proceeds in accordance with the following IRS expenditure milestones:

- 1. During the first 6 months after a bond sale the County must spend and draw down at least 10% of the sale proceeds (including interest earned thereon).
- 2. During the first 12 months after a bond sale the County must spend and draw down at least 45% of the sale proceeds (including interest earned thereon).
- 3. During the first 18 months after a bond sale the County must spend and draw down at least 75% of the sale proceeds (including interest earned thereon).
- 4. During the first 24 months after a bond sale the County must spend and draw down all of the sale proceeds (including interest earned thereon). Contractor retainage is exempted from this spending requirement resulting in up to a 5% exemption for reasonable retainage; otherwise, the requirement is that 100% of the sale proceeds must be spent.
- 5. By the end of the 36th month after a bond sale the County must spend and draw down all of the sale proceeds including all of the retainage payments (including interest earned).


To avoid arbitrage obligation calculations and payments the County must meet all five of these spending milestones. It is important to note that if a single one of these spending milestones on a financing is not met, then that County financing becomes subject to the IRS's arbitrage payment requirements. If more interest on the proceeds is earned that is paid the excess earnings must be paid to the IRS. Though there are many other rules and requirements, these spending milestones are the most pertinent to the Project Manager.

Key factors for Project Managers:

- 1. Borrowed funds should not be requested before they are needed.
- 2. When a project receives borrowed funds, those funds should be spent before the milestone date.
- 3. Cashdraws should be submitted as soon as possible and always before the milestone date.

Arbitrage calculations are extremely intricate and many peculiar rules affect the arbitrage obligation; consequently, the County has these calculations performed under contract by an outside consultant specializing in this work. These calculations are arranged by Finance. Finance also arranges any and all of the actual arbitrage payments to the IRS.







| Project Administration |             | Buildings<br>Parks<br>Roads | 2.7.4<br>☑<br>☑ |
|------------------------|-------------|-----------------------------|-----------------|
| Process Owner          | Description |                             |                 |

| Process Owner    |  |
|------------------|--|
| Treasury Manager |  |
|                  |  |

**Finance** 

# **Process Manager Fiscal Services Manager**

**Finance** 

After a bond sale or lease sale has been completed there are a series of ongoing activities or actions which are performed by Finance from the closing of the financing until the final debt service payment is made. The major tasks include:

- ♦ Making debt service payments when due, and in the amounts due, based on the financing agreement.
- ♦ Completing the annual information disclosure, which the U.S. Securities and Exchange Commission (SEC) requires from all tax exempt borrowers.
- ♦ Giving immediate notice to the SEC if a 'material event' takes place.

Performing arbitrage management as needed, including arbitrage obligation calculations and payments.

## **Contacts & Roles: Organization, Entity, or Individual**

- ♦ **BOCS** Debt services annual appropriations.
- ♦ Finance Treasury Management Perform all required tasks for debt service payment and IRS/SEC compliance.

# **Timelines: Deadlines, Critical Path Items**

♦ N/A to project, payments every 6 months, and annual disclosure executed by Finance – Treasury Management.

| Materials               | Forms                |
|-------------------------|----------------------|
| ♦ SEC Disclosure Letter | ♦ Wire transfer form |

#### Reference to Other Processes

Precedes 2.7.2 Bond/Lease Sale Concurrent with 2.7.3 Arbitrage




#### **Process Notes**

Major tasks in post-sale debt maintenance include:

- Making debt service payments when due, and in the amounts due, based on the financing agreement. These payments are normally made twice a year but may be organized with different payment periods and amounts. The annual principal payment is normally 1/20th of the original amount borrowed plus interest accrued.
- Completing the annual information disclosure, which the U.S. Securities and Exchange Commission (SEC) requires from all tax exempt borrowers. This report includes relatively abbreviated statements of the County's financial position, demographics, economic conditions and changes in debt position.
- Giving immediate notice to the SEC if a 'material event' takes place. Material events include: missed debt service payment(s), any other 'nonpayment' default, a draw on bond sale reserves, bond calls, refundings of bonds, credit rating changes, the sale or loss of the property collateralizing a financing, loss of tax exemption, etc.
- ◆ Performing arbitrage management as needed, including arranging arbitrage obligation calculations and payments. If a financing misses its draw down milestones it becomes subject to the U.S. Internal Revenue Service's (IRS) arbitrage regulations. Finance determines if a financing's construction draws miss the IRS's milestones. If they were missed Finance arranges to have the arbitrage calculation(s) performed by an outside consultant. At a minimum, arbitrage calculations are performed, and any payments are made as required every 5 years from the date of the original financing's sale closing. If the County owes a payment to the IRS, Finance arranges payment to the IRS using part of the funds earned as interest on the bonds without affecting the project funding.







| Budget Transfers Project Administration |  | Buildings<br>Parks<br>Roads | <b>2.7.5</b> |
|---|--|-----------------------------|--------------|
| Process Owner                           | Description  |                             |              |
| Director                                | Budget transfers shift already budgeted funds from one expenditure   |                             |              |
| Office of Management &<br>Budget        | code to another expenditure code. The purpose of a budget transfer is to provide sufficient operating flexibility to County departments, |                             |              |
|   | while ensuring adequate policy and fiscal control.   |                             |              |

# **Process Manager** Accounting Staff

**County Department** 

The level of approval needed for a given budget transfer is dependent on the amount, source, and destination of the transfer (see Process Notes).

#### **Contacts & Roles: Organization, Entity, or Individual**

- ♦ Project Manager Identifies need for budget transfer. Recommends use of funds within project budget.
- ◆ Department Accounting Staff Reviews project manager request and creates budget transfer document. Submits budget transfer through internal department approvals and then to the Accounting Division of the Department of Finance.
- ♦ **Budget** Reviews and approves/rejects all budget transfer requests.
- ♦ **Finance** Reviews and post budget transfers into the County's accounting system.

# **Timelines: Deadlines, Critical Path Items**

- ♦ **Request received** It is the responsibility of the project manager to identify budget deficiencies before a need becomes urgent.
- ♦ **Director Approval** All budget transfers must be approved by the Department Director or his/her designee.
- ♦ **Recorded** Budget transfers are not finalized until posted into the County's financial system.

| Materials | Forms |
|-----------|-------|
| None      | None  |

#### **Reference to Other Processes**

None

#### **Process Notes**

Special provisions:




- ♦ The budget transfer process is governed by the approved Budget Transfer Policy and Procedures documents.
- All transfers that have the final approval authority of the Department Head or the Director of OMB shall go directly to Budget. Transfers requiring Board approval shall be routed via a staff report and resolution through the normal agenda process.
- ♦ Budget transfers of the same or similar nature shall not be divided into separate transfers to avoid a higher level of approval.
- ♦ Transfers involving the internal service funds [i.e. changes to the 4xxx expenditure code (object level 3)] must be approved by the Department Head(s), and the Director of OMB. Transfers into/out of a 4xxx expenditure code (object level 3) must recognize and account for their impact on the internal service fund's revenues and expenditures (i.e. it will impact revenue code 0960 as well as an expenditure code (object level 3) in an internal service fund OCA).
- ♦ The Board of County Supervisors approval is required for any use of fund balance and all transfers into and out of capital projects.
- ♦ Should the request meet the criteria established for OMB review and approval, the requesting agency shall complete the Budget Transfer Form and submit the form to OMB. The requesting agency shall include the supporting rationale for the transfer AND, in the case of a request that meets one or more of the criteria in Section III.B. Of the Budget Transfer Policy, the agency must specifically address that criterion in the supporting rationale.
- ♦ The Board of County Supervisors shall approve any transfer that translates into a decrease in non-local revenue or an increase in local tax support requirement.
- ♦ All transfers must have a reason for request clearly stated on the budget transfer form.
- ♦ Matters not covered by this procedure shall be forwarded to the County Executive for resolution.

#### **Budget Transfer Matrix**

|                               | Department Head<br>Approval | BOCS Approval |
|-------------------------------|-----------------------------|---------------|
| (A) Transfers Within Fund,    |                             |               |
| Department and Expenditure    | \$1+                        | n/a           |
| Category (Object Level 1)     |                             |               |
| (B) Transfers Within Fund and | \$1 to \$19,999             | \$20,000+     |
| Department Between            |                             |               |
| Expenditure Categories        |                             |               |
| (Object Level 1)              |                             |               |
| (C) Transfers Within Fund     | \$1 to \$19,999             | \$20,000+     |
| Between Departments           |                             |               |
| (D) Transfers Between Funds,  | \$1 to \$19,999             | \$20,000+     |
| Sub funds                     |                             |               |







#### 2.7.6 **Internal Payment for Development Service Fees Buildings** (Journal Entries) **Parks Project Administration** Roads $\overline{\mathbf{M}}$ Description **Process Owner** Director A project may incur plan review and permit fees payable to the department of Development Services. Journal Entries are the **Finance** preferred payment method over check or credit card. Journal entries shift existing available project funding from Transportation **Process Manager** Department to another department to pay for an invoice for services and/or fees. **Transportation**

#### **Contacts & Roles: Organization, Entity, or Individual**

- ◆ Project Manager Identifies services being needed from another department. Contacts department (Development Services Administrative Analyst I and/or Management and Fiscal Analyst II) to get a copy of the invoice, completes Pre-Ascend Request Form – Invoice, and forwards to Accounting Staff for completion.
- ◆ Department Accounting Staff Reviews project manager request and completes journal entry in ASCEND. Submits journal entry in ASCEND through internal department approvals and then to the receiving agency for approvals.
- ♦ **Finance** Reviews and post journal entry into the County's accounting system.

### **Timelines: Deadlines, Critical Path Items**


- ♦ Request received It is the responsibility of the project manager to identify service and/or fees needed by another department and process paperwork a minimum of 3 days prior to required deadline.
- ◆ Director Approval All journal entries must be approved by the Department Director or his/her designee.
- ♦ **Recorded** Journal entries are not finalized until posted into the County's accounting system.

| Materials Forms              |                                   |
|------------------------------|-----------------------------------|
| None                         | Pre-Ascend Request Form - Invoice |
| Reference to Other Processes |                                   |
| None                         |                                   |



**Process Notes** 

#### **Flow Chart**





| Board Agenda Other Administrativ                                | e  | Buildings<br>Parks<br>Roads | 2.8.1<br>☑<br>☑ |
|---|--|-----------------------------|-----------------|
| Process Owner Clerk of the BOCS  Office of Executive Management | <b>Description</b> Any issue needing approval by the BOCS must be staff report, using the framework for analysis, ar presentation to BOCS. |                             | _               |
| Process Manager Project Managers  Public Works &                |  |                             |                 |

### **Contacts & Roles: Organization, Entity, or Individual**

- ♦ County Department Drafts staff report and resolution and follow items through the entire process.
- ♦ **BOCS** Approves or disapproves item.

**Transportation** 

- ♦ **Reviewing Departments** Mandatory: County Executive, County Attorney, Budget, Finance, Clerk of BOCS. Other County departments as applicable.
- ♦ Clerk of BOCS Facilitate the review and distribution process and advertise Public Hearing.

#### **Timelines: Deadlines, Critical Path Items**


- ♦ **Public Hearing advertisement** Any item requiring a Public Hearing must be submitted for advertisement to the Clerk of BOCS.
- ♦ Close Agenda Date that all items must be submitted to the Clerk of BOCS.
- ♦ **Dispatch date** All comments must be addressed.
- ♦ **Board date** Date at which action is to be taken by BOCS.

| Materials         | Forms                                  |
|-------------------|--|
| ♦ BOCS Resolution | ♦ BOCS Inter-Departmental Routing Slip |

#### **Reference to Other Processes**

#### **Process Notes**







| <b>Life Cycle Manageme</b> Other Administrative | ent  | Buildings<br>Parks<br>Roads | <b>2.8.2</b> |
|---|--|-----------------------------|--------------|
| Process Owner                                   | Description  |                             |              |
| Director  | Buildings & Grounds maintains the facility and surround  |                             |              |
| Parks & Recreation Public Works                 | functional, and attractive condition upon completion. Responsibility starts prior to construction completion and continues through the |                             | he           |
| Process Manager                                 | useful life of the facility to its removal from the C  | County assets lis           | st.          |
| Buildings & Grounds Division<br>Chief           |  |                             |              |
| Parks & Recreation Public Works                 |  |                             |              |

### **Contacts & Roles: Organization, Entity, or Individual**

- ♦ **Buildings & Grounds (B&G)** Maintenance, cyclic replacement, renovation, etc. Maintains as-built drawings.
- ♦ **Budget** Approves annual expenses and requisitions.
- ♦ **Purchasing** Provides review and guidance.
- ♦ **Accounting** Reviews and monitors financial transactions.
- ♦ **Property Management** maintains as-built drawings.

## **Timelines: Deadlines, Critical Path Items**

- ♦ CIP Approval Basic funding.
- ♦ **Transition of funds** Funds to General Fund budget.
- ♦ Life Cycle Management Annual Fund Review.

| Materials | Forms                         |
|-----------|-------------------------------|
| None      | ♦ Work Request                |
|           | Asset Ownership Transfer form |


#### **Reference to Other Processes**

Follows 2.4.10 Transition of Operating Budget

#### **Process Notes**



## **Flow Chart**





- **3.1** Glossary
- **3.2** Abbreviations
- **3.3** Agency Structures
- **3.4** External Contacts
- **3.5** Forms
- **3.6** Materials



| Term                          | Definition   |
|-------------------------------|--|
| Budget Transfer               | Process to move appropriated funds from one account or subaccount to                                     |
|                               | another account or subaccount.   |
| Capital Expenditure           | The use of funds for the acquisition or construction of major capital assets                             |
|                               | (e.g. land, road, buildings).  |
| Capital Improvement Program   | The capital infrastructure component of the County's fiscal plan and                                     |
|                               | implementation tool of the Strategic Plan and Comprehensive Plan.  |
| Certificate of Take (COT)     | As defined by the Virginia State Code a COT means a certificate recorded                                 |
|                               | by an authorized condemnor with the court wherein condemnation   |
|                               | proceedings are pending or are to be instituted, in connection with which                                |
|                               | the authorized condemnor has deposited funds with the court as provided insubdivision A 1 of § 25.1-305. |
| Certificates of Participation | According to InvestorWords.com, certificates of participation refer to                                   |
|                               | "Financing in which an individual buys a share of the lease revenues of an                               |
|                               | agreement made by a municipal or governmental entity, rather than the                                    |
|                               | bond being secured by those revenues" <sup>1</sup> . The authority usually uses the                      |
|                               | proceeds to construct a facility that is leased to the municipality, releasing                           |
|                               | the municipality from restrictions on the amount of debt that they can                                   |
|                               | incur.   |
| Change Order                  | A written order signed by a person authorized under authorized by the                                    |
|                               | Purchasing Regulations directing a Contractor to make changes, which the                                 |
|                               | changes clause of any contract authorizes to be ordered with or withou                                   |
|                               | the consent of the Contractor.*  |
| Constrained Long-Range Plan   | The Financially Constrained Long-Range Transportation Plan, or CLRP,                                     |
|                               | identifies all regionally significant transportation projects and programs                               |
|                               | that are planned in the Washington metropolitan area between 2008 and                                    |
|                               | 2030. Over 750 projects are included, ranging from simple highway  |
|                               | landscaping to billion-dollar highway and transit projects. Some of the                                  |
|                               | projects will be completed in the near future, while others are only in the                              |
|                               | initial planning stage. The projects and programs that go into the CLRP are                              |
|                               | developed cooperatively by governmental bodies and agencies  |
|                               | represented on the National Capital Region Transportation Planning Board                                 |
|                               | (TPB). The TPB Vision, the policy framework adopted by the TPB in 1998,                                  |
|                               | serves as the regional guide for project development. <sup>8</sup>                                       |
|                               |  |
|                               |  |



| Term                              | Definition  |
|-----------------------------------|---|
| Construction Change Directive     | A directive for changes in the Work for use where the owner and contractor have not reached an agreement on proposed changes in the Contract Sum or Contract Time. Form G714–2007 was developed as a directive for changes in the work which, if not expeditiously implemented, might delay the project. Upon receipt of a completed G714–2007, the contractor must promptly proceed with the change in the work described therein. <sup>7</sup>  |
| Contractor                        | Any vendor awarded a contract by the Board of County Supervisors or any using department.   |
| Customers                         | Any beneficiary of the product or process.  |
| Departments                       | Any County unit reporting directly to the County Executive or other board or commission.  |
| Direct Purchase Order             | A procurement instrument created by using department of exempt purchases, sole source purchases, and contract releases (blankets).*   |
| Direct Voucher                    | A procurement instrument created by using department for all purchases under \$1,000 and for emergency purchases over \$1,000.*   |
| Environmental Impact Statement    | A document required by the National Environmental Policy Act (NEPA), which defines the effect of a project on natural resources and location.   |
| Environmental Study Assessment    | A Phase I Environmental Site Assessment is a report prepared for a real estate holidng which identifies potential or existing environmental contamination liabilities. The analysis, often called a Phase I ESA, typically addresses both the underlying land as well as physical improvements to the property; however, techniques applied in a Phase I ESA never include actual collection of physical samples or chemical analyses of any kind. Scrutiny of the land includes examination of potential soil contamination, groundwater quality, surface water quality and sometimes issues related to hazardous substance. |
| Fiscal Year (FY)                  | The fiscal year for Prince William County begins on July 1 and ends on June 30 (e.g. Fiscal Year 2008 begins on July 1, 2007 and ends June 30, 2008).   |
| Freedom of Information Act (FOIA) | The body of Federal law protecting the rights of individuals to have access to public documents and records.  |
| General Fund                      | Primary sources of unrestricted revenue for the local government.   |
| General Ledger                    | A book of final entry of all the financial accounts of the County with offsetting debits and credits.   |



| Term  | Definition   |
|---|--|
| General Obligation Bonds  | According to investopedia.com, a general obligation bond is "[a] municipal bond backed by the credit and 'taxing power' of the issuing jurisdiction rather than the revenue from a given project. General obligation bonds are issued with the belief that a municipality will be able to repay its debt obligation through taxation or revenue from projects. No assets are used as collateral" <sup>3</sup> .  |
| Geographical Information System                                 | A specialized, database-driven computer information system. The database contains observations of spatially distributed features, activities or events, which can be defined in space as points, lines, or areas. The GIS allows users to capture, store, display, manipulate, and analyze geographically referenced data.   |
| Government Finance Officers Association                         | A professional association whose primary mission is to "enhance and promote the professional management of governments for the public benefit by identifying and developing financial policies and practices and promoting them through education, training, and leadership." <sup>2</sup>   |
| Inter Departmental Transfer                                     | Process by which expenditures and/or revenues are transferred from one County agency to another County agency.   |
| Invitation For Bids   | All documents whether attached or incorpororated by reference, utilized for soliciting sealed bids.*   |
| Lease Purchase Certificates                                     | A financing mechanism that uses a lease on the project being financed to collateralize the loan/financing. The certificates are the associated, formal, legal contract/commitment to repay the loan by making debt service payments at set times and in set amounts as described within the certificates.  |
| Liquidated Damages  | An agreement between two or more parties where a fixed sum is awarded for unsatisfactory execution of the terms in a binding contract.   |
| Metropolitan Washington Council of<br>Government (MWCOG or COG) | According to their website, MWCOG is "a regional organization of Washington area local governments. COG is composed of 21 local governments surrounding our nation's capital, plus area members of the Maryland and Virginia legislatures, the U.S. Senate, and the U.S. House of Representatives. COG provides a focus for action and develops sound regional responses to such issues as the environment, affordable housing, economic development, health and family concerns, human services, population growth, public safety, and transportation" <sup>4</sup> . |
| Modification  | Any written alteration of a contract signed by the parties bound by the $\operatorname{contract.}^*$   |



| Term  | Definition  |
|---|---|
| Northern Virginia Transportation<br>Authority     | A regional authority created by the Virginia General Assembly on July 1, 2002, charged with developing a regional transportation plan, working with Northern Virginia's communities to develop regional priorities and policies to improve air quality, and serve as an advocate for the transportation needs of Northern Virginia before the state and federal governments."   |
| Northern Virginia Transportation<br>Commission    | The Northern Virginia Transportation Commission (NVTC) was established to manage and control the functions, affairs, and property of the Northern Virginia Transportation Districtwhich was created by the 1964 Acts of Assembly of the Commonwealth of Virginia, Chapter 630; and the Transportation District Act. The purpose of the Act is to facilitate "planning and developing a transportation system for Northern Virginia and for the safety, comfort and convenience of its citizens and for the economical utilization of public funds" <sup>5</sup> . |
| Notice to Proceed                                 | Official notice given by an authorized County representative to commence work on a project.   |
| Official Statement                                | According to Scott & Stringfellow Inc., an official statement is "[a] required document published during any municipal bond offering, the Official Statement offers financial information, details of the bond offering and a legal opinion as to the validity of the offering" <sup>6</sup> .  |
| Operating Evpanditure                             | The use of funds on reoccuring expenses.  |
| Operating Expenditure                             | The use of funds of reoccuring expenses.  |
| Organizational Cost Account                       | The OCA code is the lowest level of detail in ASCEND.   |
| Participants                                      | Any person, organization, or agency involved in the execution of a process.   |
| Potomac Rappahannock<br>Transportation Commission | The Potomac and Rappahannock Transportation Commission (PRTC) is a multi-jurisdictional agency representing Prince William and Stafford Counties and the cities of Manassas, Manassas Park and Fredericksburg.  |
| Profits & Loss Analyzer (P&L)                     | A financial statement summarizing revenues, expenditures, and balance.  |
| Project Manager                                   | Refers to a County employee with general authority and responsibilities for the oversight and implementation of a task.   |
| Public Private Education Act                      | A state law that allows private entities to enter into agreements to construct, improve, maintain and operate educational facilities.   |
| Public Private Transportation Act                 | A state law that allows private entities to enter into agreements to construct, improve, maintain and operate transportation facilities.  |
| Purchase Order                                    | A procurement instrument issued by the Purchasing Office to order supplies, services, insurance, or construction.*  |
| Request for Proposals                             | A request for an offer from one or more vendors and includes the general terms, which are sought from the offeror.  |



| Term                            | Definition  |
|---------------------------------|---|
| Request for Quotations          | A request for an offer from one or more vendors under an open market procurement where the estmiated cost is less than \$50,000.* |
|                                 | producement where the estimated cost is less than \$50,000.   |
| Requisition                     | A document or documents, in a form prescribed by the Director of  |
|                                 | Finance, which shall constitute demand by the using department for the  |
|                                 | provision of supplies, services, insurance, or construction.*   |
| Scope of Work                   | A statement of work expected to be performed, which may include   |
| C' V C                          | deliverables and an expected level of performance.  |
| Six-Year Secondary Road Plan    | A document showing the allocation of state funds toward local   |
|                                 | transportation projects over a six-year period.   |
| Solicitation                    | The process of notifying vendors that the County wishes to receive bids or  |
| Solicitation                    | proposals on a set of requirements to provide supplies, services,   |
|                                 | insurance, or construction. Solicitation documents include Request for  |
|                                 | Quotation (RFQ), Request for Proposal (RFP), and Invitation for Bid (IFB). $^{st}$  |
| Stake Holders                   | Any person, organization, or agency who has a vested interest in the  |
|                                 | outcome of a process.   |
| Task Order                      | A specific work agreement issued to a vendor on an existing open-ended  |
| Tusk Order                      | contract. Vendor's are pre-qualified and must be used in sequential order   |
|                                 | unless special circumstances dictate the use of a waiver. Waivers must be   |
|                                 | approved by the Purchasing Office prior to issuance of a task order.  |
| Transportation & Roadway        | TRIP is a Prince William County program that provides funding by  |
| Improvement Program (TRIP)      | magisterial district for the construction of capital improvements to PWC's  |
|                                 | local roadways and other transportation facilities, specifically small-scale  |
|                                 | projects.   |
| Transportation Improvement Plan | A three-year program of federal, state, and locally funded transportation   |
|                                 | projects for which MPO approval is required.  |
| Utility Field Inspection        | The on-site location and marking of utilities (e.g. water, sewer, cable,  |
|                                 | telecommunications, etc.) that may be in conflict with proposed   |
|                                 | construction activities.  |
| Virginia Railway Express        | A state funded commuter rail.   |
| Virginia Resources Authority    | An organization created by the general assembly used to finance local   |
| -                               | capital projects for public safety, transportation, wastewater, flood   |
|                                 | prevention & dam safety, solid waste, water, federal facility development,  |
|                                 | brownfield remediation and redevelopment, airports, land conservation &   |
|                                 | preservation, and wireless broadband.   |



## **Capital Projects Glossary**

Section 3.1

| Torm | Definition |  |
|------|------------|--|
| Term | Definition |  |

| *                    |                         |                       |                     |
|----------------------|-------------------------|-----------------------|---------------------|
| Dofined as nor the I | Drinco William County   | Purchasing Regulation | oc Soction 100 04   |
| Delined as Del The F | zinice vviinanii Countv | FULCHASHIR REPUIATION | 15 300.0001 100.04. |

<sup>&</sup>lt;sup>1</sup> http://www.investorwords.com/810/Certificate\_of\_Participation.html



<sup>&</sup>lt;sup>2</sup> http://www.gfoa.org/index.php?option=com\_content&task=view&id=76&Itemid=96

<sup>&</sup>lt;sup>3</sup> http://www.investopedia.com/terms/g/generalobligationbond.asp

<sup>4</sup> http://www.mwcog.org/about/

<sup>5</sup> http://www.thinkoutsidethecar.org/nvtc/background.asp

<sup>&</sup>lt;sup>6</sup> http://www.scottstringfellow.com/ss/glossary.asp#O

http://www.aia.org/docs\_series\_g


<sup>&</sup>lt;sup>8</sup> http://www.mwcog.org/clrp/

| Abbreviation | Full Name                                       |
|--------------|---|
| A/E          | Architect/Engineer                              |
| A/E          | Architecture/Engineering                        |
| ADA          | Americans with Disabilities Act                 |
| AIA          | American Institute of Architects                |
| B&G          | Buildings and Grounds                           |
| BOCS         | Board of County Supervisors                     |
| BT           | Budget Transfer                                 |
| CCD          | Construction Change Directive                   |
| CIP          | Capital Improvement Program                     |
| CLRP         | · · · · ·                                       |
| CO           | Constrained Long-Range Plan                     |
| COP          | Change Order Certificates of Participation      |
| COT          | Certificate of Take                             |
|              |   |
| CTB          | Commonwealth Transportation Board               |
| CXO          | County Executive Office                         |
| CY           | Calendar Year                                   |
| DEQ          | Department of Environmental Quality             |
| DOT          | Department of Transportation                    |
| DOIT         | Department of Information Technology            |
| DPO          | Direct Purchase Order                           |
| EIS          | Environmental Impact Study                      |
| FCM          | Facilities Construction Management              |
| FOIA         | Freedom of Information Act                      |
| FONSI        | Finding of No Significant Impact                |
| FY           | Fiscal Year                                     |
| GC           | General Contractor                              |
| GF           | General Fund                                    |
| GFOA         | Government Finance Officers Association         |
| GIS          | Geographical Information System                 |
| GL           | General Ledger                                  |
| GO           | General Obligation Bonds                        |
| GPIN         | Grid Parcel Identification Number               |
| IDT          | Inter Departmental Transfer (also see REA)      |
| IFB          | Invitation For Bids                             |
| LD           | Liquidated Damages                              |
| LP           | Lease Purchase Certificates                     |
| MWCOG        | (Metropolitan Washington) Council of Government |
| NEPA         | National Environmental Policy Act               |
| NTP          | Notice to Proceed                               |
| NVTA         | Northern Virginia Transportation Authority      |
| NVTC         | Northern Virginia Transportation Commission     |
| OEM          | Office of Executive Management                  |




| Abbreviation  | Full Name   |
|---------------|---|
| OMB           | Office of Management and Budget                           |
| OS            | Official Statement  |
| P&L           | Profits & Loss Analyzer                                   |
| PM            | Project Manager   |
| PO            | Purchase Order  |
| PPEA          | Public Private Education Act                              |
| PPTA          | Public Private Transportation Act                         |
| Prop. Mgmt.   | Property Management                                       |
| PRTC          | Potomac Rappahannock Transportation Commission / OmniRide |
| Purch         | Purchasing  |
| PW            | Public Works  |
| PWCSA         | Prince William County Service Authority                   |
| REA (aka IDT) | Revenue and Expenditure Adjustment                        |
| RFI           | Request for Information                                   |
| RFP           | Request for Proposals                                     |
| RFQ           | Request for Quotations                                    |
| ROD           | Record of Decision  |
| ROW           | Right-of-Way  |
| SA            | Service Authority   |
| SC            | Subcontractor   |
| SOW           | Scope of Work   |
| Sq. FT.       | Square Foot   |
| SSYP          | Six-Year Secondary Road Plan                              |
| TEA-21        | Transportation Equity Act for the 21st Century            |
| TIP           | Transportation Improvement Plan                           |
| ТО            | Task Order  |
| TRIP          | Transportation & Roadway Improvement Program              |
| UFI           | Utility Field Inspection                                  |
| VDOT          | Virginia Department of Transportation                     |
| VRA           | Virginia Resources Authority                              |
| VRE           | Virginia Railway Express                                  |


























External Contacts Section 3.4

| Organization                            | Title                              | Name                 | Phone        | Email                              |
|---|------------------------------------|----------------------|--------------|------------------------------------|
|   |                                    |                      |              |                                    |
| AT&T                                    | OSP Engineer, Proj Program Mgmt    | Marc Bianco          |              | mb458f@att.com                     |
| Century Link (Army)                     | Senior Engineer                    | Noah Dobbins         | 703.464.7529 | Noah.Dobbins@CenturyLink.com       |
| Colonial Pipeline Company               | Relocation Project Manager         | Heath Bryant         | 678-762-2269 | HBryant@colpipe.com                |
| Columbia Gas                            | Associate Field Engineer           | Christopher E. Scott | 540-341-4544 | christopherScott@nisource.com      |
| Comcast                                 | Construction Supervisor            | Amy Goad             | 202-815-9919 | Amy_Goad@comcast.com               |
| Dominion Power                          | Project Manager                    | David Ojumu          | 571-203-5165 | david.o.ojumu@dominionenergy.com   |
| Fiberlight                              | Project Manager                    | Wayne Haithcox       | 571-421-7575 | wayne.haithcox@fiberlight.com      |
| Level 3 Communications                  | OSP Engineer                       | Boyd Williams        | 703.639.9758 | Boyd.Williams@centurylink.com      |
| Manassas Electric                       | Asst Director/Electrical Services  | David Jones          | 703-257-8351 | djones@ci.manassas.va.us           |
| Metroduct                               | Operations Manager                 | Travis Walter        | 703-335-5301 | tjwalter@metroductsystems.com      |
| Miss Utility                            | n/a                                | n/a                  | 811          | n/a                                |
| Northern Virginia Electric Cooperative  | Distribution Designer              | Carol Comstock       | 703-754-6732 | CComstock@NOVEC.COM                |
| Prince William County Service Authority | Inspection Manager                 | Conrad Holtslag      | 703-898-3433 | choltslag@pwcs.org                 |
| Prince William County Service           | Project Engineer II                | Edward Kovalchuk     | 703-375-7944 | E.Kovalchuk@pwcsa.org              |
| Authority                               |                                    |                      |              |                                    |
| Summit IG                               | OSP Engineer                       | Chip Turner          | 703-376-3703 | cturner@summitig.com               |
| Verizon                                 | Construction - Local Manager       | Joe Zych             | 540-903-4188 | joezych@msn.com                    |
| VDOT ITS                                | Engineer                           | David Smallwood      | 703-334-0208 | David.smallwood@vdot.virginia.gov  |
| VDOT                                    | Permits Manager                    | Art Klos             | 703-366-2004 | a.klos@vdot.virginia.gov           |
| Virginia Dept. of Health                | Permits                            | Maria Michellbork    | n/a          | Maria.Michellbork@VDH.Virginia.gov |
| Virginia DEQ                            | Permit Construction                | Mariana Lupini       | n/a          | mariana.Lupini@deq.virginia.gov    |
| Washington Gas                          | SP Engineer II                     | Michael Stablein     | 703-750-4270 | mstablein@washgas.com              |
| Williams gas Pipeline Atlantic - Gulf   | Engineer II                        | Austin Bennett       | 434-964-2126 | Austin.Bennett@williams.com        |
| Zayo Group                              | Operations PM, Mid-Atlantic Region | Brad Leatherman      | 703-928-0649 | bradley.leatherman@zayo.com        |



| Form Name  | References           |
|--|----------------------|
| Adjacent Property Owners Affidavit   | 2.1.2                |
| Appendix 21  | 2.5.1, 2.5.2, 2.5.4  |
| Application and Certificate for Payment (AIA Document G702)                            | 2.3.3, 2.3.5, 2.3.8  |
| Asset Ownership Transfer form  | 2.8.2                |
| BOCS Inter-Departmental Routing Slip   | 2.8.1                |
| C-5  | 2.3.11, 2.4.9        |
| Certificate of Substantial Completion  | 2.3.10               |
| Change Order (AIA Document G701)   | 2.3.2, 2.3.8         |
| Consent of Surety Company to Final Payment (AIA Document G707)                         | 2.3.5, 2.4.1         |
| Consent of Surety to Reduction in or Partial Release of Retainage (AIA Document G707A) | 2.3.5                |
| Construction Change Directive (AIA Document G714)                                      | 2.3.8                |
| Contractor's Affidavit of Payment of Debts and Claims (AIA Document G706)              | 2.4.1                |
| Contractor's Affidavit of Release of Liens (AIA Document G706A)                        | 2.4.1, 2.4.7         |
| Cost Proposal form for Interior Design Services  | 2.2.10               |
| Daily Report   | 2.3.6                |
| Daily Testing  | 2.3.6                |
| HUD1   | 2.6.7                |
| Planning Level Cost Estimate   | 2.1.1                |
| Pre-Ascend Request Form - Invoice  | 2.2.20, 2.3.3, 2.7.6 |
| Project Closure Checklist  | 2.4.8                |
| Project Closure Checklist ASCEND   | 2.4.8                |
| Project Estimate Worksheet   | 2.3.13, 2.3.14       |
| Proposal Request (AIA Document G709)   | 2.3.2, 2.3.8         |
| Public Facilities Determination (PFD)  | 2.2.15               |
| Public Facilities Review   | 2.1.2                |
| Public Facilities Review Application   | 2.1.2                |
| Punchlist  | 2.3.10               |
| Request for Payment – Information Required to Obtain Contractor Payment                | 2.3.3, 2.3.5         |
| Request for Payment  | 2.3.3, 2.3.5         |
| Request for Payment with Retainage   | 2.3.3, 2.3.5         |
| Right-of-Way Acquisition Report  | 2.6.7                |
| Settlement Checklist (Churches)  | 2.6.5                |
| Settlement Checklist (Corporations)  | 2.6.5                |
| Settlement Checklist (Property Owners)   | 2.6.5                |
| Solicitation Committee CXO Memo  | 2.1.4                |
| Solicitation Information Form for Construction Projects                                | 2.3.16               |
| Solicitation Information Form for RFP Professional Engineering Services                | 2.1.6, 2.3.16        |
| Special Events Checklist   | 2.4.5                |
| Task Order Form  | 2.2.11               |
| VDOT Street Acceptance Checklist   | 2.4.4                |
| W9 Form  | 2.6.5                |
| Wire transfer form   | 2.7.4                |
| Work Request   | 2.8.2                |
| Work Zone Safety Assistance  | 2.3.9, 2.3.17        |

Forms follow in alphabetic order as shown on the list above.



#### ADJACENT PROPERTY OWNERS AFFIDAVIT

# COMMONWEALTH OF VIRGINIA COUNTY OF PRINCE WILLIAM

| This  |  | ,   |   |
|---|--|---|---|
| (Day)   | (Month)  | (Year)  |   |
| I,  |  |   |   |
| I,(Owner/Contract Purchaser   | /Authorized Agent)   |   |   |
| hereby make oath that the list of involved, landowners within 50 property; all property immediate parcels which lie in other locality association where the subject property; local jurisdictions local military base, installation or mil Guard) within 3,000 feet of the feet of the subject property, is a | O feet of all portions of<br>ely across the street or<br>ties of the Commonwe<br>roperty is located within<br>ct's has members who<br>ated within one-half m<br>litary airport (excluding<br>subject property; and l | f the subject property, included road from the subject proper alth; any planned developmen 500 feet of the planned under own property within 2,000 file of all portions of the subject armories operated by the Vicensed public-use airport load. | ding the subject<br>erty, including those<br>ent district owner<br>ait development and<br>feet of the subject<br>ject property;<br>Virginia National<br>ocated within 3,000 |
|   | Owner/C<br>(Circle or  | ontract Purchaser/Authorizene)  | ed Agent  |
| COMMONWEALTH OF VIRO  | GINIA:   |   |   |
| County of   |  |   |   |
| Subscribed and sworn to me thi by the aforenamed principal.   | sday of  | , 20, in my co  | ounty and aforesaid   |
|   | $\frac{1}{N}$  | OTARY PUBLIC  |   |
| My Commission Expires:  |  |   |   |

Appendix No. 21 Revised 8-26-03

#### PLAN AND ESTIMATE CHECK LIST

**Utility Owner** Estimate Amount:

| Project Utility Co. Share PPMS VDOT Share   |
|---|
| (Indicate yes, no, or n/a in space provided by each item)   |
| (X) 1. Check Form UT-9 to determine responsibility of payment. Does it agree with utility plans   |
| and estimate?   |
| () 2. Does permit inventory (LUPS) show any new facilities which have been installed? () 3. Is there a narrative statement describing existing and proposed facilities? |
| () 4. Do plans show existing and proposed right of way lines?   |
| () 5. Are utilities referenced to road plan stations?   |
| () 6. Do plans contain legend?  |
| () 7. Do plans show existing and proposed utility facilities?   |
| () 8. Is temporary work necessary?  |
| () 9. Does proposed adjustment conflict with road construction or other utility adjustments?  |
| () 10. Is special provision necessary?  |
| () 11. Are profiles or cross sections of proposed crossings included?   |
| () 12. Has proposed adjustment been checked with all highway plan revisions?  |
| () 13. Does plan and estimate include only state responsibility portion of adjustment?  |
| () 14. Does plan and estimate include total adjustment with State's responsibility pro-rated?   |
| () 15. Do estimate and plan quantities agree?   |
| () 16. In your opinion, do plans show most practical and economical adjustment?   |
| () 17. Do plans show betterment?  |
| () 18. Is betterment credit allowed in estimate? Check breakdown.   |
| () 19. Conduit:   |
| () a. Is underground conduit proposed?  |
| () b. Is there sufficient justification for number of ducts proposed?   |
| () c. Are bridge attachments proposed?  |
| () 20. In your opinion, does estimate show an unreasonable costs? (Engineering, right of way,   |
| material, force labor, contract labor, etc.) If "yes" explain in comments.  |
| () 21. Is utility company requesting use of contract work?  |
| Is request adequate? ()   |
| () 22. Does estimate provide sufficient salvage credit? Check breakdown.  |
| () 23. Is work schedule included?   |
| () 24. Interstate:  |
| () a. Does adjustment generally conform to AASHTO Policy?   |
| () b. Are proposed poles, anchors, manholes, etc., located within limited access right  |
| of way?   |
| () c. If so, is there any alternative?  |
| () d. Are aerial and underground crossings held to a minimum?   |
| () 25. Primary:   |
| () a. Are proposed facilities located on right of way?  |
| () b. Is right of way 33.53 meters (110 feet) or over?  |
| () c. Has utility signed comprehensive agreement?   |
| () d. Are proposed facilities located according to agreement?   |
| () 26. Is information on real property interest and/or rights included?   |
| () 27. Are any environmental permits needed?  |
| ().28. LIST ANY COMMENT REGARDING PLANS AND ESTIMATE ON BACK OF FORM.   |

Copy

\_ DATE\_ Copy of this check list should be maintained in the District Utilities Engineer's file on each project.

to State Utilities Engineer with Plan & Estimate.

| APP                                       | LICATION AND   | CERTIFICAT  | E FOR PAYMENT  | AIA DOCUMENT G702   | (Instructions on reverse side)  | PAGE ONE OF PAGE   |
|---|--|---|--|---|---|--|
| TO (OV                                    | VNER):   |   | PROJECT:   |   | APPLICATION NO:   | Distribution to:   |
|   |  |   |  |   | PERIOD TO:  | ☐ ARCHITECT ☐ CONTRACTO                                      |
| FROM                                      | (CONTRACTOR):  |   | VIA (ARCHITECT):   |   | ARCHITECT'S PROJECT NO:   |  |
| CONTR                                     | ACT FOR:   |   |  |   | CONTRACT DATE:  | <del>.</del>   |
| CO  | NTRACTOR'S AF  | PLICATION   | FOR PAYMENT  | Application is made for Paym<br>Continuation Sheet, AIA Doo                                       | ent, as shown below, in connect   | ion with the Contrac   |
| CHAN                                      | IGE ORDER SUMMARY  |   |  |   | M   |  |
| Chang                                     | ge Orders approved in<br>ous months by Owner<br>TOTAL  | ADDITIONS   | DEDUCTIONS   | 2. Net change by Change Or<br>3. CONTRACT SUM TO DAT  | ders \$<br>E (Line 1 ± 2) \$<br>DRED TO DATE \$   |  |
| Appro                                     | ved this Month   |   |  | (Column G on G703)  |   |  |
| Numb                                      | per Date Approved  |   |  | (Column D + E on G7(<br>b % of Stored Mater<br>(Column F on G703)<br>Total Retainage (Line 5a + 5 | ial \$<br>5b or   |  |
|   | TOTALS   |   |  |   | 5703)   |  |
| The und information comple paid by issued | hange by Change Orders  dersigned Contractor certification and belief the Work conted in accordance with the Good the Contractor for Work for and payments received from is now due. | overed by this Applicat<br>Contract Documents, to<br>or which previous Cer                              | ion for Payment has been<br>hat all amounts have been<br>tificates for Payment were                                | (Line 4 less Line 5 Tota 7. LESS PREVIOUS CERTIFICA PAYMENT (Line 6 from 8. CURRENT PAYMENT DUE   | ,   |  |
| CONTR                                     | ACTOR:   | Date:   |  | State of:<br>Subscribed and sworn to bef<br>Notary Public:<br>My Commission expires:              | County of:<br>ore me this day of  | <b>,2</b> 50 O   |
| In accordata con<br>best of<br>indicate   | chitect's cert<br>rdance with the Contract Do<br>mprising the above application<br>the Architect's knowledge, in<br>ed, the quality of the Work is<br>intractor is entitled to payme | ocuments, based on or<br>on, the Architect certifi<br>oformation and belief t<br>in accordance with the | n-site observations and the<br>es to the Owner that to the<br>he Work has progressed as<br>Contract Documents, and | (Attach explanation if amoun ARCHITECT:  By:  | t certified differs from the amou  Date: able. The AMOUNT CERTIFIED uance, payment and acceptance of Owner or Contractor under this | nt applied for.)  is payable only to the payment are without |

# PRINCE WILLIAM COUNTY ASSET OWNERSHIP TRANSFER FORM

| I hereby request the following to be:  TRANSFERRED TO SURPLUS TRANSFERRED FROM SURPLUS TRANSFERRED TO TRANSFERRED TO |                 |                              |                |              |             |            |                      |           | ADED IN (As part of seal   | ed bid proposal or Req  | uest for Quote) | -                                      |  |
|--|-----------------|------------------------------|----------------|--------------|-------------|------------|----------------------|-----------|----------------------------|-------------------------|-----------------|--|--|
|  | PROPERTY<br>ID# | DESCRIPTION<br>(Include Make |                | QT           | Y SERIAL    | NUMBER     | CONDITION<br>ITEM(S) | OF        | KEYS & MANUAL<br>ATTACHED  | . CURRENT<br>LOCATION   |                 | HISTORICAL<br>SIGNIFICANCE<br>COMMENTS |  |
| 1.   |                 |                              |                |              |             |            |                      |           | ☐ KEYS<br>☐ OPERATING MANU | JALS                    |                 |  |  |
| 2.   |                 |                              |                |              |             |            |                      |           | ☐ KEYS<br>☐ OPERATING MANU | JALS                    |                 |  |  |
| 3.   |                 |                              |                |              |             |            |                      |           | ☐ KEYS<br>☐ OPERATING MANU | JALS                    |                 |  |  |
| 4.   |                 |                              |                |              |             |            |                      |           | ☐ KEYS<br>☐ OPERATING MANU | JALS                    |                 |  |  |
| Initia   | ator's Name     | Phone                        | Ext.           | Internal Zip | Departm     | ent Name   |                      | Section/U | nit Dept. No.              | Department H            | lead Signature  | Date                                   |  |
| <b>I h</b> e   | reby acknowle   | dge receipt of ass           | et(s):         |              |             |            |                      |           |                            |                         |                 |  |  |
| Rec  | eiver's Name    | Phone                        | Ext.           | Internal Zip | Departm     | ent Name   |                      | Section/U | nit Dept. No.              | Department H            | lead Signature  | Date                                   |  |
|  |                 |                              |                |              | FOR PL      | JBLIC W    | ORKS AND             | DIRECT    | OR OF FINANCE              | ONLY                    |                 |  |  |
|  |                 | ITEM                         | RECO           | MMENDED D    | SPOSITION ( | )F ITEM    |                      |           | CONDITION OF IT            | EM                      | ESTIMATED REP   | AIR COST                               |  |
|  |                 | 1. Hold fo                   | r Future Us    | e Sale       | Trans       | fer        | Scrap                | Excellent | ∏Fair                      | Poor                    | \$              |  |  |
|  |                 |                              | r Future Us    |              | Trans       |            |                      | Excellent | ∏Fair                      | Poor                    | \$              |  |  |
|  | _               |                              | r Future Us    |              | Trans       |            |                      | Excellent | Fair                       | Poor                    | \$              |  |  |
|  |                 | 4.   LHold fo                | r Future Us    | e Sale       | Trans       | rer 🗀      | Scrap                | Excellent | ∏Fair                      | Poor                    | \$              |  |  |
| Арј  | proved/Disap    | proved By:                   | or, Public Wor | rks          |             |            | te                   | Disposa   | al Accomplished By:        | Landfill Superintendent |                 | Date                                   |  |
|  |                 | Direct                       | or, Finance    |              |             | <u>D</u> a | te                   | Witness   | sed By:                    | Representative, Public  | Works           | Date                                   |  |

# STAFF REPORT INTER-DEPARTMENTAL ROUTING

| Today's Date               |                  |             |        |        | Initiating Department:   |       |
|----------------------------|------------------|-------------|--------|--------|--|-------|
| Staff Contact              | Pers             | on <u>:</u> | •      |        | Phone: Fax:  |       |
| Presenter at B             | <mark>OCS</mark> | S Mee       | eting: |        |  |       |
| Report Title               |                  |             |        |        |  |       |
| Date of Board              | d of C           | Count       | ty Sup | erviso | ors Meeting:   |       |
| Agenda Posit               | ion:             | CXC         | ) Time | e□     | Consent Dept. Public Hearing Time: _ (check one) 2:00 p.m. 7:30 p.m.   |       |
| ROUTING                    | SCE              | IEDU        | ULE    |        |  |       |
|                            | Approved         | Disapproved |        | /IEW   | Returned to for corrections as required by for response to complete from for response from | ments |
|                            | ∢                | Š           | In     | Out    | Monday,COMMENTS  | ŕ     |
| ATOVO                      |                  |             | Date   | Date   |  |       |
| ATCXO/<br>Clerk            |                  |             |        |        |  |       |
|                            |                  |             | Time   | Time   |  |       |
|                            |                  |             | Date   | Date   |  |       |
| County<br>Attorney         |                  |             |        |        |  |       |
|                            |                  |             | Time   | Time   |  |       |
|                            |                  |             | Date   | Date   |  |       |
| Budget                     |                  |             | Date   | Date   |  |       |
| Director                   |                  |             | Time   | Time   |  |       |
|                            |                  |             |        |        |  |       |
| Director of                |                  |             | Date   | Date   |  |       |
| Finance                    |                  |             |        | _      |  |       |
|                            |                  |             | Time   | Time   |  |       |
|                            |                  |             | Date   | Date   |  |       |
| *DCXO-                     |                  |             |        |        |  |       |
| SLR                        |                  |             | Time   | Time   |  |       |
|                            |                  |             |        |        |  |       |
| *DCVO CM                   |                  |             | Date   | Date   |  |       |
| *DCXO-CM<br>All financial- |                  |             |        |        |  |       |
| related items              |                  |             | Time   | Time   |  |       |
|                            |                  |             | ļ      |        |  |       |
| *DCXO-EJ                   |                  |             | Date   | Date   |  |       |
| DCAO-LJ                    |                  |             | Time   | Time   |  |       |
|                            |                  |             |        |        |  |       |

# STAFF REPORT INTER-DEPARTMENTAL ROUTING

| Initiating Dep | artm   | ent:_       |            |             |                      |   |
|----------------|--------|-------------|------------|-------------|----------------------|---|
| Report Title:_ |        |             |            |             |                      |   |
| Date of Board  | l of C | Count       | y Sup      | ervis       | ors Meeting:         |   |
|                |        |             |            | iai age     | encies are required. |   |
| ROUTING S      |        | Disapproved | REV        | /IEW        | COMMENTS             | _ |
|                |        |             | In<br>Date | Out<br>Date | - Comment            | _ |
|                |        |             | Time       | Time        |                      |   |
|                |        |             | Date       | Date        |                      |   |
|                |        |             | Time       | Time        |                      |   |
|                |        |             | Date       | Date        |                      |   |
|                |        |             | Time       | Time        |                      |   |
|                |        |             | Date       | Date        |                      |   |
|                |        |             | Time       | Time        |                      |   |
|                |        |             | Date       | Date        |                      | _ |
|                |        |             | Time       | Time        |                      |   |
|                |        |             | Date       | Date        |                      | _ |
|                |        |             | Time       | Time        |                      |   |
|                |        |             |            |             |                      |   |

# COMMONWEALTH OF VIRGINIA DEPARTMENT OF TRANSPORTATION REPORTING STARTING AND COMPLETION OF PROJECTS LOCALLY ADMINISTERED PROJECTS

| State Project No.                                   |  | UPC                    | Federal Project No.  |  |  |  |
|---|--|------------------------|----------------------|--|--|--|
| Locality/Local Sponsor<br>PRINCE WILLIAM COUNT      | ГУ   | Local Project No.      |                      |  |  |  |
| Contractor: Project Description / Pha               |  |                        |                      |  |  |  |
| Contract Work                                       | DATE STARTED   | DATE COMP              | LETED                |  |  |  |
| Local Forces  |  |                        |                      |  |  |  |
| 1 0 1   | pplete. All work has been in nancement projects. It is cert pecifications. | -                      | • •                  |  |  |  |
|   | eted within VDOT right of weted outside VDOT right of v                    | -                      | s on file.           |  |  |  |
| A final inspection was per                          | formed on (date)   | of VDO                 | Γ was in attendance. |  |  |  |
| Unless noted below, the pr                          | roject termini were not altere   | ed during construction | 1.                   |  |  |  |
| REMARKS OR EXPLA                                    | NATIONS:   |                        |                      |  |  |  |
| Local Official Signature                            |  | Printed Nan            | ne                   |  |  |  |
| Title   | _  |                        |                      |  |  |  |
| Local Acceptance Date                               |  |                        |                      |  |  |  |
| Once completed, a copy s<br>distribution within VDO | should be provided to the V<br>T   | DOT Project Coor       | dinator for further  |  |  |  |
|   | ject Coordinator Signatur  |                        | Date:                |  |  |  |

| CERTIFICATE OF<br>SUBSTANTIAL<br>COMPLETION<br>AIA DOCUMENT G704   | Distribution to: OWNER ARCHITECT CONTRACTOR FIELD OTHER  |  |  |   |
|--|--|--|--|---|
| PROJECT: (name, address)   |  |  | ARCHITECT:   |   |
| (name, address)  | •  |  | ARCHITECT'S PROJECT NUMBER:  |   |
| TO (Owner):  |  |  | CONTRACTOR:  |   |
|  |  |  | CONTRACT FOR:  |   |
| <u>_</u>   |  |  | CONTRACT DATE:   |   |
| DATE OF ISSUANCE:  |  |  |  |   |
| PROJECT OR DESIGNATED P  | ORTION SHALL INC   | CLUDE                                  | ::   |   |
| The Work performed under this Completion of the Project or por   |  |  | and found to be substantially complete.<br>e is hereby established as  | The Date of Substantial                             |
| which is also the date of commen   | cement of applicable   | warran                                 | ties required by the Contract Documents  | , except as stated below.                           |
| Construction is sufficiently comp<br>Work or designated portion there.  A list of items to be completed<br>attached hereto. The failure to in- | ete, in accordance we for the use for white of for the use for white or corrected, prepared any items on sustract Documents. The | ith the ch it is ed by ch list date of | the Contractor and verified and amendoes not alter the responsibility of the Coff commencement of warranties for item iting. | ded by the Architect, is contractor to complete all |
| ARCHITECT  |  | BY                                     |  | DATE  |
| The Contractor will complete or of from the above Date of Substantia   |  | ne list o                              | of items attached hereto within  | days  |
| CONTRACTOR   |  | BY                                     | · · · · · · · · · · · · · · · · · · ·  | DATE  |
| The Owner accepts the Work or at   | designated portion th<br>(time   |  | s substantially complete and will assum  | e full possession thereof<br>(date).                |
| OWNER  | ,  | BY                                     |  | DATE  |
| and insurance shall be as follow   | /S:<br>! and insurance counsel s   |  | security, maintenance, heat, utilities   | _   |

| CHANGE ORDER  AIA DOCUMENT G701   | OWNER ARCHITECT CONTRACTOR FIELD OTHER |   |                                       |
|---|--|---|---------------------------------------|
| PROJECT: (name, address)  |  | CHANGE ORDER NUMBER:                            | · · · · · · · · · · · · · · · · · · · |
|   |  | DATE:   |                                       |
| TO CONTRACTOR: (name, address)  |  | ARCHITECT'S PROJECT NO:                         |                                       |
|   |  | CONTRACT DATE:                                  |                                       |
|   |  | CONTRACT FOR:                                   | tu.                                   |
| The Contract is changed as follows:   |  |   |                                       |
|   |  |   |                                       |
|   |  |   |                                       |
|   |  |   |                                       |
|   |  |   | •                                     |
|   |  |   |                                       |
|   |  | •   |                                       |
|   |  |   |                                       |
|   | •                                      |   |                                       |
|   |  |   |                                       |
| Not valid until signed by the Owner,  | Architect and Cont                     | ractor.   |                                       |
| The original (Contract Sum) (Guaranteed Max<br>Net change by previously authorized Change<br>The (Contract Sum) (Guaranteed Maximum P<br>The (Contract Sum) (Guaranteed Maximum<br>(unchanged) by this Change Order in the<br>The new (Contract Sum) (Guaranteed Maximum<br>The Contract Time will be (increased) (decreased) | Orders                                 | \$ e Order was \$ l) (decreased) \$             | ( ) days.                             |
| The date of Substantial Completion as of th   |  | order therefore is                              | ( ) days.                             |
| NOTE: This summary does not reflect char<br>Construction Change Directive.  | nges in the Contract Sum, (            | Contract Time or Guaranteed Maximum Price whice | ch have been authorized by            |
| ARCHITECT   | CONTRACTOR                             | OWNER   |                                       |
| Address   | Address                                | Address   | New York William No.                  |
| BY  | ВҮ                                     | BY  |                                       |

DATE \_

DATE \_

CHANGE

DATE\_

## CONSENT OF SURETY COMPANY TO FINAL PAYMENT

OWNER ARCHITECT CONTRACTOR SURETY OTHER

AIA DOCUMENT G707

|  | Title                                  |                      |
|--|--|----------------------|
| Attest: (Seal):  | Signature of Authorized Representative |                      |
|  | Surety Company                         |                      |
| IN WITNESS WHEREOF, the Surety Company has hereunto set its hand this  | day of                                 | 19 .                 |
| as set forth in the said Surety Company's bond.  |  |                      |
|  | •                                      | , OWNER,             |
| hereby approves of the final payment to the Contrac<br>relieve the Surety Company of any of its obligations to |  | Contractor shall not |
|  |  | , CONTRACTOR,        |
| on bond of there insert name and address of Contractor)  |  |                      |
|  |  | , SURETY COMPANY,    |
| In accordance with the provisions of the Contract be (here insert name and address of Surety Company)          | etween the Owner and the Contractor as | indicated above, the |
|  |  |                      |
| CONTRACTOR:  | _                                      |                      |
| <u>L</u>   | CONTRACT DATE:                         |                      |
| · 1  | CONTRACT FOR:                          |                      |
| TO (Owner)   | ARCHITECT'S PROJECT NO:                | ,                    |
| PROJECT: (name, address)   |  | 4                    |

NOTE: This form is to be used as a companion document to AIA DOCUMENT G706, CONTRACTOR'S AFFIDAVIT OF PAYMENT OF DEBTS AND CLAIMS, Current Edition

# CONSENT OF SURETY TO REDUCTION IN OR PARTIAL RELEASE OF RETAINAGE

| OWNER      |  |
|------------|--|
| ARCHITECT  |  |
| CONTRACTOR |  |
| SURETY     |  |
| OTHER      |  |

AIA DOCUMENT G707 A

| PROJECT: (name, address)   |  |                        |
|--|--|------------------------|
| TO (Owner)   | ARCHITECT'S PROJECT NO:                        |                        |
|  |  |                        |
|  | CONTRACT FOR:                                  |                        |
| 3  | CONTRACT DATE:                                 |                        |
|  | <b>-</b> .                                     |                        |
| •  |  |                        |
|  |  |                        |
| In accordance with the provisions of the Contra (here insert name and address of Surety as it appears in the |  | s indicated above, the |
|  |  | , SURETY,              |
|  |  |                        |
| on bond of (here insert name and address of Contracto  | r as it-appears in the bond)                   |                        |
|  | ,  | , CONTRACTOR,          |
| hereby approves the reduction in or partial relea  | ase of retainage to the Contractor as follows: |                        |
|  |  |                        |
|  |  |                        |
| The Surety agrees that such reduction in or part of any of its obligations to (here insert name and add      |  | not relieve the Surety |
|  |  |                        |
|  |  | , owner,               |
| as set forth in the said Surety's bond.  |  | , OWNER,               |
| IN WITNESS WHEREOF,  |  |                        |
| the Surety has hereunto set its hand this  | day of   | 19                     |
|  | ·  |                        |
|  | Surety   | •                      |
|  | Signature of Authorized Paprocente             | tivo                   |
| Attest:  | Signature of Authorized Representa             | LLI V C                |
| (Seal):  | Title  |                        |

# CONSTRUCTION CHANGE DIRECTIVE

| OWNER      | Ε |
|------------|---|
| ARCHITECT  | Ε |
| CONTRACTOR |   |
| FIELD      |   |
| OTHER      |   |

| AIA DOCUMENT G714 (Instructions on reverse side. This do           | ocument replaces AIA Document G713, Construction Char  | nge Authorization.)                          |
|--|--|--|
| PROJECT:   |  | DIRECTIVE NO:                                |
| (name, address)  |  | DATE:  |
| TO CONTRACTOR:   |  | ARCHITECT'S PROJECT NO:                      |
| (name, address)  |  | CONTRACT DATE:                               |
|  |  | CONTRACT FOR:                                |
| You are hereby directed to m                                       | nake the following change(s) in this Contract:   | ٠  |
|  |  | •  |
|  |  |  |
|  |  | •  |
|  |  |  |
|  |  |  |
|  | DDODOGD AD HOTHENTO  |  |
| 1 The proposed basis of adjustm                                    | PROPOSED ADJUSTMENTS nent to the Contract Sum or Guaranteed Maximum F  |  |
|  | decrease) of \$  | nec is.                                      |
|  | per  |  |
|  | agraph 7.3.6 of AIA Document A201, 1987 edition.   |  |
| ☐ as follows:  |  |  |
|  | d to (be adjusted) (remain unchanged). The propose<br>days).   | ed adjustment, if any, is (an increase of    |
| becomes effective IMMEDIATELY<br>Contractor shall proceed with the | rchitect and received by the Contractor, this documents as a Construction Change Directive (CCD), and the change(s) described above. | tractor's agreement with the proposed adjust |
| ARCHITECT  | OWNER  | CONTRACTOR                                   |
| Address  | Address  | Address                                      |
|  |  | _  |
| ВҮ   | BY   | BY   |

DATE .

DATE .

DATE .

| CONTRACTOR'S            |
|-------------------------|
| AFFIDAVIT OF            |
| PAYMENT OF              |
| <b>DEBTS AND CLAIMS</b> |

**OWNER ARCHITECT** CONTRACTOR SURETY OTHER

| AIA Document G/06   |                                       |  |  |
|---|---------------------------------------|--|--|
| TO (Owner)  | 乛                                     | ARCHITECT'S PROJECT NO:<br>CONTRACT FOR:   |  |
| PROJECT: (name, address)  |                                       | CONTRACT DATE:   |  |
| State of:  County of:  The undersigned, pursuant to Article 9 of the Gene A201, hereby certifies that, except as listed below, materials and equipment furnished, for all work, lal claims against the Contractor for damages arising i referenced above for which the Owner or his prope | he has pa<br>bor, and s<br>in any mai | id in full or has otherwise satisfied ervices performed, and for all knownner in connection with the perform | all obligations for all<br>vn indebtedness and |
| EXCEPTIONS: (If none, write "None". If required by to Owner for each exception.)  | the Owne                              | , the Contractor shall furnish bon   | d satisfactory to the                          |
|   |                                       |  |  |
| SUPPORTING DOCUMENTS ATTACHED HERETO:   | CONTR                                 | ACTOR:   |  |
| 1. Consent of Surety to Final Payment. Whenever Surety is involved, Consent of Surety is required. AIA DOCUMENT G707, CONSENT OF SURETY, may be used for this purpose. Indicate attachment: (yes ) (no ).   | Address                               | ::   |  |
| The following supporting documents should be attached hereto if required by the Owner:  | BY:                                   |  |  |
| <ol> <li>Contractor's Release or Waiver of Liens, conditional upon receipt of final payment.</li> <li>Separate Releases or Waivers of Liens from Subcontractors and material and equipment suppliers, to the extent required by the Owner, accompanied by a list thereof.</li> </ol>      |                                       | oed and sworn to before me this<br>day of<br>Public:   | 19   |
| 3. Contractor's Affidavit of Release of Liens (AIA DOCUMENT G706A).   | Му Сог                                | nmission Expires:  |  |

| CONTRACTOR'S            |
|-------------------------|
| AFFIDAVIT OF            |
| <b>RELEASE OF LIENS</b> |

OWNER ARCHITECT CONTRACTOR SURETY OTHER

|   | ] |
|---|---|
| L | ] |

AIA DOCUMENT G706A

| AIA DOCOMENT GAOOA   |   |  |  |
|--|---|--|--|
| TO (Owner)   |   | PROJECT NO:  |  |
|  | CONTRACT  | FOR:   |  |
|  |   |  |  |
| 1  | CONTRACT  | DATE:  | ,                                      |
| PROJECT:   | _   |  |  |
| (name, address)  |   |  |  |
| State of:  |   |  |  |
| County of:   |   |  |  |
| The undersigned, pursuant to Article 9 of the Gene A201, hereby certifies that to the best of his know or Waivers of Lien attached hereto include the Coment, and all performers of Work, labor or service arising in any manner out of the performance of | ledge, information and be<br>intractor, all Subcontracto<br>es who have or may have | lief, except as listed be<br>rs, all suppliers of mat<br>liens against any prope | low, the Releases<br>erials and equip- |
| EXCEPTIONS: (If none, write "None". If required by a Owner for each exception.)  | the Owner, the Contracto  | or shall furnish bond sa   | atisfactory to the                     |
|  |   |  |  |
| $\epsilon^{-1}$  |   |  |  |
|  |   |  |  |
|  |   |  |  |
|  |   |  |  |
|  |   | •  |  |
|  |   |  |  |
|  | •   |  |  |
|  |   |  |  |
|  |   |  |  |
|  | •   |  | •                                      |
| SUPPORTING DOCUMENTS ATTACHED HERETO:  | CONTRACTOR:   |  |  |
| <ol> <li>Contractor's Release or Waiver of Liens, conditional upon receipt of final payment.</li> </ol>  |   |  | . •                                    |
| 2. Separate Releases or Waivers of Liens from Sub-<br>contractors and material and equipment sup-<br>pliers, to the extent required by the Owner, ac-  | Address:  |  |  |
| companied by a list thereof.   | BY:   |  |  |
|  |   |  |  |
| •  | Subscribed and sworn to   |  | 10                                     |
|  |   | day of   | 19                                     |
| •  | Notary Public:  |  |  |

My Commission Expires:



### **COUNTY OF PRINCE WILLIAM**

PROPERTY MANAGEMENT

9517 Innovation Drive, Manassas, Virginia 20109 (703) 792-7290 Metro 631-1703 Fax: (703) 792-330-5435

### **COST PROPOSAL**

| DATE:                            | 50% Submittal due:              |          | 100% Submittal due: |
|----------------------------------|---------------------------------|----------|---------------------|
| CONTRACTOR PROVIDING SERVICE:    |                                 |          |                     |
| CONTRACT NAME AND NUMBER:        | <b>Interior Design Services</b> |          |                     |
| CONTRACT EXPIRATION DATE:        |                                 | OPTION Y | YEAR:               |
| CONTRACTOR'S ADDRESS:            |                                 |          |                     |
| CONTRACTOR'S CONTACT:            |                                 | PHONE:   |                     |
|                                  |                                 | FAX:     |                     |
| COUNTY PROJECT MANAGER:          |                                 | PHONE:   |                     |
|                                  |                                 | CELL:    |                     |
| PROJECT NAME AND NUMBER:         |                                 |          |                     |
| BUILDING#; FL#; PROJECT ADDRESS: |                                 |          |                     |
| COUNTY END USER:                 |                                 | PHONE:   |                     |
|                                  |                                 |          |                     |

SCOPE OF WORK:\_This project entails the design of

| Programming                        | <b>Existing Systems Furniture Plans</b> |             |
|------------------------------------|---|-------------|
| General                            | In Existing Format                      |             |
| Report                             | <b>Component With Panel Plan</b>        |             |
| <b>Blocking/Option Development</b> | Electric Infeed Locations               |             |
| 1 Option                           | <b>New Systems Furniture Plans</b>      |             |
| 2 – 3 Options                      | Spec plus Format                        |             |
| <u>Schematics</u>                  | CAP Format                              | $\boxtimes$ |
| 50% Submittal                      |   |             |
| 75% Submittal                      | Systems Furniture Product               |             |
| Base Building Plan                 | Equity Panels                           | $\boxtimes$ |
| Area of Project                    | Saxony, Opal                            |             |
| Entire Floor                       | Sennit, Oatmeal                         | $\boxtimes$ |
| Other                              | Other                                   |             |
| <b>Construction Documents</b>      | Components                              |             |
| Design Intent                      | Equity soft gray                        | $\boxtimes$ |
| Complete Bid Set                   | neutral                                 |             |
| Electrical                         | other                                   |             |
| Mechanical                         | Reuter                                  | $\boxtimes$ |
| Structural                         | Electric                                |             |
| Plumbing                           | 6/8 Wire                                | $\boxtimes$ |
| Fire Evacuation Drawings           | 10 Wire                                 |             |

Page 2

**Project Name and Number:** 

**Contractor:** 

**Contract Name and Number: Interior Design Services** 

**Expiration Date:** 

| QTY | LABOR DESCRIPTION             | HR.      |        |                   | INSTALL      | REVIEW         | TOTAL      | TOTAL |
|-----|-------------------------------|----------|--------|-------------------|--------------|----------------|------------|-------|
|     |                               | RATE     | SURVEY | <b>SCHEMATICS</b> | <u>PLANS</u> | <b>MEETING</b> | <u>HRS</u> |       |
|     | INTERIORS                     |          |        |                   |              |                |            |       |
|     | Principal                     |          |        |                   |              |                |            |       |
|     | Senior Designer               |          |        |                   |              |                |            |       |
|     | Junior Designer               |          |        |                   |              |                |            |       |
|     | CAD Draftsman                 |          |        |                   |              |                |            |       |
|     | Project Manager               |          |        |                   |              |                |            |       |
|     | Field Installation Supervisor |          |        |                   |              |                |            |       |
|     | Project Engineer              |          |        |                   |              |                |            |       |
|     |                               |          |        |                   |              |                |            |       |
|     | Reimbursable Expenses         | Each     |        |                   |              |                |            |       |
|     | Photocopies                   |          |        |                   |              |                |            |       |
|     | Floppy Disks                  |          |        |                   |              |                |            |       |
|     | Color Copies                  |          |        |                   |              |                |            |       |
|     |                               | Per S.F. |        |                   |              |                |            |       |
|     | Bluelines                     |          |        |                   |              |                |            |       |
|     | Mylars                        |          |        | _                 |              |                |            |       |
|     | Vellums                       |          |        |                   |              |                |            |       |
|     |                               | TOTAL    |        |                   |              |                |            |       |

| <b>ESTIMATED COST (Not to</b> | Exceed):   | \$                 |  |  |  |  |  |
|-------------------------------|--|--------------------|--|--|--|--|--|
|                               | (To be filled in by contractor prior to start of work) |                    |  |  |  |  |  |
| PRICE FIRM THROUGH (          | Minimum of 120 days):                                  | DATE:              |  |  |  |  |  |
|                               |  |                    |  |  |  |  |  |
| PERIOD OF PERFORMAN           | CE:  | DATE:              |  |  |  |  |  |
|                               | (Services shall be performed and deliver               | ables provided by) |  |  |  |  |  |
| ESTIMATE PREPARED IN          | ACCORDANCE WITH THE ABOVE S                            | SCOPE OF WORK BY:  |  |  |  |  |  |
|                               |  |                    |  |  |  |  |  |
|                               |  | DATE:              |  |  |  |  |  |
|                               | (Contractor)   | ·                  |  |  |  |  |  |
|                               |  |                    |  |  |  |  |  |
| <b>AUTHORIZED BY:</b>         |  | DATE:              |  |  |  |  |  |
|                               | (County Rep/Project Manager, Proper                    | ty Management )    |  |  |  |  |  |
|                               |  |                    |  |  |  |  |  |
| WORK COMPLETED:               |  | DATE:              |  |  |  |  |  |
|                               | (Contractor)   | <u> </u>           |  |  |  |  |  |

Instructions: Contractor to FAX estimate to (703) 330-5435 authorization by County Rep/Project Manager by \_\_\_\_\_ at 5:00PM Contractor to notify County Rep/Project Manager if job cost exceeds estimate. Contractor to submit authorized copy with invoice. 8/10/07

#### DAILY REPORT / PROJECT DIARY

| Day:<br>Weather:<br>Temperat | ntractor Worked: Hours<br>umber : | AM:<br>Low:<br>From:<br>Insp. Tim |                |       | Page No:  Date: PM: High: To: |               |  |
|------------------------------|-----------------------------------|-----------------------------------|----------------|-------|-------------------------------|---------------|--|
| Item #                       | <u>Description</u>                | <u>Unit</u>                       | Quantity       | Price |                               | Location      |  |
| <u>110111 11</u>             | Бессирион                         | <u> </u>                          | <u>quarity</u> | 11100 |                               | <u> </u>      |  |
|                              |                                   |                                   |                |       |                               |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
| Labor                        |                                   |                                   |                |       | <br>  Equipment               |               |  |
| Labor                        |                                   |                                   |                |       | Equipment                     |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
| Commen                       | ·e·                               |                                   |                |       |                               |               |  |
| Commen                       |                                   |                                   |                |       |                               |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
|                              |                                   |                                   |                |       |                               |               |  |
| Name:                        | <del></del>                       | Approv                            | ed by          |       |                               | <del>_</del>  |  |
| Inspector                    | Keeping This Diary                |                                   |                |       | Project Engin                 | eer (Initial) |  |
| Signed:                      |                                   |                                   |                |       |                               |               |  |

#### <u>Soils</u>

The undersimed arrived on site, as requested, to observe the placement of compaction of soils for

| (give locations and provide site sketch for exact test locations). Please see the attached sketch.   |
|--|
| Utilizing the Nuclear Method (ASTM D-2922) to check compaction of soils; test results indicated that the compacted material, at the areas and elevations tested, met or exceeded the project requirements of% the maximum dry density as obtained in our laboratory by using the Standard Proctor Method (ASTM D-698) (with the exception of (give location (s) of areas that failed). The contractor was notified and (describe what action was taken). |
| The soils observed on this date appeared to be placed in compliance with project drawings and specifications with regards to lift thickness and moisture content. (with the exception of (describe what failed and why).   |

#### Supplementary forms:

Compaction Summary Sheet-attached to field report

Prince William County forms-only used in Prince William, attached to field report

#### Additional notes on soil reporting:

- \* Always include a sketch showing the location of fill placement **AND** the locations of where you took your tests.
- \* If you get failing test results for any area, make sure that you record the specific location and that you do eventually get a passing testing that same location (or detail the reason why not.) An uncorrected failing test should be recorded as a deficiency.
- \* Be sure to include an elevation or depth below subgrade to provide test locations vertically, in addition to the horizontal locations provided by the sketch.
- \* Compaction test results higher than 102-1035 probably indicate an incorrect proctor for the soil you are testing. Call you project engineer for instruction.
- \* Prince William County requires One-Point-Proctor tests for soils for work for subgrades of roads that will be turned over to the state. See your project engineer or supervisor to get the special forms.
- \* Be aware that you will need to do a +4 correction if the percentage of gravel changes.
- \* When giving locations, be specific and used fixed markers. Examples:
  - Three 8" lifts at sanitary trench from manhole #8 to 30' north of manhole #8
  - Fill at building pad #2
  - Backfill from station 1+50 to station 2+75
  - Be sure to check project specifications for the appropriate compaction percentage.
- \* TECHNICIAN REMEMBER TO ALWAYS (ALL REPORTS) GIVE THE PINK COPY TO CONTRACTOR BEFORE LEAVING THE JOB SITE, ESPECIALLY IF A DEFICIENCY EXISTED FOR THAT DAY.

#### 21A/21B or CR6

| 21A or 21B graded aggregate, CR6, VDOT No. 57 course aggregate] (pick one) for (give location of subbase placement and provide site sketch for exact test locations). Please see the attached sketch.  |
|--|
| Utilizing the Nuclear Method (ASTM D-2922) (or the Sand Cone Method (ASTM S-1556) (write only the method used ) to check compaction of subbase [VDOT No. 21A or 21B graded aggregate, CR6, VDOT No. 57 course aggregate] (pick one); test results indicated that the compacted material, at the areas and elevations tested, met or exceeded the project requirements of % the maximum dry density as obtained (if from supplier, give the company name) in our laboratory by using the Standard Proctor Method (ASTM D-698) (or the Modified Proctor Method (ASTM D-1557) (write only the proctor method used), (with the exception of (give locations (s) of areas that failed). The contractor was notified and (describe what action was taken). |
| The subbase observed on this date appeared to be placed in compliancewith project drawings and specifications with regards to lift thickness and moisture content. (with the exception of (describe what failed and why).  |
| Supplementary forms:   |

Compaction Summary Sheet-attached to field report Prince William County forms as necessary

#### Additional notes on 21A or 21B testing;

- \* Always include a sketch showing exact placement and test locations.
- \* Find out what quarry the material is coming from. Call the quarry and ask for a proctor value for the material they are hauling. The quarry will give you the following; 1. Dry density of the material; 2. The percent of +4 material; 3. The specific gravity of the +4; and 4. The optimum moisture content of the -4 marterial. Use these numbers with the nomograph to perform a +4 correction and moisture content correction.
- \* The type of equipment used to compact 21A, 21B or CR6 determines allowable lift thickness. If a jumpingiack
  - is used for compaction, lifts should not exceed 3" in thickness (uncompacted). If a large steel-drum roller is used, 21A, 21B or CR 6 can be placed in up to 6' lifts.
- \* Do not test for compaction on an area of subbase that has an excessive amount of course or fine aggregate.
- \* TECHNICIAN REMEMBER TO ALWAYS (ALL REPORTS) GIVE THE PINK COPY TO CONTRACTOR BEFORE LEAVING THE JOB SITE, ESPECIALLY IF A DEFICIENCY EXISTED FOR THAT DAY.

#### DAILY TESTING

### Geotechnical Consulting & Testing, Inc.



4899 Prince William Parkway Woodbridge, Virginia 22192 Phone (703) 730-4160 21505 Greenoak Way Dulles, Virginia 20166 Phone (703) 421-4000

## NUCLEAR DENSITY TEST FOR SOIL OR AGGREGATE DIRECT TRANSMISSION ONLY

| Project:   | Date:  |
|--|--|
| Producer:  | Diamet I and in the  |
| Nuc. Gauge Mod. No.  | Serial No:   |
| FIELD TEST NUMBER:  STREET  STATION  REFERENCE TO CENTER LINE  ELEVATION  TYPE OF TEST  METHOD OF COMPACTION  COMPACTED DEPTH OF LIFT  |  |
| GAUGE DEPTH SETTING  |  |
| (A) WET DENSITY PCF (B) MOISTURE WT.PCF (C) DRY DENSITY PCF (A-B) (D) PERCENT MOISTURE (C/G) (E) MAXIMUM DRY WT. PCF (F) OPTIMUM MOISTURE CONTENT (G) CORRECTED MAX. DRY WT. (H) CORRECTED OPTIMUM MOIST. (I) % DENSITY (C/G) X 100 (J) % DENSITY REQUIRED | DENSITY DETERMINATION  |
| (3) 70 DENSITT REQUIRED  | 4 DETERMINATION  |
| (A) WT. OF TOTAL SAMPLE & PAN (B) WT. OF PAN (C) NET WT. OF SAMPLE (A/B) (D) WT OF +4 MAT. & PAN (E) WT. OF PAN (F) NET WT OF +4 MAT. (D/E) (G) % OF +4 MAT. (F/C) X 100   |  |
| Technician: Cert No. Observed by:  (PWC Inspector)   | SEAL   |
|  | RE CONDUCTED IN CONFORMANCE WITH THE CURRENT AND PROCEDURES AND WITH THE PRIOR APPROVAL OF |
| (Signature)  | (Date)   |



### Geotechnical Consulting & Testing, Inc.

□ 4899 Prince William Parkway Woodbridge, VA 22192 (703) 730-4160

Engineering Report #:

☐ 21505 Greenoak Way Dulles, VA 20166 (703) 421-4000

Test Date:

#### COMPACTION TEST REPORT

Utilities/Backfill

| Con | ect Name:<br>tractor:<br>npaction M  |  |              |              |             |   |    | GCT Pro |            |   |    |           |
|-----|--|--|--------------|--------------|-------------|---|----|---------|------------|---|----|-----------|
|     | ge Serial  |  |              | DS:          |             |   |    |         | MS:        |   |    |           |
| #   | Sta  | Test Location (see belo<br>Street and/or Utility | Stru<br>From | cture        | Elev<br>-SG | # | DC | МС      | Den<br>Wet | sity<br>Dry                             | M% | %<br>Comp |
|     | and the second of the Paris of State of |  |              |              |             |   |    |         |            |   |    |           |
|     |  |  |              |              |             |   |    |         |            | *************************************** |    |           |
|     |  |  |              |              |             |   |    |         |            |   |    |           |
|     |  |  |              |              |             |   |    |         |            |   |    |           |
|     |  |  |              | <del> </del> |             |   |    |         |            |   |    |           |
|     |  |  |              |              |             |   |    |         |            |   |    |           |
|     |  |  |              |              |             |   |    |         |            |   |    |           |
|     |  |  |              | -            |             |   |    |         |            |   |    |           |
|     |  |  |              |              |             |   |    |         |            |   |    |           |

#### PROCTOR INFORMATION

|   | Detailed Soil Description | Dry     |    | +4% | Corrected |    |
|---|---------------------------|---------|----|-----|-----------|----|
| # |                           | Density | M% |     | Density   | М% |
|   |                           |         |    |     |           |    |
|   |                           |         |    |     |           |    |
|   |                           |         |    |     |           |    |
|   |                           |         |    |     |           |    |

#### Choose from one of the following for TEST LOCATION.

SAN = Sanitary Main

Roadway (Example: Northborne Drive) General Fill (No Utility BF)

SAN LAT = Sanitary Lateral (Lot #)

CG = Curb & Gutter (Road Name Here)

STM = Stormwater

SWM Dam = Dam Embankment

WM = Water Main (Road Name Here)

Use SG for finished grading ONLY

WS = Water Services (Lot #)

## **Planning Level Cost Estimate-**

Project Start Year: 20##

|                                   |                                  | Date:         |               |
|-----------------------------------|----------------------------------|---------------|---------------|
| Contruction Cost Estin            | nate :                           |               |               |
| <u>Estimate</u>                   | Year :                           |               |               |
| Project Start                     | Year :                           |               |               |
| ·                                 |                                  |               |               |
| PE Design                         |                                  | Design        | Management    |
| PE Design (consultant fees)       | 5%-20% of construction           |               |               |
| PWC PM Fees/Costs                 | 25%-35% of PE                    |               | \$0.00        |
| VDOT PM Fees/Costs                | 5%-15% of PE                     |               | \$0.00        |
| Permits                           | 5% of PE                         |               | \$0.00        |
| Environmental Fees/Costs          |                                  |               | \$0.00        |
| PE Subtotals                      |                                  | \$0.00        | \$0.00        |
| PE TOTAL                          | \$0.00                           | <u>30.00</u>  | <u> 30.00</u> |
| Diale of Man                      | ·                                |               |               |
| Right of Way                      |                                  | ROW           | Management    |
| Right of Way Acquisition          |                                  |               |               |
| Utility Relocation                |                                  |               |               |
| Enviromental Mitigations          |                                  |               |               |
| ROW/Utility Relocatiobs Subtotals |                                  | \$0.00        | \$0.00        |
| ROW/Utility Relocation TOTAL      | <u>\$0.00</u>                    | •             |               |
|                                   |                                  |               |               |
| CONSTRUCTION                      |                                  | Construction  | Management    |
| Construction (contractor cost)    | 100% of estimate                 |               |               |
| PWC PM and CEI Fees               | 15%-30% of estimate              |               | \$0.00        |
| VDOT PM and CEI Fees              | 2%-5% of estimate                |               | \$0.00        |
| Construction Subtotals            |                                  | \$0.00        | \$0.00        |
| Construction TOTAL                | <u>\$0.00</u>                    | <del></del> - |               |
|                                   |                                  |               |               |
| Current TOTAL COST                | (DE_ROW and Construction present | t value)      | \$0.00        |

## **Planning Level Cost Estimate-**

### **Current Cost Estimate with Contingencies**

|                          |  | Date: 0                | -Jan-00           |
|--------------------------|--|------------------------|-------------------|
| CONTINGENCIES            |  |                        |                   |
| PE Design Contingency    | 10%-40% of PE Design                         | Ε                      | 0.0               |
| ROW Contingency          | 0% for Right of Way                          |                        | 0.0               |
| Construction Contingency | 10%-40% of Construction                      |                        | 30.0              |
| PM and CM Contingency    | 10% for PWC+VDOT Project Manageme            | ent                    | 0.0               |
| PE Subtotals             |  | Design \$0.00          | Management \$0.00 |
| PE TOTAL                 | <u>\$0.00</u>                                |                        |                   |
|                          |  | ROW                    | Management        |
| ROW Subtotals            |  | <u>\$0.00</u>          | \$0.00            |
| ROW TOTAL                | \$0.00                                       |                        |                   |
|                          |  | Construction           | Management        |
| Construction Subtotals   |  | <u>\$0.00</u>          | \$0.00            |
| Construction TOTAL       | \$0.00                                       |                        |                   |
| Estimated Budget TOTAL   | L COST (PE, ROW and Construction present val | ue with contingencies) | \$0.00            |

## **Planning Level Cost Estimate-**

### Future Cost Estimate

|                          |                                  | Date:                        |               |
|--------------------------|----------------------------------|------------------------------|---------------|
| CURRENT COST             |                                  | YEAR: 0                      |               |
| Current TOTAL COST       | (PE, ROW and Construction presen | nt value with contingencies) | <u>\$0.00</u> |
| FUTURE COST              |                                  | YEAR: 2                      | 021           |
| Delay                    | in years                         | 2 ye                         |               |
| Inflation Rate           | 2.5%-5.0% per annum              | 4.00 %                       |               |
|                          |                                  | Design                       | Management    |
| PE Design Subtotals      |                                  | <u>\$0.00</u>                | <u>\$0.00</u> |
| PE Design TOTAL          | \$0.00                           |                              |               |
|                          |                                  | ROW                          | Management    |
| ROW Subtotals            |                                  | \$0.00                       | <u>\$0.00</u> |
| ROW TOTAL                | \$0.00                           |                              |               |
|                          |                                  | Construction                 | Management    |
| Construction Subtotals   |                                  | <u>\$0.00</u>                | <u>\$0.00</u> |
| Construction TOTAL       | <u>\$0.00</u>                    |                              |               |
| Future TOTAL COST        | (PE, ROW and Construction future | value with contingencies)    | <u>\$0.00</u> |
| Cost in delaying project | \$0.00                           |                              |               |



## A. Settlement Statement (HUD-1)

| B. Type of Loan   |                     |                         |                                |                    |                    |
|---|---------------------|-------------------------|--------------------------------|--------------------|--------------------|
| B. Type of Loan   |                     |                         |                                |                    |                    |
| 1. FHA 2. RHS 3. Conv. U  | Jnins. 6. File Numb | oer:                    | 7. Loan Number:                | 8. Mortgage Insur  | rance Case Number: |
| 4. VA 5. Conv. Ins.   |                     |                         |                                |                    |                    |
| C. Note: This form is furnished to give you a statement of actu "(p.o.c.)" were paid outside the closing; they are show |                     |                         |                                |                    | s marked           |
| D. Name & Address of Borrower:  | E. Name & A         | ddress of Selle         | er:                            | F. Name & Addres   | ss of Lender:      |
|   |                     |                         |                                |                    |                    |
|   |                     |                         |                                |                    |                    |
|   |                     |                         |                                |                    |                    |
|   |                     |                         |                                |                    |                    |
| G. Property Location:   | H. Settlemer        | at Agent:               |                                | I. Settlement Date | a·                 |
| G. Property Location.   | Ti. Settlemen       | it Agent.               |                                | i. Settlement Date | <del>.</del>       |
|   | DI 60 I             |                         |                                |                    |                    |
|   | Place of Set        | tlement:                |                                |                    |                    |
|   |                     |                         |                                |                    |                    |
| J. Summary of Borrower's Transaction  |                     | K. Sumn                 | nary of Seller's Transac       | ction              |                    |
|   |                     |                         |                                |                    |                    |
| 100. Gross Amount Due from Borrower   |                     | 400. Gros               | s Amount Due to Seller         |                    |                    |
| 101. Contract sales price   |                     | 401. Contr              | ract sales price               |                    |                    |
| 102. Personal property  |                     | 402. Perso              | onal property                  |                    |                    |
| 103. Settlement charges to borrower (line 1400)   |                     | 403.                    |                                |                    |                    |
| 104.  |                     | 404.                    |                                |                    |                    |
| 105.  |                     | 405.                    |                                |                    |                    |
| Adjustment for items paid by seller in advance  |                     | _                       | nt for items paid by seller    | in advance         |                    |
| 106. City/town taxes to   |                     | 406. City/t             |                                | to                 |                    |
| 107. County taxes to  |                     | 407. Coun               |                                | to                 |                    |
| 108. Assessments to   |                     | 408. Asses              | ssments                        | to                 |                    |
| 110.  |                     | 409.<br>410.            |                                |                    |                    |
| 111.  |                     | 410.                    |                                |                    |                    |
| 112.  |                     | 412.                    |                                |                    |                    |
| 120. Gross Amount Due from Borrower   |                     |                         | s Amount Due to Seller         |                    |                    |
| 200. Amount Paid by or in Behalf of Borrower  |                     |                         | ictions In Amount Due to s     | eller              |                    |
| 201. Deposit or earnest money   |                     |                         | ss deposit (see instructions)  |                    |                    |
| 202. Principal amount of new loan(s)  |                     | 502. Settle             | ement charges to seller (line  | 1400)              |                    |
| 203. Existing loan(s) taken subject to  |                     | 503. Existi             | ng loan(s) taken subject to    |                    |                    |
| 204.  |                     | 504. Payo               | ff of first mortgage loan      |                    |                    |
| 205.  |                     | 505. Payo               | ff of second mortgage loan     |                    |                    |
| 206.  |                     | 506.                    |                                |                    |                    |
| 207.  |                     | 507.                    |                                |                    |                    |
| 208.  |                     | 508.                    |                                |                    |                    |
| 209.  |                     | 509.                    |                                |                    |                    |
| Adjustments for items unpaid by seller  |                     | _                       | nts for items unpaid by se     |                    |                    |
| 210. City/town taxes to   |                     | 510. City/t             |                                | to                 |                    |
| 211. County taxes to 212. Assessments to  |                     | 511. Coun<br>512. Asses | -                              | to                 |                    |
| 213.  |                     | 513.                    | Somerito                       | to                 |                    |
| 214.  |                     | 514.                    |                                |                    |                    |
| 215.  |                     | 515.                    |                                |                    |                    |
| 216.  |                     | 516.                    |                                |                    |                    |
| 217.  |                     | 517.                    |                                |                    |                    |
| 218.  |                     | 518.                    |                                |                    |                    |
| 219.  |                     | 519.                    |                                |                    |                    |
| 220. Total Paid by/for Borrower   |                     | 520. Total              | Reduction Amount Due S         | eller              |                    |
| 300. Cash at Settlement from/to Borrower  |                     | 600. Cash               | at Settlement to/from Sell     | er                 |                    |
| 301. Gross amount due from borrower (line 120)  |                     | 601. Gross              | s amount due to seller (line 4 | 120)               |                    |

The Public Reporting Burden for this collection of information is estimated at 35 minutes per response for collecting, reviewing, and reporting the data. This agency may not collect this information, and you are not required to complete this form, unless it displays a currently valid OMB control number. No confidentiality is assured; this disclosure is mandatory. This is designed to provide the parties to a RESPA covered transaction with information during the settlement process.

603. Cash

602. Less reductions in amounts due seller (line 520)

From Seller

302. Less amounts paid by/for borrower (line 220)

From

To Borrower

303. Cash

| L. Settlement Charges  |                             |                         |          |                  |                         |                     |
|--|-----------------------------|-------------------------|----------|------------------|-------------------------|---------------------|
| 700. Total Real Estate Broker Fees                                 |                             |                         |          |                  | Doid From               | Doid From           |
| Division of commission (line 700) as fo                            | llows :                     |                         |          |                  | Paid From<br>Borrower's | Paid From Seller's  |
| 701. \$ to   |                             |                         |          |                  | Funds at<br>Settlement  | Funds at Settlement |
| 702. \$ to   |                             |                         |          |                  |                         |                     |
| 703. Commission paid at settlement                                 |                             |                         |          |                  |                         |                     |
| 704.   |                             |                         |          |                  |                         |                     |
| 800. Items Payable in Connection with Lo                           | oan                         |                         |          |                  |                         |                     |
| 801. Our origination charge  |                             |                         | \$       | (from GFE #1)    |                         |                     |
| 802. Your credit or charge (points) for the sp                     | ecific interest rate choser | 1                       | \$       | (from GFE #2)    |                         |                     |
| 803. Your adjusted origination charges                             |                             |                         |          | (from GFE #A)    |                         |                     |
| 804. Appraisal fee to  |                             |                         |          | (from GFE #3)    |                         |                     |
| 805. Credit report to  |                             |                         |          | (from GFE #3)    |                         |                     |
| 806. Tax service to 807. Flood certification to                    |                             |                         |          | (from GFE #3)    |                         |                     |
| 808.   |                             |                         |          | (from GFE #3)    |                         |                     |
| 809.   |                             |                         |          |                  |                         |                     |
| 810.   |                             |                         |          |                  |                         |                     |
| 811.   |                             |                         |          |                  |                         |                     |
|  | lin Advance                 |                         |          |                  |                         |                     |
| 900. Items Required by Lender to be Paid                           |                             | ldov                    |          | (Fr OFF 1146)    |                         |                     |
| 901. Daily interest charges from                                   | to @\$                      | /day                    |          | (from GFE #10)   |                         |                     |
| 902. Mortgage insurance premium for 903. Homeowner's insurance for | months to years to          |                         |          | (from GFE #3)    |                         |                     |
| 904.   | yours to                    |                         |          | (IIOIII GFE #11) |                         |                     |
|  |                             |                         |          |                  |                         |                     |
| 1000. Reserves Deposited with Lender                               |                             |                         |          |                  |                         |                     |
| 1001. Initial deposit for your escrow account                      |                             |                         | Φ.       | (from GFE #9)    |                         |                     |
| 1002. Homeowner's insurance 1003. Mortgage insurance               | months @ \$ months @ \$     | per month<br>per month  | \$<br>\$ |                  |                         |                     |
| 1004. Property Taxes   | months @ \$                 | per month               | \$       |                  |                         |                     |
| 1005.  | months @ \$                 | per month               | \$       |                  |                         |                     |
| 1006.  | months @ \$                 | per month               | \$       |                  |                         |                     |
| 1007. Aggregate Adjustment   |                             |                         | -\$      |                  |                         |                     |
| 1100. Title Charges  |                             |                         |          |                  |                         |                     |
| 1101. Title services and lender's title insuran                    | ice                         |                         |          | (from GFE #4)    |                         |                     |
| 1102. Settlement or closing fee                                    |                             |                         | \$       | ()               |                         |                     |
| 1103. Owner's title insurance                                      |                             |                         |          | (from GFE #5)    |                         |                     |
| 1104. Lender's title insurance                                     |                             |                         | \$       | ,                |                         |                     |
| 1105. Lender's title policy limit \$                               |                             |                         |          |                  |                         |                     |
| 1106. Owner's title policy limit \$                                |                             |                         | •        |                  |                         |                     |
| 1107. Agent's portion of the total title insurar                   |                             |                         | \$       |                  |                         |                     |
| 1108. Underwriter's portion of the total title i                   | nsurance premium to         |                         | \$       |                  |                         |                     |
| 1109.  |                             |                         |          |                  |                         |                     |
| 1110.  |                             |                         |          |                  |                         |                     |
| 1111.  |                             |                         |          |                  |                         |                     |
| 1200. Government Recording and Transfe                             | er Charges                  |                         |          |                  |                         |                     |
| 1201. Government recording charges                                 |                             |                         |          | (from GFE #7)    |                         |                     |
| 1202. Deed \$ Mortga   | ige \$                      | Release \$              |          | (C. 677          |                         |                     |
| 1203. Transfer taxes  1204. City/County tax/stamps  Deed           | 1.S. Morto                  | gage \$                 |          | (from GFE #8)    |                         |                     |
| 1205. State tax/stamps Deed  |                             | gage \$                 |          |                  |                         |                     |
| 1206.  | , iviority                  | 7-3- ¥                  |          |                  |                         |                     |
| 1300. Additional Settlement Charges                                |                             |                         |          |                  |                         |                     |
| 1301. Required services that you can shop f                        | ·or                         |                         |          | (from GFE #6)    |                         |                     |
| 1301. Required services that you can shop to                       | O.                          | \$                      |          | ( 5. 2 //5)      |                         |                     |
| 1303.  |                             | \$                      |          |                  |                         |                     |
| 1304.  |                             |                         |          |                  |                         |                     |
| 1305.  |                             |                         |          |                  |                         |                     |
| 1400. Total Settlement Charges (en                                 | iter on lines 103. Sec      | tion I and 502 Section  | K)       |                  |                         |                     |
|  | nor on lines 103, 3et       | Alon o and 302, Section | Α,       |                  |                         |                     |

| Charges That Cannot Increase  | HUD-1 Line Number   |   |  |  |  |
|---|---|---|--|--|--|
| Our origination charge  | # 801   |   |  |  |  |
| Your credit or charge (points) for the specific interest rate chosen  | # 802   |   |  |  |  |
| Your adjusted origination charges   | # 803   |   |  |  |  |
| Transfer taxes  | # 1203  |   |  |  |  |
|   |   |   |  |  |  |
| Charges That In Total Cannot Increase More Than 10%   |   | Good Faith Estimate   | HUD-1  |  |  |
| Government recording charges  | # 1201  |   |  |  |  |
|   | #   |   |  |  |  |
|   | #   |   |  |  |  |
|   | #   |   |  |  |  |
|   | #   |   |  |  |  |
|   | #   |   |  |  |  |
|   | #   |   |  |  |  |
|   | #   |   |  |  |  |
|   | Total   |   |  |  |  |
| Incre   | ease between GFE and HUD-1 Charges  | \$  | or %   |  |  |
|   |   |   |  |  |  |
| Charges That Can Change   |   | Good Faith Estimate   | HUD-1  |  |  |
| Initial deposit for your escrow account   | # 1001  |   |  |  |  |
| Daily interest charges \$ /day  | # 901   |   |  |  |  |
| Homeowner's insurance   | # 903   |   |  |  |  |
|   | #   |   |  |  |  |
|   | #   |   |  |  |  |
|   | #   |   |  |  |  |
| Loan Terms  |   |   |  |  |  |
| Your initial loan amount is   | \$  |   |  |  |  |
| Your loan term is   | years   |   |  |  |  |
| Your initial interest rate is   | %   |   |  |  |  |
| Your initial monthly amount owed for principal, interest, and any mortgage insurance is                               | \$ includes  Principal Interest Mortgage Insurance  | Principal Interest  |  |  |  |
| Can your interest rate rise?  | No Yes, it can rise to a maxing and can change again every interest rate can increase or decrease by guaranteed to never be lower than  | after   | change will be on  Every change date, your e loan, your interest rate is  %. |  |  |
| Even if you make payments on time, can your loan balance rise?  | No Yes, it can rise to a maxi   | mum of \$   |  |  |  |
| Even if you make payments on time, can your monthly amount owed for principal, interest, and mortgage insurance rise? | No Yes, the first increase ca owed can rise to \$ . The   | n be on and the maximum it can ever rise to is                                  | monthly amount   |  |  |
| Does your loan have a prepayment penalty?   | No Yes, your maximum prep   | payment penalty is \$   |  |  |  |
| Does your loan have a balloon payment?  | No Yes, you have a balloon on .   | payment of \$ d   | ue in years  |  |  |
| Total monthly amount owed including escrow account payments   | You do not have a monthly escrow homeowner's insurance. You must You have an additional monthly esthat results in a total initial monthly principal, interest, any mortagage  Property taxes  Flood insurance | st pay these items directly yours<br>scrow payment of \$<br>y amount owed of \$ | self This includes ked below:  |  |  |

Comparison of Good Faith Estimate (GFE) and HUD-1 Charrges

Good Faith Estimate

HUD-1

Note: If you have any questions about the Settlement Charges and Loan Terms listed on this form, please contact your lender.

### **DOT Pre-Ascend Request Form - Invoice**

To be completed by Requestor Revised 1/9/2018



| Select Analyst                                     |                            |                                     |               |                           |
|--|----------------------------|-------------------------------------|---------------|---------------------------|
| Select Transaction Type                            |                            |                                     |               |                           |
| Date   |                            |                                     |               |                           |
| Requestor  |                            |                                     |               |                           |
| Ascend PO or Task Order#                           |                            |                                     |               |                           |
| Check Request Pick up                              |                            |                                     |               |                           |
| Fund Type Use 1st and 2nd                          | d column for operating and |                                     |               |                           |
| 3rd and 4th column for pro                         | jects                      | Operating(GL) COA                   | Project PATEO | Project PATEO             |
|  |                            |                                     |               |                           |
| Total amount of invoice                            |                            |                                     |               |                           |
| Indicate if expense is to be                       | e split and % (Yes and %)  |                                     |               |                           |
| or No  |                            |                                     |               |                           |
| Select Title/Name operating Type in Project Name   |                            |                                     |               |                           |
| Project # If split funding                         |                            |                                     |               |                           |
| include all  |                            |                                     |               |                           |
| Select Fund for Oper Type                          |                            |                                     |               |                           |
| in for Project                                     |                            |                                     |               |                           |
|  |                            |                                     |               |                           |
| Department #                                       |                            |                                     |               |                           |
| Program #  |                            |                                     |               |                           |
| Activity#  |                            |                                     |               |                           |
| Object/expense                                     |                            |                                     |               |                           |
| Project Task:                                      |                            |                                     |               |                           |
| Organization                                       |                            |                                     |               |                           |
| Award #  |                            |                                     |               |                           |
| Blue = information to be entered                   |                            | Gray = select from a drop down list |               | Black = no<br>information |
| 1  |                            | drop down list                      |               | illiorillation            |
| Description & Billing<br>instuctions (indicate who |                            |                                     |               |                           |
| to bill, and amount of this                        |                            |                                     |               |                           |
| transactionto                                      |                            |                                     |               |                           |
| bill).Indicate if last                             |                            |                                     |               |                           |
| payment and PO to be                               |                            |                                     |               |                           |
| closed after payment. If                           |                            |                                     |               |                           |
| more than 2 awrds use                              |                            |                                     |               |                           |
| additional sheet.                                  |                            |                                     |               |                           |

# Prince William County Department of Transportation Project Closure Checklist

| Project Name  | Date             |        |    | •   |          |
|---|------------------|--------|----|-----|----------|
| Project Manager   | Project Number   |        |    |     |          |
| Please sign indicating you have reviewed (and checked off) activities relating to your respective response  | sibilities.      |        |    |     |          |
| PROJECT MANAGER SIGNATURE   |                  | DATE   |    |     |          |
| Activity  |                  | YES    | NO | N/A | Comments |
| All environmental issues have been resolved and finalized.  |                  |        |    |     |          |
| All outstanding and/or potential utility issues, including relocation invoices have been identified and paid.   |                  |        |    |     |          |
| All notice of intent to file claim/claims and issues have been identified and resolved.   |                  |        |    |     |          |
| All contractor assessed damages have been identified and resolved.  |                  |        |    |     |          |
| All the contract requirements for bonds have been met and released (bid, performance, labor, etc.)  |                  |        |    |     |          |
| All field office refunds for electric services, phone, water, etc., have been identified and collected.   |                  |        |    |     |          |
| All punch list items are completed.   |                  |        |    |     |          |
| The project has been accepted by the County and VDOT and C-5 has been issued.   |                  |        |    |     |          |
| All internal service obligations and bills have been identified and paid. (Construction Crew, Cost Recoverie  | es, IDT's, etc.) |        |    |     |          |
| All Agency proffers, donations and other funds have been identified and received.   |                  |        |    |     |          |
| All pending or potential litigation has been identified and forwarded to the County Attorney and resolved   | •                |        |    |     |          |
| All Board Resolutions have been resolved.   |                  |        |    |     |          |
| Project close out has been submitted to VDOT.   |                  |        |    |     |          |
| All contract work is completed, billed, and paid or released by PWC including retainage.  |                  |        |    |     |          |
| Final invoice mailed to VDOT.   |                  |        |    |     |          |
| RIGHT OF WAY SIGNATURE  |                  | DATE   |    |     |          |
| 8 - 41 - 14   |                  | VEC    | NO | N/A | C        |
| All right of way issues have been identified, settled and/or paid.  |                  | YES    | NO | N/A | Comments |
|   |                  |        |    |     |          |
| All pending or potential litigation has been identified and forwarded to the County Attorney and resolved. Estimated outstanding right of way liability | •                | Amount | ć  |     |          |
| Estimated outstanding right of way hability   |                  | Amount | Ş  |     |          |
| AGENCY ACCOUNTING SIGNATURE   |                  | DATE   |    |     |          |
| Activity  |                  | YES    | NO | N/A | Comments |
| All general ledger payable and receivable balances are zero.  |                  | 11.3   | NO | N/A | Comments |
| All field office refunds for electric services, phone, water, etc., have been identified and collected.   |                  |        |    |     |          |
| All revenue agreements have been identified, billed and received. (Bonds, Service Authority, VDOT, etc.)  |                  |        |    |     |          |
| All revenue and expense budgets have been reconciled and appropriate transfers made.  |                  |        |    |     |          |
| All hours have been billed and recovered through cost recovery.   |                  |        |    |     |          |
| All outstanding invoices have been paid.  |                  |        |    |     |          |
| All retainage funds have been released.   |                  |        |    |     |          |
| All purchase orders have been closed.   |                  |        |    |     |          |
| •   |                  |        |    |     |          |
| PURCHASING SIGNATURE  |                  | DATE   |    |     |          |
| Activity  |                  | YES    | NO | N/A | Comments |
| Purchase orders are closed and related procurement documents for project closure have been received.  |                  |        |    | Í   |          |
| MANAGEMENT & FISCAL ANALYST SIGNATURE   |                  | DATE   |    |     |          |
|   |                  |        |    |     |          |
| Activity  PT to Close Project Financially   |                  | YES    | NO | N/A | Comments |
| BT to Close Project - Financially   |                  |        |    |     |          |
| Attachments: Project Funds Available Data Dump Report Project Awards Fund Summary   |                  |        |    |     |          |
| APPROVALS   |                  | DATE   |    |     |          |
| Division Chief  |                  |        |    |     |          |
| Agency Senior Account   |                  |        |    |     |          |
| Administrative Analyst  |                  |        |    |     |          |
| Director  |                  |        |    |     |          |
| Finance/Accounting Division   |                  |        |    |     |          |
| Budget  |                  |        |    |     |          |

# Prince William County Project Closure Checklist ASCEND

| 110  | joot Globale Glibokilot AGGEND   |                                   |     |          |    |
|--|--|-----------------------------------|-----|----------|----|
| Agency Name  | Agency Nu  | mber                              |     |          |    |
| Project Name<br>Project Manager<br>Project Number    | Project OCA# Performance Start Date  | OCA Description<br>Review Date    |     | _        |    |
| Funding Sources – Check all that Apply               |  |                                   |     |          |    |
| General Fund Debt Sta                                | te 🗌 Federal 🔲   | Other $\square$                   |     |          |    |
| Proffers   | TC TRIP/Revenue Sharing  |                                   |     |          |    |
|  | wed (and checked off) activities relating ties which have been checked "NO" sh |                                   |     | <b>.</b> |    |
| ACTIVITY   |  |                                   | YES | NO       | NA |
| All contract work is completed, billed, and paid or  | released by PWC including retainage.   |                                   |     |          |    |
| All contractor claims and issues have been identi    | ified and resolved.  |                                   |     |          |    |
| All contractor assessed damages have been ider       | ntified and resolved.  |                                   |     |          |    |
| All the contract requirements for bonds have bee     | n met and released (bid, performance, labor, etc.)                             | )                                 |     |          |    |
| All VDOT issues have been identified and resolve     | ed.  |                                   |     |          |    |
| The project has been accepted by VDOT                |  |                                   |     |          |    |
| All internal service obligations and billings have b | een identified and paid.( Construction Crew, OIT,                              | Planning, Cost Recoveries, IDT's) |     |          |    |

#### Project Closure Checklist ASCEND

| ACTIVITY (Project Manager continued)   | YES | NO | NA |
|--|-----|----|----|
| All Agency proffers, donations and other funds been identified and received.   |     |    |    |
| All debt and miscellaneous revenue agreements have been identified, billed and received? (Bonds, Service Authority, VDOT, etc.)  |     |    |    |
| All pending or potential litigation has been identified and forwarded to the County Attorney and resolved.                       |     |    |    |
| All Board Resolutions have been resolved.  |     |    |    |
| All environmental issues have been resolved and finalized.   |     |    |    |
| All outstanding and/or potential utility issues, including relocation invoices have been identified and paid.                    |     |    |    |
| All field office refunds for electric services, phone, water etc., have been identified and collected.                           |     |    |    |
| RIGHT OF WAY SIGNATURE DATE ACTIVITY   | YES | NO | NA |
| All right of way issues have been identified, settled and/or paid.   |     |    | Ш  |
| All pending or potential litigation has been identified and forwarded to the County Attorney and resolved.                       |     |    |    |
| AGENCY ACCOUNTING SIGNATURE DATE   |     | -  |    |
| <u>ACTIVITY</u>  | YES | NO | NA |
| All general ledger payable and receivable balances are zero.   |     |    |    |
| All field office refunds for electric services, phone, water etc., have been identified and collected.                           |     |    |    |
| All retainage funds have been released.  |     |    |    |
| All debt and miscellaneous revenue agreements have been identified, billed, and received. (Bonds, Service Authority, VDOT, etc.) |     |    |    |
| All revenue and expense budgets have been reconciled and appropriate transfers made.   |     |    |    |

#### Project Closure Checklist ASCEND

| ACTIVITY (Agency Accounting Continued)  | YES        | NO | NA  |
|---|------------|----|-----|
| All hours have been billed and recovered through cost recovery.   |            |    |     |
| All outstanding invoices have been paid.  |            |    |     |
|   |            |    |     |
| Purchasing Signature Date   |            | _  |     |
| ACTIVITY  | YES        | NO | NA  |
| Purchase orders are closed and related procurement documents for project closure have been received.                    |            |    |     |
| SignatureDate   |            |    |     |
| ACTIVITY  | YES        | NO | NA  |
| All respective work done by this internal service fund agency has been completed, billed, and funds have been received. |            |    |     |
| SignatureDate   |            |    |     |
| ACTIVITY  | YES        | NO | NA  |
| All respective work done by this internal service fund agency has been completed, billed, and funds have been received. |            |    |     |
| SignatureDate   |            |    |     |
| ACTIVITY  | ZES<br>SES | NO | □ × |
| All respective work done by this internal service fund agency has been completed, billed, and funds have been received. |            |    |     |

#### Project Closure Checklist ASCEND

| Approvals                               |       | Date |
|---|-------|------|
| Management and Fiscal Analyst           |       |      |
| Division Chief                          |       |      |
| Agency Senior Accountant                |       |      |
| Business Manager                        |       |      |
| Director                                |       |      |
| Forward to Finance/ Accounting Division | <br>_ |      |

#### **Comments and Action Items**

| Comment or Action Item | Responsible Party | Date Completed |
|------------------------|-------------------|----------------|
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |

### **Comments and Action Items Continued**

| Comment or Action Item | Responsible Party | Date Completed |
|------------------------|-------------------|----------------|
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |
|                        |                   |                |

### **PROJECT ESTIMATE WORKSHEET**

| Straight workstations         \$500.00         \$6           File banks/bookcases         \$50.00         \$6           All new product - EQUITY         \$7,500.00         \$6           Straight workstations         \$5,000.00         \$6           File banks/bookcases         \$1,500.00         \$6           All new product - CURRENTS         \$1,500.00         \$6           Standard workstations         -         \$1,500.00         \$6           Straight workstations         -         \$7         \$5         \$6   | Project Tasks                    | # of units | Cost per<br>unit | Total  |
|---|----------------------------------|------------|------------------|--------|
| Standard workstations         \$750.00         \$6           Straight workstations         \$500.00         \$6           File banks/bookcases         \$500.00         \$6           All new product - EQUITY         \$7,500.00         \$6           Straight workstations         \$5,000.00         \$6           File banks/bookcases         \$1,500.00         \$6           All new product - CURRENTS         \$1         \$1,500.00         \$6           All new product - CURRENTS         \$1         \$1,500.00         \$6           All new product - CURRENTS         \$1         \$5,000.00         \$6           Straight workstations         \$1,500.00         \$6           Straight workstations         \$3,200.00         \$6           Systems product, reconfiguration         \$2,000.00         \$6           Straight workstations         \$2,000.00         \$6           Straight workstations         \$150.00         \$6           Existing systems teardown         \$150.00         \$6           Straight workstations         \$150.00         \$6           Straight workstations         \$525.00         \$6           Installation of systems         \$250.00         \$6           Straight workstations         \$250.00   | SYSTEMS FURNITURE                |            |                  |        |
| Straight workstations         \$500.00         \$6           File banks/bookcases         \$50.00         \$6           All new product - EQUITY         \$7,500.00         \$6           Straight workstations         \$5,000.00         \$6           File banks/bookcases         \$1,500.00         \$6           All new product - CURRENTS         \$1,500.00         \$6           All new product - CURRENTS         \$1,500.00         \$6           Straight workstations         \$-         \$5           Straight workstations         \$3,200.00         \$6           File banks/bookcases         \$2,000.00         \$6           Straight workstations         \$2,000.00         \$6           File banks/bookcases         \$600.00         \$6           Existing systems teardown         \$150.00         \$6           Straight workstations         \$150.00         \$6           Straight workstations         \$75.00         \$6           Installation of systems         \$25.00         \$6           Straight workstations         \$250.00         \$6           Straight workstations         \$250.00         \$6           Installation of systems         \$250.00         \$6           Straight workstations         \$2   | Design for systems furniture     |            |                  |        |
| File banks/bookcases         \$50.00         \$6           All new product - EQUITY         \$7,500.00         \$6           Straight workstations         \$5,000.00         \$6           Straight workstations         \$1,500.00         \$6           All new product - CURRENTS         \$1,500.00         \$6           Standard workstations         -         \$1  | Standard workstations            |            | \$750.00         | \$0.00 |
| All new product - EQUITY         \$7,500.00         \$6           Straight workstations         \$5,000.00         \$6           File banks/bookcases         \$1,500.00         \$6           All new product - CURRENTS         \$1,500.00         \$6           Standard workstations         -         \$1,500.00         \$6           Straight workstations         -         \$5,000.00         \$6           File banks/bookcases         -         \$3,200.00         \$6           Straight workstations         \$2,000.00         \$6           Existing systems teardown         \$600.00         \$6           Existing systems teardown         \$150.00         \$6           Straight workstations         \$150.00         \$6           Straight workstations         \$150.00         \$6           Installation of systems         \$75.00         \$6           Straight workstations         \$525.00         \$6           Straight workstations         \$250.00         \$6           File banks/bookcases         \$125.00         \$6           Electrical         \$250.00         \$6   | Straight workstations            |            | \$500.00         | \$0.00 |
| Standard workstations         \$7,500.00         \$6           Straight workstations         \$5,000.00         \$6           File banks/bookcases         \$1,500.00         \$6           All new product - CURRENTS         -         \$1,500.00         \$6           Standard workstations         -         -         \$1,500.00         \$6           Straight workstations         -         -         \$2,000.00         \$6         \$6         \$5         \$5         \$5         \$600.00         \$6         \$6         \$600.00         \$6         \$6         \$600.00         \$6 <t< td=""><td>File banks/bookcases</td><td></td><td>\$50.00</td><td>\$0.00</td></t<> | File banks/bookcases             |            | \$50.00          | \$0.00 |
| Straight workstations         \$5,000.00         \$0           File banks/bookcases         \$1,500.00         \$0           All new product - CURRENTS         \$1,500.00         \$0           Standard workstations         -         \$1           Straight workstations         -         \$2           File banks/bookcases         \$3,200.00         \$0           Straight workstations         \$2,000.00         \$0           File banks/bookcases         \$600.00         \$0           Existing systems teardown         \$150.00         \$0           Straight workstations         \$150.00         \$0           Straight workstations         \$75.00         \$0           Installation of systems         \$250.00         \$0           Straight workstations         \$250.00         \$0           File banks/bookcases         \$125.00         \$0           Electrical         \$25.00         \$0  | All new product - EQUITY         |            |                  |        |
| File banks/bookcases         \$1,500.00         \$0           All new product - CURRENTS         -         -           Standard workstations         -         -           File banks/bookcases         -         -           Systems product, reconfiguration         \$3,200.00         \$0           Standard workstations         \$2,000.00         \$0           Straight workstations         \$600.00         \$0           Existing systems teardown         \$150.00         \$0           Straight workstations         \$150.00         \$0           Straight workstations         \$100.00         \$0           Installation of systems         \$75.00         \$0           Straight workstations         \$525.00         \$0           Straight workstations         \$250.00         \$0           File banks/bookcases         \$125.00         \$0           Electrical         \$25.00         \$0   | Standard workstations            |            | \$7,500.00       | \$0.00 |
| All new product - CURRENTS         Standard workstations         -           Straight workstations         -         -           File banks/bookcases         -         -           Systems product, reconfiguration         \$3,200.00         \$0           Standard workstations         \$2,000.00         \$0           Straight workstations         \$600.00         \$0           File banks/bookcases         \$150.00         \$0           Straight workstations         \$100.00         \$0           File banks/bookcases         \$75.00         \$0           Installation of systems         \$525.00         \$0           Straight workstations         \$250.00         \$0           File banks/bookcases         \$125.00         \$0           File banks/bookcases         \$125.00         \$0           Electrical         \$250.00         \$0   | Straight workstations            |            | \$5,000.00       | \$0.00 |
| Standard workstations         -           Straight workstations         -           File banks/bookcases         -           Systems product, reconfiguration         \$3,200.00           Standard workstations         \$2,000.00           Straight workstations         \$600.00           File banks/bookcases         \$600.00           Existing systems teardown         \$150.00           Straight workstations         \$100.00           File banks/bookcases         \$75.00           Installation of systems         \$525.00           Straight workstations         \$525.00           Straight workstations         \$250.00           File banks/bookcases         \$125.00           File banks/bookcases         \$250.00  | File banks/bookcases             |            | \$1,500.00       | \$0.00 |
| Straight workstations         -           File banks/bookcases         -           Systems product, reconfiguration         \$3,200.00           Standard workstations         \$2,000.00           Straight workstations         \$600.00           File banks/bookcases         \$600.00           Existing systems teardown         \$150.00           Straight workstations         \$100.00           File banks/bookcases         \$75.00           Installation of systems         \$525.00           Straight workstations         \$250.00           Straight workstations         \$250.00           File banks/bookcases         \$125.00           File banks/bookcases         \$250.00  | All new product - CURRENTS       |            |                  |        |
| File banks/bookcases         -           Systems product, reconfiguration         \$3,200.00         \$0           Standard workstations         \$2,000.00         \$0           Straight workstations         \$600.00         \$0           File banks/bookcases         \$600.00         \$0           Existing systems teardown         \$150.00         \$0           Straight workstations         \$100.00         \$0           File banks/bookcases         \$75.00         \$0           Installation of systems         \$525.00         \$0           Straight workstations         \$250.00         \$0           File banks/bookcases         \$125.00         \$0           Electrical         \$25.00         \$0           Disconnections         \$25.00         \$0   | Standard workstations            |            | -                |        |
| Systems product, reconfiguration         \$3,200.00         \$0           Straight workstations         \$2,000.00         \$0           File banks/bookcases         \$600.00         \$0           Existing systems teardown         \$150.00         \$0           Straight workstations         \$150.00         \$0           Straight workstations         \$75.00         \$0           Installation of systems         \$525.00         \$0           Straight workstations         \$250.00         \$0           File banks/bookcases         \$125.00         \$0           Electrical         \$25.00         \$0   | Straight workstations            |            | -                |        |
| Standard workstations         \$3,200.00         \$0           Straight workstations         \$2,000.00         \$0           File banks/bookcases         \$600.00         \$0           Existing systems teardown         \$150.00         \$0           Standard workstations         \$100.00         \$0           File banks/bookcases         \$75.00         \$0           Installation of systems         \$525.00         \$0           Straight workstations         \$250.00         \$0           File banks/bookcases         \$125.00         \$0           Electrical         \$25.00         \$0           Disconnections         \$25.00         \$0  |                                  |            | -                |        |
| Straight workstations         \$2,000.00         \$0           File banks/bookcases         \$600.00         \$0           Existing systems teardown         \$150.00         \$0           Standard workstations         \$100.00         \$0           File banks/bookcases         \$75.00         \$0           Installation of systems         \$525.00         \$0           Straight workstations         \$250.00         \$0           File banks/bookcases         \$125.00         \$0           Electrical         \$25.00         \$0           Disconnections         \$25.00         \$0   | Systems product, reconfiguration |            |                  |        |
| File banks/bookcases         \$600.00         \$0           Existing systems teardown         \$150.00         \$0           Standard workstations         \$100.00         \$0           Straight workstations         \$75.00         \$0           Installation of systems         \$525.00         \$0           Straight workstations         \$250.00         \$0           File banks/bookcases         \$125.00         \$0           Electrical         \$25.00         \$0           Disconnections         \$25.00         \$0   | Standard workstations            |            | \$3,200.00       | \$0.00 |
| Existing systems teardown         \$150.00         \$0           Standard workstations         \$100.00         \$0           Straight workstations         \$75.00         \$0           Installation of systems         \$525.00         \$0           Standard workstations         \$525.00         \$0           Straight workstations         \$250.00         \$0           File banks/bookcases         \$125.00         \$0           Electrical         \$25.00         \$0           Disconnections         \$25.00         \$0  | Straight workstations            |            | \$2,000.00       | \$0.00 |
| Standard workstations         \$150.00         \$0           Straight workstations         \$100.00         \$0           File banks/bookcases         \$75.00         \$0           Installation of systems         \$525.00         \$0           Standard workstations         \$525.00         \$0           Straight workstations         \$250.00         \$0           File banks/bookcases         \$125.00         \$0           Electrical         \$25.00         \$0  | File banks/bookcases             |            | \$600.00         | \$0.00 |
| Straight workstations         \$100.00         \$0           File banks/bookcases         \$75.00         \$0           Installation of systems         \$525.00         \$0           Standard workstations         \$525.00         \$0           Straight workstations         \$250.00         \$0           File banks/bookcases         \$125.00         \$0           Electrical         \$25.00         \$0   | Existing systems teardown        |            |                  |        |
| File banks/bookcases \$75.00 \$0 Installation of systems Standard workstations \$525.00 \$0 Straight workstations \$250.00 \$0 File banks/bookcases \$125.00 \$0 Electrical Disconnections \$25.00 \$0  | Standard workstations            |            | \$150.00         | \$0.00 |
| Installation of systems         \$525.00           Standard workstations         \$525.00           Straight workstations         \$250.00           File banks/bookcases         \$125.00           Electrical         \$25.00           Disconnections         \$25.00  | Straight workstations            |            | \$100.00         | \$0.00 |
| Standard workstations         \$525.00         \$0           Straight workstations         \$250.00         \$0           File banks/bookcases         \$125.00         \$0           Electrical         \$25.00         \$0           Disconnections         \$25.00         \$0   |                                  |            | \$75.00          | \$0.00 |
| Straight workstations \$250.00 \$0 File banks/bookcases \$125.00 \$0 Electrical Disconnections \$25.00 \$0  | Installation of systems          |            |                  |        |
| File banks/bookcases \$125.00 \$0  Electrical \$25.00 \$0   | Standard workstations            |            | \$525.00         | \$0.00 |
| Electrical Disconnections \$25.00 \$0   | Straight workstations            |            | \$250.00         | \$0.00 |
| Disconnections \$25.00 \$0  |                                  |            | \$125.00         | \$0.00 |
| ·   | Electrical                       |            |                  |        |
| Connections \$150.00 \$0  | Disconnections                   |            | ·                | \$0.00 |
|   | Connections                      |            | \$150.00         | \$0.00 |
| Subtotal: \$0   |                                  |            | Subtotal         | \$0.00 |

| Project Tasks               | # of units | Cost per<br>unit | Total  |
|-----------------------------|------------|------------------|--------|
| FREESTANDING FURNITURE      |            |                  |        |
| Chairs (Allseating)         |            |                  |        |
| Task chairs                 |            | \$550.00         | \$0.00 |
| Executive chairs            |            | \$900.00         | \$0.00 |
| Conference/guest chairs     |            | \$375.00         | \$0.00 |
| Desks (Kimball - Affinity)  |            |                  |        |
| Standard double pedestal    |            | \$1,025.00       | \$0.00 |
| Secretarial "L"\$           |            | \$1,400.00       | \$0.00 |
| Executive "L"               |            | \$1,450.00       | \$0.00 |
| Executive "U"               |            | \$2,000.00       | \$0.00 |
| Tables (Kimball - Affinity) |            |                  |        |
| Rectangular, 84 x 42        |            | \$800.00         | \$0.00 |
| Round, 48 diameter          |            | \$675.00         | \$0.00 |
| Bookcases (Kimball)         |            |                  |        |
| 2-shelf wood                |            | \$375.00         | \$0.00 |
| 4-shelf wood                |            | \$650.00         | \$0.00 |
| File cabinets (Kimball)     |            |                  |        |
| 2-drawer, wood              |            | \$650.00         | \$0.00 |
| 4-drawer, wood              |            | \$1,050.00       | \$0.00 |
| Computer tables (Kimball)   |            | \$400.00         | \$0.00 |
|                             |            |                  |        |
|                             |            | Subtotal:        | \$0.00 |

| Project Tasks                          | # of units | Cost per unit | Total  |
|--|------------|---------------|--------|
| MISCELLANEOUS COST                     |            |               |        |
| Permits                                |            | \$125.00      | \$0.00 |
| Move                                   |            |               |        |
| Employee in systems furniture          |            | \$75.00       | \$0.00 |
| Employee in freestanding furniture     |            | \$125.00      | \$0.00 |
| Shared furniture (i.e. reception & CR) |            | \$125.00      | \$0.00 |
| Construction                           |            |               |        |
| Design                                 |            | \$0.00        | \$0.00 |
| Construction materials                 |            | \$0.00        | \$0.00 |
| Labor                                  |            | \$0.00        | \$0.00 |
|  |            |               |        |
|  |            | Subtotal:     | \$0.00 |
|  |            | TOTAL:        | \$0.00 |

| PROPOSAL REQUEST AIA DOCUMENT G709   | OWNER ARCHITECT CONTRACTOR FIELD OTHER |        |  |
|--|--|--------|--|
| PROJECT: (name, address)   |  |        | PROPOSAL REQUEST NO:                               |
| OWNER:   |  |        | DATE:  |
| TO: (Contractor)   |  | · —    | ARCHITECT'S PROJECT NO:                            |
| '  |  | ,      | CONTRACT FOR:                                      |
|  |  |        | CONTRACT DATED:                                    |
| Please submit an itemized quotation tions to the Contract Documents de   | n for changes in the Cescribed herein. | oņtrac | t Sum and/or Time incidental to proposed modifica- |
| THIS IS NOT A CHANGE ORDER   | NOR A DIRECTION                        | то     | PROCEED WITH THE WORK DESCRIBED HEREIN.            |
| Description: (Written description of the Wo  | rk)                                    |        |  |
|  |  |        |  |
|  |  |        |  |
| e de la companya de l |  |        |  |
|  |  |        |  |
|  | •                                      |        |  |
|  |  |        |  |
|  |  |        |  |
|  |  |        |  |
| Attachments: (List attached documents that s   | support description)                   |        |  |
|  |  |        |  |
|  |  |        |  |
|  |  |        |  |
|  |  |        |  |
|  |  |        |  |
|  |  |        |  |
|  |  |        |  |
| ARCHITECT:   |  |        |  |
| BY:  |  |        | · · · · · · · · · · · · · · · · · · ·              |

**OWNER** 

GENERAL NOTES

1. This site has been addressed by the Prince William County Mapping Office as: PRINCE WILLIAM COUNTY FIRE STATION 22


7500 CENTURY PARK DR, MANASSAS, VA 20109 (addresses for subdivision lots shall appear on the approved plat for recordation).


| 2. Addresses assigned are for the layout of individual businesses or dwelling units and are for exterior doors as shown on this plan only. Any deviation in design or layout will require that a revised plan be submitted to the Office of Mapping for re—addressing. It is the responsibility of the developer to inform the County Office of Mapping before a change in layout occurs and to submit complete and accurate information for re—addressing. Prince William County does not assume any responsibility where re—addressing is required even though tenants have | EXISTING INDEX CONTOUR  PROPOSED CONTOUR   | LEE HV   |  |
|---|--|--|--|
| already occupied a portion of the building.   | EXISTING EDGE OF PAVEMENT  PROPOSED EDGE OF PAVEMENT  EX. E/P  PROPOSED UTILITY POLE  EXISTING WATERLINE W/ TEE  PROPOSED UTILITY POLE  EXISTING WATERLINE W/ TEE  PROPOSED UTILITY POLE   | VETOI VETOI  | REVIEWED BY:  APPROVED BY:   |
| 3. Methods and materials used in the construction of the improvements herein shall conform to the current County construction standards and specifications and/or current VDOT standards and specifications.  | EXISTING CURB AND GUTTER $=$ $=$ $=$ $=$ $=$ $=$ $=$ $=$ $=$ $=$   | GRO  |  |
| <ol> <li>The contractor or developer is required to notify the Prince William County Department of Public Works in writing three (3) days prior to the beginning of the construction and specifically request inspection before beginning 703— 792—7070.         <ul> <li>A. Installation of approved erosion control devices.</li> <li>B. Clearing and Grading</li> </ul> </li> </ol>  | PROPOSED CURB AND GUTTER  TRANSITION FROM CG-6 TO CG-6R $ \begin{array}{c ccccccccccccccccccccccccccccccccccc$   | INTERSTATE I-66  | This plan has been reviewed and has been found to be in general conformance with the requirements of Prince William County. The developer is hereby authorized to obtain all necessary land development permits, subject to all designs, procedures, materials and |
| C. Subgrade excavation.  D. Installing storm sewers or culverts.  | EXISTING TELEPHONE LINE TO THE PROPOSED WATER VALVE WHITE WELL BRODGED WATER WATER WETER W |  | workmanship being in compliance with lawful requirements. If not bonded or permitted (if applicable) within five (5) years of the authorized date or lawfully extended, this authorization   |
| E. Setting curb and gutter forms.  F. Placing curb and gutter.  | EXISTING STORM SEWER  EX. 15" RCP  EX. 15" RCP  EXISTING REDUCER  EXISTING REDUCER  EXISTING REDUCER   | PROJECT AREA   | will expire. A valid agreement and bond with Prince William County must be maintained to assure plan and permit validity.  |
| G. Placing other concrete. H. Placing gravel base.  | PROPOSED STORM SEWER PROPOSED REDUCER PROPOSED REDUCER   |  |  |
| I. Placing any bituminous surfacing.  *J. Installing water mains <u>outside</u> the Service Authority's boundaries.   | EXISTING SANITARY SEWER  STOP SIGN  HANDICAP RAMP (CG-12)  | BALLS FORD RD  | Sheet List Table   |
| *K. Installing sanitary sewer <u>outside</u> the Service Authority's boundaries.  | PROPOSED SANITARY SEWER  DENOTES LOCATION OF STD VDOT  CG-12 AND/OR JURISDICTIONAL   |  | Sheet Number Sheet Title cooo PWC COVER SHEET  |
| 5. Measures to control erosion and siltation, including detention ponds serving as silt basins during construction, must be provided prior to issuance of the site development permit. The approval of these plans in no way relieves the developer or his agent of the responsibilities contained in the Virginia Erosion and sediment Control Handbook.   | EXISTING ELECTRIC SERVICE  PROPOSED ELECTRIC SERVICE  E  E  STANDARD RAMP CONSTRUCTION  PARKING INDICATOR INDICATES THE NUMBER OF TYPICAL PARKING SPACES   |  | C100 GENERAL NOTES AND DETAILS C101 GENERAL NOTES AND DETAILS C102 GENERAL NOTES AND DETAILS C200 ADJACENT OWNERS  |
| 6. A permit must be obtained from the Office of the Resident Engineer, Virginia Department of Transportation (VDOT) Prince William County, prior to construction in existing State right—of—way, 707—366—1900.  | EXISTING GAS LINE  |  | C200 SUSTING CONDITIONS & DEMOLITION PLAN C202 EXISTING EASEMENT PLAN  |
| 7. Approval of this plan does not guarantee issuance of an entrance permit by VDOT when such permit is required under State law.  | SLOPES TO BE SEEDED, MULCHED & TACKED PURSUANT TO SECTION 1100.00 PRINCE WILLIAM   |  | C203 PROPOSED EASEMENT PLAN C300 E&S PHASE 1   |
| 8. The exact location of all guard rails will be determined by VDOT personnel. "A joint inspection will be held with the Developer, County Representatives, and Representatives, of the Virginia Department of Transportation (VDOT) to determine if and where guard rail and/or paved ditches will be needed. The developer will be responsible for providing guardrail and paved ditches as determined by this joint inspection."  Refer to Virginia Department of Transportation (VDOT) Guard Rail and Paved Ditch Specifications.   | EASEMENT LINE VEHICLES PER DAY COUNT VPD  CENTERLINE PROPOSED BUILDING ENTRANCE  |  | C301 E&S PHASE 2 C302 E&S NOTES AND DETAILS C303 E&S NOTES AND DETAILS C304 E&S NOTES AND DETAILS C305 POLLUTION PREVENTION PLAN   |
| 9. An approved set of plans and all applicable permits must be available at the construction site. Also, a representative of the developer must   | LIMITS OF CLEARING AND GRADING  EXISTING STREET LIGHT  →  12.0  EXISTING STREET LIGHT  |  | C306 SOILS IDENTIFICATION MAP C307 BORING LOGS   |
| be available at all times.  10. Warning signs, markers, barricades or flagmen should be in accordance with the Manual on Uniform Traffic Control Devices (MUTCD).   | PROPOSED STREET LIGHT  + PROPOSED STREET LIGHT   | SOILS MAP  | C308 BORING LOGS C309 GEOTECHNICAL INVESTIGATION   |
| 11. All unsuitable material shall be removed from the construction limits of the roadway before placing embankment.   | PROPOSED SPOT ELEVATION  PROPOSED STREET NAME SIGN  EXISTING TREE DRIP LINE  PROPOSED SANITARY LATERAL CLEANOUT  | SUILS MAT  | C400 SITE LAYOUT PLAN C401 FIRE LANE & MARKING PLAN C402 SIGHT DISTANCE  |
| 12. All pavement sections on the approved plans are based on a minimum CBR value of 10. CBR tests are to be performed by the engineer and submitted to the Prince William County Planning Office for review prior to placement of base material. CBR values less than 10 will require submittal of revised pavement section.  | EXISTING TREE  EXISTING TREE  EXIST OAK  SANITARY MANHOLE INDENTIFIER  12  | NOTE: DUE TO THE SEVERE ERODIBILITY AND PROBLEM SOILS PRESENT ON THIS SITE, A GEOTECHNICAL ENGINEER SHALL EXAMINE THE SITE AND PROVIDE RECOMMENDATIONS FOR THE PROPOSED CONSTRUCTION.  | C500 UTILITY PLAN C501 WATERLINE & PROFILE DETAILS C502 SANITARY SEWER PROFILE & DETAILS   |
| 13. All roadside ditches at grades of more than 5% shall be paved with cement concrete to the limits indicated on the plans and as required at the field inspection.  | PROPOSED TREE  STORM DRAIN STRUCTURE IDENTIFIER  12  | TOTAL TITLE THOU OSED CONSTRUCTION.  | C503 PWCSA INFORMATION SHEET C504 PWCSA INSPECTOR SHEET C600 GRADING PLAN C601 DETAILED GRADING PLAN   |
| 14. All springs shall be capped and piped to the nearest storm sewer manholes or curb inlet. The pipe shall be minimum 6" diameter and conform to VDOT standard SB—1.   | SURVEY AND TOPOGRAPHIC INFORMATION   |  | C602 STORM SEWER PROFILE C603 STORM SEWER COMPUTATIONS C604 STORM SEWER DETAILS  |
| <ul><li>15. All standard street name signs, traffic control devices, and street lights shall be installed by the developer when the first building unit is occupied.</li><li>16. Construction debris shall be containerized in accordance with the Virginia Litter Control Act; no less than one litter receptacle shall be provided at the construction site</li></ul>   | Horizontal and vertical control surveys were performed     by <u>. TIMMONS GROUP</u> in <u>. NAD83</u> All elevations must be referenced to the National Geodetic  | 31B  | C605 STORM SEWER DETAILS C606 STORM SEWER DETAILS C607 STORM SEWER DETAILS C608 DITCH COMPUTATIONS   |
| 17. The contractor shall provide adequate means of cleaning mud from trucks and/or other equipment prior to entering public streets, and it is the contractors responsibility to clean streets, allay dust, and to take whatever measures are necessary to insure that the streets are maintained in a clean, mud and dust free condition at all times.   | Vertical Datum of 1929 (NGVD 29).<br>3. Source of topographic mapping is <u>. TIMMONS GROUP</u> .<br>dated <u>. JANUARY 2018</u> .   | 31B 31B  | C609         DITCH COMPUTATIONS           C700         BMP AREA MAP           C701         SWM COMPUTATIONS           C702         SWM COMPUTATIONS  |
| 18. * Notification shall be given to the appropriate utility Company (Service Authority, Virginia—American Water Company, or Dale Service Corporation) prior to construction of water and/or sanitary sewer lines. Information should also be obtained from the appropriate authority concerning permits, cut sheets, and connections to existing lines.  | <ul> <li>4. Boundary survey was performed by . TIMMONS GROUP . dated . JANUARY 2018</li> <li>5. The application of the professional's seal and signature as required by Section 1.14 of the STATE BOARD</li> </ul>   | 26A 33C 33C  | C703 CHANNEL & FLOOD PROTECTION ANALYSIS C704 CHANNEL & FLOOD PROTECTION COMPUTATIONS C705 STORMWATER MANAGEMENT COMPUTATIONS C706 STORMWATER MANAGEMENT COMPUTATIONS C707 STORMWATER MANAGEMENT NOTES   |
| 19. All sanitary sewers and water mains and appurtenances shall be constructed in accordance with the current standards and specifications of Prince William County and/or the Service Authority.   | OF ARCHITECTS, PROFESSIONAL ENGINEERS, LAND SURVEYORS AND CERTIFIED LANDSCAPE ARCHITECTS RULES AND REGULATIONS shall be evidence that: the boundary data is correct to the best of the land surveyor's knowledge, and complies with the minimum standards and procedures of the said Board; the topograhic   | 13B EN 31C   | C707 STORMMATER MANAGEMENT NOTES  C708 OVERALL DRAINAGE AREA COMPUTATIONS  C709 OVERALL SWM COMPUTATIONS  C710 EXISTING SEDIMENT BASIN COMPUTATIONS  |
| 20. The developer and/or contractor shall be responsible to supply all utility companies with copies of plans that have been approved by Prince William County and advising them that all grading shall conform to the approved plans, and further that the utility companies shall be responsible for honoring these plans and the finished grades in the installation of their utility lines.   | information is accurate to within one—half of the contour interval, as shown. Application of the seal and signature indicates acceptance of responsibility for the work shown hereon.  | BALLS FORD RD  TABLE  TO THE STATE OF THE ST | C711 OVERALL SWM COMPUTATIONS C712 STORMWATER MANAGEMENT POND10—YEAR STORM COMPUTATIONS C713 STORMWATER MANAGEMENT POND100—YEAR STORM COMPUTATIONS   |
| 21. Contractors shall notify operators who maintain underground utility lines in the area of proposed excavating or blasting at least two (2) working days, but not more than ten (10) working days, prior to commencement of excavation or demolition. Names and telephone numbers of theoperators underground utility lines in Prince William County appear below. These numbers shall also be used to serve in an  | PRINCE WILLIAM COUNTY SANITATION AUTHORITY   | NOTES NOTES  | C800 UNIT PRICE LIST L100 LANDSCAPE PLAN L200 LANDSCAPE DETAILS L201 LANDSCAPE DETAILS   |
| emergency condition.  Washington Gas Light Co.  | 1. THIS PLAN COMPLIES WITH THE NEW PRINCE WILLIAM COUNTY SERVICE AUTHORITY UTILITY STANDARDS MANUAL, WHICH WENT INTO EFFECT ON FEBRUARY 1, 2017. ALL UTILITY PERMITS ISSUED AFTER THIS DATE MUST COMPLY WITH THE CONSTRUCTION CRITERIA IN THE NEW MANUAL, INCLUDING ANY REVISIONS WHICH HAVE BEEN ISSUED.  | MW AS S  | E0-01A SITE PHOTOMETRIC PLAN R200 TRAFFIC SIGNAL SUMMARY OF QUANTITIES R300 TRAFFIC SIGNAL PLAN R301 TRAFFIC SIGNAL PLAN FUTURE WIDENING   |
| Virginia Power Co.  Northern Virginia Electric Co-op Columbia Gas of Virginia Continental Telephone of VA  Service Authority  (After hours-Emergency 335-7990) Virginia—American Water  703-491-2136  | BMP CREDIT   | SOILS INFORMATION WAS OBTAINED FROM THE "SOIL SURVEY OF PRINCE WILLIAM COUNTY, VIRGINIA" ISSUED AUGUST 1989.   | 58 TOTAL SHEETS  |
| Continental Telephone of VA  Colonial Pipeline Co.  Transcontinental Gas Pipe Line Corp.  Dale Service Corporation  703-494-4161  | 1. APPLICANT SHALL PROVIDE A PROOF OF PURCHASE OF THE OFFSITE NUTRIENT CREDITS (FROM THE NONPOINT SOURCE CREDIT BANKS APPROVED BY THE DEQ) IN THE FORM OF PURCHASE AND SALE AGREEMENT PRIOR TO APPLYING FOR THE LAND   | SCALE 1"=400'  | DEVIOLONIO   |
| 22. The service Authority requires that a clean—out be placed within one foot (0.3 meters) of the property line.  | DISTURBANCE PERMIT OR THE CONSTRUCTION GENERAL PERMIT, WHICHEVER COMES FIRST.  | SOILS DATA   | REVISIONS  |
| 23. The location of existing utilities shown in these plans are taken from existing records. It shall be the contractors responsibility to verify the exact horizontal and vertical location of all existing utilities as needed prior to construction. The contractor shall inform the engineer of any   |  | UNIT MAPPING POTENTIAL SLOPE UNIT NAME PERMEABILITY ERODIBILITY REPORT RUNOFF FLOODING GENERALLY K  31B D 2-7% JACKLAND - SURFACE - MODERATE; SUBSOIL - VERY SLOW; SUBSTRATUM - MODERATE  SUBSTRATUM - MODERATE MODERATE  WATER CAPACITY RUNOFF FLOODING GENERALLY K  K  MODERATE MODERATE SLOW TO MEDIUM NONE GREATER THAN 5'   | DATE DESIGNER NO. DESCRIPTION  |
| conflicts arising from his existing utility verification and the proposed construction.  24. The developer will be responsible for any damage to the existing streets and utilities which occurs as a result of his construction project within or contiguous to the existing right—of—way.   |  | 31C D 7-15% JACKLAND - SURFACE - MODERATE; HAYMAKET SUBSOIL - WODERATE MODERATE MEDIUM NONE GREATER 0-0.5 THAN 5'  | 07/31/18   |
| 25. All utilities placed under existing streets shall be bored or jacked.  26. When grading is proposed within easements of utilities, letters of permission from all involved companies must be provided to Prince William   |  | 38B B 0-5% MEADOWVILLE LOAM SURFACE - MODERATELY RAPID; SUBSOIL - MODERATE TO MODERATE SLOW TO MEDIUM SLIGHT TO MEDIUM NONE GREATER THAN 5' 0-0.00 TO MODERATE TO  |  |
| County Planning Office prior to issuance of grading and/or site development permits.  27. The developer will be responsible for the relocation of any utilities which is required as a result of his project. The relocation should be done   |  | — MODERATELÝ RAPID THAN 5'   |  |
| prior to construction.  28. Before burning, blasting, transportation or storage of explosives in Prince William County, a permit shall be obtained from the Fire Marshal's  | DESIGNATED PLANS EXAMINER CERTIFICATE  |  |  |
| Office, 792-6360.  29. Fire and Rescue Services must be notified immediately (703-792-6810) in the event that unusual items such as tanks, cylinders, unidentified containers, etc. which could contain potentially hazardous materials are discovered or observed. All activities must cease and not be  | 1ST SUBMISSION REVIEWED AND RECOMMENDED FOR SUBMISSION   |  | PRINCE WILLIAM COUNTY  |
| resumed until authorization to proceed is given by the Fire Marshal's Office.  30. Sidewalk underdrains shall be installed per Section 650.65 of the Design and Construction Standards Manual.  | DESIGNATED PLANS EXAMINER REG. NUMBER DATE   |  | COVER SHEET  |
| 31. All walkways outside of the right—of—way limits will be maintained by the homeowners association.   | 2ND SUBMISSION REVIEWED AND RECOMMENDED FOR SUBMISSION   | PROJECT NAME: PRINCE WILLIAM COUNTY FIRE STA   | TIMMONS GROUP NO.: 41050   |
| 32. Maintenance of the Storm Drainage or Storm Water Management facilities located therein shall be pursuant to Section 700 of the Prince William County Design and Construction Standards Manual.  |  | SUBDIVISION or SITE PLAN NAME:   | MARKET NAME: PLAN NUMBER: SPR2019-00035S02   |
| 33. If units shown on this plan will be occupied in phases, a phasing plan must be approved by the engineering inspection branch prior to the issuance of any occupancy permits. (Detached single family subdivision exempt.)   | DESIGNATED PLANS EXAMINER REG. NUMBER DATE   | PRINCE WILLIAM COUNTY FIRE STA   | TION 22   plan type: site plan present zoning & use: date of plan: (mm/dd/yyyy)  |
| 34. These plans identify the location of all known gravesites. Gravesites shown on this plan will be protected in accordance with state law.  In the event gravesites are discovered during construction, the County's Archaeologist must be notified immediately (792—6830). All activities  | BOND ESTIMATE  | GAINESVILLE  | M-1 - VACANT 07/31/2018  NER ADDRESS: OWNER PHONE#: OWNER FAX#:  |
| must cease and not be resumed until authorization to proceed is given by the County Archaeologist.  35. Roof top mechanical equipment, if any, must be enclosed within a wall or similar screening barrier, designed in harmony with the building.  | PERFOMANCE BOND: LANDSCAPE ESCROWS:  |  | OUNTY COMPLEX CT WOODBRIDGE, VA 22192 (703) 791-7308   |
| 36. Individual sign permits will be required from the Zoning Office for all free standing and facade signs prior to erecting the signs.   | TOTAL CONSTRUCTION COST: \$667,425 TOTAL COST: \$41,240  |  | ELOPER ADDRESS:  DEVELOPER PHONE#:  DEVELOPER FAX#:  |
| 37. All buffer areas shall be screened according to the Design and Construction Standards Manual.   | A. ADMINSTRATIVE COST- 10% OF TOTAL SILTATION AND EROSION ESCROWS:   | THESE PLANS ARE IN   | MONS GROUP 20110 ASHBROOK PLACE, SUITE 100 ASHBURN, VA. 20147  |
| 38. For proffer statements and proffer analyses, see project booklet.  39. For waivers see sheet(s) <u>L200</u> .   | \$50,000: <b>\$50,000</b> TOTAL COST: <b>\$147,005</b>   | WILLIAM COUNTY STANDARDS AND ORDINANCES. ANY DEVIATION OR ARCHITECT OR SURVEYOR CERTIFYING PLAN:   |  |
| 40. Anticipated sewage flows:   | COMPOUNDED ANNUALLY AT 3.0% PER YEAR OF THE TOTAL CONSTRUCTION COST: \$20,023  ADMIN 10%: \$14,700   | CHANGE IN THESE PLANS SHALL PARCEL INDENTIFICATION NUMBERS: GPIN 7597-63-03  BE APPROVED BY THE DIRECTOR  TOTAL AREA ORGAN AREA F. 52, AGRES   |  |
| 41. Anticipated fire flows: BALLS FORD ROAD EAST FLOW AT 20 PSI=3482 GPM, BALLS FOR ROAD WEST FLOW AT 20 PSI=2838 GPM  42. Distance to nearest existing school or proposed school site: 0.83 MILES  | TOTAL PERFORMANCE BOND: \$787,448  TOTAL SILTATION AND EROSION ESCROW AMOUNT: \$161,705  | OF PLANNING PRIOR TO CONSTRUCTION.  IOTAL AREA: 9.8626 ACRES PROJECT AREA: 5.52 ACRES  RELATED PLANS TRACKING NUMBERS (Including Rez. &  | DISTURBED AREA: 5.52 ACRES IMPERVIOUS AREA: 2.22 ACRES BMP STORAGE: 24,342 CF S.U.P.): 14-00340  |
| 42. Distunce to neurest existing school or proposed school site:  | ECONOVI AMOUNT. #101,703   | FN-SPC   |  |
|   |  |  | Revised: June 1997 SHEET 1 OF 58   |


LEGEND


VICINITY MAP


1" = 2000'











#### **December 4, 2018**

**TO:** Bryce Barrett, Planner

Department of Planning

Thru; Lou Ann Dorrier, County Architect

Department of Public Works

**FROM:** Thomas Bruun, Director

Department of Public Works

**RE:** Public Facility Review #PFR2019-00005, Fire Station 22 – Letter of Commitment

**Gainesville Magisterial District** 

The Prince William County Department of Public Works is requesting a Public Facility Review (PFR) under §15.2-2232 Code of Virginia to allow for the construction of a 20,053 Square Foot Fire Station with up to four apparatus bays located at 7500 Century Park Drive. The site is identified on County Maps as GPIN: 7597-63-0358. The following commitments are intended to offset some of the impacts of the proposal and to generally render the application more consistent with the Comprehensive Plan and comments received at the November 16, 2018 Post-Submission meeting.

#### Site design

- 1. Public Works commits to develop the property in substantial compliance with the plan entitled "Prince William County Fire Station 22" dated July 31, 2018 and revised on December 3, 2018 (the "Plan").
- 2. The limits of disturbance will be as shown on the Plan and subject to minor modifications in connection with final site plan review or final engineering.
- 3. The maximum impervious surface resulting from the facility construction will be approximately as shown on the Plan. Compliance will be shown on final site plan.

#### Police

- 4. The site lighting will maintain an average of 2.0 foot candles in parking and pedestrian areas
- 5. All other applicable zoning requirements for height and illumination levels on site will be met and considerations made to utilize Crime Prevention through Environmental Design (CPTED) best practices at time of site plan review.

#### Water and Sewer

6. Public Works commits to design and construct all on-site and off-site water and sanitary sewer utility improvements necessary to develop the subject property in accordance with the Service Authority's USM, and County and State requirements, standards and

regulations at time of site plan review.

#### **Transportation**

- 7. Public Works commits to coordinate with the lead engineering firm Rinker Design Associates, P.C. to reflect the approved **Balls Ford Road Widening** plans and the lead engineering firm for the **Transform I-66 Outside the Beltway** project regarding the right-or-way for all construction related easements and road construction
- 8. Public Works commits to providing pedestrian connection from the entrance of the fire station to the trail proposed along Balls Ford Road project as shown on the plan and subject to minor modifications in connection with final site plan review or final engineering.
- 9. Public Works commits to providing directional signage to ensure the emergency vehicle egress on Balls Ford is not utilized as an entrance. Compliance will be shown on final site plan.

#### Watershed

- 10. Public Works commits to minimize conflicts with existing utilities and easements with landscaping buffers. Compliance will be shown on final site plan.
- 11. The Northern portion of the Property will remain undisturbed in lieu of required buffers.
- 12. The required landscape strips along Balls Ford Road and Century Park Drive will be installed after completion of the **Balls Ford Road Widening** and **Transform I-66 Outside the Beltway** road improvements. Such landscape strip shall be on the subject property and outside the required utility easements parallel to the roads. Compliance will be shown on final site plan.



#### **COUNTY OF PRINCE WILLIAM**

5 County Complex Court, Suite 210 Prince William, Virginia 22192-9201 (703) 792-7615 FAX (703) 792-4401 www.pwcgov.org/planning PLANNING OFFICE

## **Application Package**

for Public Facility Review (PFR)

### **Contents**

| Instructions  | 2 |
|---|---|
| Application for a Public Facility Review                  |   |
| Application for Deferral of Traffic Impact Analysis (TIA) | 5 |
| Cultural Resources Assessment and Record Check            | 6 |

#### **INSTRUCTIONS**

Before submission of a Public Facility Review (PFR) application please complete a Public Facility Determination Request Form in order to determine if a PFR application is required. Form Link

All applicable items contained in this application package must be completed and submitted. Additional information may be requested during the quality control review.

Please attach additional pages where necessary to identify all requested information clearly.

#### **Submission Requirements**

#### I. Completed PFR Application

- PFR Fee in accordance with the current <u>Fee Schedule</u>. Checks should be made payable to "Prince William County".
- Application for a Public Facility Review Page 4
  - Fill in the case name.
  - Identify the public facility.
  - List all affected parcels by GPIN and indicate the zoning and acreage of each parcel.
  - Describe the location of the property.
  - Give names of the property owner(s), authorized agent(s), applicant, and engineer. Please check the box next to the contact person to whom correspondence on the application should be sent.
  - Sign the application.
- Application for Deferral of Traffic Impact Analysis (TIA) Page 5
- Cultural Resources Assessment and Record Check Page 6

#### II. The following copies and types of plans:

- a. 25 folded copies Large plans to accurately depict the layout, up to 24" x 36" (11" x 17" preferred).
- b. 1 copy Reduced (8.5" x 11") plan.
- c. A scale of no less than 1"=200'
- d. Contour interval no greater than 5'
- e. Date of plan, north arrow match lines, and sheet numbers.
- f. Vicinity map, preferably at 1"=2,000'

- g. Present zoning (including Overlay Districts) of the project parcel(s) and all adjacent parcels, along with their present use. Provide the project name and plan number of adjacent development as assigned by Prince William County, if applicable.
- h. The project parcel(s) GPIN and all adjacent parcels' GPINs.
- i. Total project site acreage
- j. Generalized proposed structures and/or buildings including number and size, street access layout, offstreet parking, recreation areas, open space, improvements to existing street and right-of-way, buffers, vehicles per day, and stormwater management facilities.
- k. Existing easements, covenants, and any other restriction shown.
- 1. Existing drainage facilities, including major culverts, ponds, and streams.
- m. Location of all existing improvements and buildings on site.
- n. Electronic version of plans in Adobe pdf format (submitted on a CD).
- o. Location of existing vegetation and approximate grading and clearing limits.

#### III. On a case-by-case basis, staff may request additional information to analyze the application.

For further information please call the Planning Office at 703-792-7615 or email your question to planning@pwcgov.org.

## APPLICATION FOR A PUBLIC FACILITY REVIEW TO THE PLANNING COMMISSION OF PRINCE WILLIAM COUNTY, VIRGINIA

| G.P.I.N.   | Zoning Acres   |
|--|--|
| from an intersection of two (2) public roads or str  | e property by distance, in feet or portion of a mile, and direct<br>reets.)  |
| The name(s), mailing address(es), and telephone rengineer(s) as applicable are (attach additional page   | ,  |
| Owner of Property  | <u>Authorized Agent(s)</u>   |
| Name:  |  |
| Mailing Address:   |  |
| City/State/Zip:  |  |
| D)   | Phone:   |
|  |  |
|  |  |
|  | Email:Engineer   |
| Email: Contract Purchaser/Lessee   | Email: <u>Engineer</u>   |
| Contract Purchaser/Lessee  Name:   | Email:  Engineer  Name:  |
| Email:  Contract Purchaser/Lessee  Name:  Mailing Address:   | Email:  Engineer  Name:  |
| Contract Purchaser/Lessee           Name:           Mailing Address:           City/State/Zip  | Email:   |
| Email:  Contract Purchaser/Lessee  Name:  Mailing Address:  City/State/Zip  Phone:   | Email:  Engineer  Name:  Mailing Address:  City/State/Zip  |
| Email:  Contract Purchaser/Lessee  Name:  Mailing Address:  City/State/Zip  Phone:  Email:   | Email:  Engineer  Name:  Mailing Address:  City/State/Zip Phone:   |
| Name:  Mailing Address:  City/State/Zip  Phone:  Email:  *Please check the box next to the  I have read this application, understand its intent, | Email:  Engineer  Name:  Mailing Address:  City/State/Zip  Phone:  Email:  contact to which correspondence should be sent.  and freely consent to its filing. Furthermore, I have the power william County officials and other authorized government |

### **APPLICATION FOR DEFERRAL OF TRAFFIC IMPACT ANALYSIS (TIA)**

(To be completed with assistance from PWC Transportation Department) www.pwcgov.org/Transportation or (703)792-6825

| 10 be com  | pleted by   | applicant:   |   |   |   |   |   |  |
|--|---|--|---|---|---|---|---|--|
| Applicant 1  | Name:   |  |   |   |   | Phone:  |   |  |
| Proposed U   | Jse:  |  |   |   |   |   |   |  |
| Address:   |   |  |   |   |   | Lot Size:_  |   |  |
| Please mar   | k: R  | ezoning  | Special Use   | Permit C  | Other:  |   |   |  |
| TO DE COMDIETEG DY ADDITCANT:                                    |   |  |   | _   | d by PWC Transportation epartment:                          |   |   |  |
| Tract/Use Area Zoning Land Use                                   |   |  | ITE Code  | (ITE Latest<br>Edition<br>Trip Rate)  | Trips/24<br>Hours   | Trips/AM<br>Peak  | Trips/PM<br>Peak  |  |
|  |   |  |   |   |   |   |   |  |
|  |   |  |   |   |   |   |   |  |
|  |   |  |   |   |   |   |   |  |
|  |   |  | 1200 Daily Tr   | ing or 100 Po   | Total   | Yes   |   |  |
|  |   |  | 1200 Daily 11   | ips of 100 re   | ak Hour Trips   | No  |   |  |
|  |   |  | FOI   | OFFICE  | USE ONLY  |   |   |  |
| preparing trequirement whether a A TIA is not exceed the (DCSM). | the analysis of the 527 review of trequired threshold However, review pw may be | s must meet analysis before w is required d to be submels established a TIA may brocess if site e required | ormation disks) with the PWC ore beginning the distance well as the nitted at this tir din §602.01 of whe required ubsequent de | is required to C Department on analysis. Act applicable feeme. The traffic the Prince Willater in the etails warran | be submitted wit<br>of Transportation<br>ditionally, at the | and VDOT<br>scoping sess<br>e proposed c<br>sign and Cor<br>cial use per<br>pplicant sh | to discuss the sion, VDOT value levelopment distruction Star mit processiould also be | e scope and<br>vill determine<br>loes not appe<br>ndards Manua<br>or during to<br>e aware that |
|  | n waived l  | by the Direc   | tor for the follo   | owing reasons:  |   |   | <del></del>   |  |
|  |   |  |   |   |   |   |   |  |
| TIA has been   | print nam   |  |   |   |   |   |   |  |

# Cultural Resources Assessment and Record Check for Pending Development Applications

This is a desk review of the project and is subject to change if additional information becomes available.

Contact the Planning Office at 703-792-7615 or <a href="mailto:planning@pwcgov.org">planning@pwcgov.org</a> for more information.

|   | nt Name:   |   | •   |
|---|--|---|---|
| L'OXZ # •                                 |  |   |   |
|   | Email:<br>nspection Findings:  |   |   |
| v isuai 11                                | ispection Findings.  |   |   |
|   |  |   |   |
|   | Y ARCHAEOLOGIST OFFICIAL USE   |   |   |
| County 1.                                 | Records Check: (Verify reference to site on the following) Prince William County Cultural Resources Map (GIS)  | Vac   | No  |
| 2.  | 1820 Prince William County Map (Wood)  | Yes   | No  |
| 3.  | 1901 Prince William County Map (Brown)   | Yes   | No  |
| 3.<br>4.                                  | 1904 Army Maneuvers Map  | Yes   | No  |
| 5.  | 1915-1927 USGS 15 Minute Quad Maps   | Yes<br>Yes  | No  |
| 6.  | 1933 Virginia Highway Map  | Yes   |   |
| 7.  | Eugene Scheel's Historic Prince William Map  | Yes   |   |
| 8.  | Eugene Scheel's African American Heritage Map  | Yes   |   |
| 9.  | County Register of Historic Sites (CRHS)   | Yes   | No  |
| 10.                                       | High Sensitivity Areas – Historic Sites Map  | Yes   | No  |
| 11.                                       | High Sensitivity Areas – Prehistoric Sites Map   | Yes   | No  |
| 12.                                       | The Official Military Atlas of the Civil War   | Yes   | No  |
| 13.                                       | Civil War Map from the Library of Congress   | Yes   | No  |
| 14.                                       | American Battlefield Protection Program Maps   | Yes   | No  |
| 15.                                       | Map of Fairfax, Loudoun, & Prince William Counties   | Yes   | No  |
| 16.                                       | USGS Topographic Maps  | Yes   |   |
| 17.                                       | Other  |   |   |
| C   | CRHS or a Prehistoric or Historic High Sensitivity Area is cultural Resources Survey* must be submitted with Rezoning  | and Special   |   |
|   | ections 32-700.20(9) and 32-700.50(3)(a) of the Zoning Ordi  | nance.  |   |
| 30  | nere is a medium to high potential for finding archaeological  | sites and or  | historic structures on the projec   |
| T   | ea, therefore, a Phase I Cultural Resources Survey* must be ermit applications per Sections 32-700.20(9) and 32-700.50(3)  |   | ith Rezoning and Special Use  |
| T<br>ar<br>Pe                             | ea, therefore, a Phase I Cultural Resources Survey* must be  | 3)(a) of the Z  | ith Rezoning and Special Use Coning Ordinance.  |
| TI<br>ar<br>Pe<br>N<br>Fi                 | ea, therefore, a Phase I Cultural Resources Survey* must be ermit applications per Sections 32-700.20(9) and 32-700.50(  | 3)(a) of the Z<br>the project a<br>is not warran                  | ith Rezoning and Special Use Coning Ordinance.  rea.  Ited due to ground disturbance of               |
| Ti<br>ar<br>Pe<br>N<br>Fi<br>re           | ea, therefore, a Phase I Cultural Resources Survey* must be ermit applications per Sections 32-700.20(9) and 32-700.50(3) or archaeological and historic sites or graves are recorded on arther cultural resource review by the County Archaeologist   | 3)(a) of the Z<br>the project a<br>is not warran<br>rce survey re | ith Rezoning and Special Use Coning Ordinance.  rea.  Ited due to ground disturbance of ports.        |
| Ti<br>ar<br>Pe<br>N<br>Fi<br>re           | ea, therefore, a Phase I Cultural Resources Survey* must be ermit applications per Sections 32-700.20(9) and 32-700.50(3) or archaeological and historic sites or graves are recorded on arther cultural resource review by the County Archaeologist commendations of no further work from prior cultural resources: | 3)(a) of the Z<br>the project a<br>is not warran<br>ree survey re | ith Rezoning and Special Use coning Ordinance.  rea.  Ited due to ground disturbance oports.          |
| Ti<br>ar<br>Pe<br>N<br>Fi<br>re           | ea, therefore, a Phase I Cultural Resources Survey* must be ermit applications per Sections 32-700.20(9) and 32-700.50(3) or archaeological and historic sites or graves are recorded on arther cultural resource review by the County Archaeologist commendations of no further work from prior cultural resource.  | 3)(a) of the Z<br>the project a<br>is not warran<br>rce survey re | ith Rezoning and Special Use Coning Ordinance.  rea.  Ited due to ground disturbance of ports.        |
| Ti<br>ar<br>Pe<br>N<br>Fi<br>re<br>Commen | ea, therefore, a Phase I Cultural Resources Survey* must be ermit applications per Sections 32-700.20(9) and 32-700.50(3) or archaeological and historic sites or graves are recorded on arther cultural resource review by the County Archaeologist commendations of no further work from prior cultural resources: | 3)(a) of the Z<br>the project a<br>is not warran<br>rce survey re | ith Rezoning and Special Use Coning Ordinance.  rea.  Ited due to ground disturbance of ports.  Date: |

| Con           | ditions as not | ed during FCM p              | artial v | valk-through of floor 2, 2018-03-29  |                       |                             |        |       |         |
|---------------|----------------|------------------------------|----------|--|-----------------------|-----------------------------|--------|-------|---------|
| Item          | n Date         | Bldg Area                    | Rm#      | E Description  | Resp                  | Comments/date               |        | Signo | ff/date |
| 1             | 3/15/2018      | Vestibule                    | 100      | Crash doors near icemaker  |                       | Needs panic hardware/RG     | 26-Mar |       |         |
| 2             | 12/15/2017     | Vestibule                    | 100      | Columns need to be prepped/painted   | Paintworx             | Completed                   |        | FCM   | 26-Mar  |
| 3             | 12/12/2017     | Vestibule                    | 100      | Floor needs to be re-surfaced - there are flaws                                    | <del>Ddickerson</del> | Item stricken/RG            |        | FCM   | 26-Mar  |
| 4             | 12/12/2017     | Vestibule                    | 100      | Storefront frame needs to be repainted   | Design Glazing        | Needs touchup/RG            | 26-Mar |       |         |
| 5             | 3/15/2018      | Break room                   | 101      | Need caulking between curtain wall and linoleum                                    |                       | Noted                       | 26-Mar |       |         |
| 6             | 12/15/2017     | Break room                   | 101      | Window frame to vestibule paint is incomplete                                      | Design Glazing        | Completed                   |        | FCM   | 26-Mar  |
| 7             | 12/12/2017     | Break room                   | 101      | Columns need to be prepped/painted   | Paintworx             |                             |        |       |         |
| 8             | 12/12/2017     | Break room                   | 101      | Scratches on counter surfaces need to be sanded/polished                           | DES                   | Stainless steel counters    | 26-Mar |       |         |
| 9             | 3/15/2018      | Corridor                     | 103      | Column near stairs on LL south needs painting                                      | Paintworx             | Vinyl base in lieu of paint | 26-Mar |       |         |
| 10            | 3/15/2018      | Corridor                     | 103      | Terrazzo base on column outside Data<br>Room #112                                  |                       | Noted                       | 26-Mar |       |         |
| 11            | 12/15/2017     | Corridor                     | 103      | Column needs scuffmaster paint at bottom, stopped early                            | Paintworx             | See item #9                 |        | FCM   | 26-Mar  |
| <del>12</del> | 12/15/2017     | Corridor                     | 103      | Columns need to be prepped/painted   | Paintworx             | See item #9                 |        | FCM   | 26-Mar  |
| 13            | 3/15/2018      | Fitness                      | 104      | <del>OK</del>  |                       | See item #14                | 26-Mar |       |         |
| 14            | 12/12/2017     | Fitness                      | 104      | Water fountain spout replaced/cleaned, paint residue                               | Cmaster               | Noted                       | 26-Mar |       |         |
| 15            | 3/15/2018      | Fitness storage              | 105      | OK   |                       |                             |        | FCM   | 15-Mar  |
| 16            | 3/15/2018      | Vestibule<br>women's locker  | 106      | OK   |                       |                             |        | FCM   | 15-Mar  |
| 17            | 3/15/2018      | First Aid,<br>women's locker | 107      | OK   |                       | Refrigerator moved in       | 26-Mar | FCM   | 15-Mar  |
| 18            | 3/15/2018      | Women's locker               | 108      | Small refrigerator to be moved here  |                       | Completed                   |        | FCM   | 26-Mar  |
| 19            | 3/15/2018      | Women's locker               | 108      | Transition for threshold from hallway  |                       | Noted                       | 26-Mar |       |         |
| 20            | 1/3/2018       | Women's shower               | 109      | Grab bar installed in wrong location; replace damaged wall tile above shower seat. | I-Tiles               | Completed                   |        | FCM   | 26-Mar  |

| Con           | ditions as not | ted during FCM p        | artial v       | valk-through of floor 2, 2018-03-29   |                 |   |        |       |         |
|---------------|----------------|-------------------------|----------------|---|-----------------|---|--------|-------|---------|
| Item          | Date           | Bldg Area               | Rm#            | Description   | Resp            | Comments/date                                 |        | Signo | ff/date |
| 21            | 1/3/2018       | Women's rm              | 110            | Provide engraved plates at all receptacles  | FLBE            | Plate outside Rm 107                          | 26-Mar |       |         |
| 22            | 3/15/2018      | Elec closet             | 111            | OK  |                 |   |        | FCM   | 15-Mar  |
| 23            | 3/15/2018      | Data Room               | 112            | OK  |                 |   |        | FCM   | 15-Mar  |
| <del>24</del> | 1/3/2018       | <del>Stair 1</del>      | <del>113</del> | Conceal exposed conduit   | <del>FLBE</del> | Item stricken/RG                              |        | FCM   | 26-Mar  |
| 25            | 3/15/2018      | Janitor                 | 114            | Broken hose hanger  |                 | Noted   | 26-Mar |       |         |
| 26            | 3/15/2018      | Janitor                 | 114            | Needs transition strip  |                 | Noted   | 26-Mar |       |         |
| 27            | 3/15/2018      | Men's locker vestibule  | 115            | Needs sign in corridor (number & function)  |                 | Completed                                     |        | FCM   | 26-Mar  |
| 28            | 3/15/2018      | Men's locker            | 116            | Caulk on lockers 24, 54-55, 88  |                 | Noted   | 26-Mar |       |         |
| 29            | 3/15/2018      | Men's locker            | 116            | Lockers 50-51 have dings in metal   |                 | Noted   | 26-Mar |       |         |
| 30            | 1/3/2018       | Men's locker            | 116            | Current status of power strip<br>configuration and locker remains open;<br>mockup is not followed; appears to be<br>some issue with concealment of electrical<br>cord wire and placement of plug to<br>electrical outlet and their location |                 | Install quads on each locker (parts on order) | 26-Mar |       |         |
| 31            | 3/15/2018      | First Aid, men's locker | 117            | OK  |                 |   |        | FCM   | 15-Mar  |
| 32            | 3/15/2018      | First Aid, men's locker | 118            | OK  |                 |   |        | FCM   | 15-Mar  |
| 33            | 3/15/2018      | First Aid, men's locker | 119            | OK  |                 |   |        | FCM   | 15-Mar  |
| 34            | 1/3/2018       | Men's toilet            | 120            | Label access doors  | Acme            | Noted   | 26-Mar |       |         |
| 35            | 1/3/2018       | Men's toilet            | 120            | Provide engraved plates at all receptacles  | FLBE            | Noted   | 26-Mar |       |         |
| 36            | 3/15/2018      | Men's shower            | 121            | OK  |                 |   |        | FCM   | 15-Mar  |
| 37            | 3/15/2018      | Men's toilet            | 122            | OK  |                 |   |        | FCM   | 15-Mar  |
| <del>38</del> | 3/15/2018      | Vestibule               | 123            | Needs sign in corridor (number &  |                 | Item stricken                                 |        | FCM   | 26-Mar  |
| 39            | 3/15/2018      | Roll call room          | 124            | Pressure filler for columns   |                 | Noted   | 26-Mar |       |         |
| 40            | 3/15/2018      | Roll call room          | 124            | Transitions for thresholds  |                 | Noted   | 26-Mar |       |         |
| 41            | 3/15/2018      | Corridor                | 125            | Outside Rms 152-164, paint bottoms (under wainscoting) dark grey  |                 | Completed                                     |        | FCM   | 26-Mar  |
| 42            | 3/15/2018      | Sgts Squad A            | 126            | Damaged squares of carpet need to be replaced   |                 |   |        |       |         |

| Con           | ditions as not | ed during FCM p       | artial w | valk-through of floor 2, 2018-03-29                            |                 |                      |        |       |         |
|---------------|----------------|-----------------------|----------|--|-----------------|----------------------|--------|-------|---------|
| Item          | Date           | Bldg Area             | Rm#      | Description  | Resp            | Comments/date        |        | Signo | ff/date |
| 43            | 3/15/2018      | Sgts Squad A          | 126      | Patch holes in wall near TV                                    |                 |                      |        |       |         |
| 44            | 3/15/2018      | Sgts Squad B          | 127      | Patch holes in wall near TV                                    |                 |                      |        |       |         |
| 45            | 3/15/2018      | Sgts Squad C          | 128      | Patch holes in wall near TV                                    |                 |                      |        |       |         |
| 46            | 1/3/2018       | Sgts Squad C          | 128      | Provide sealant white that matches ceiling                     | K-Plus/Paintwor | rx                   |        |       |         |
|               |                |                       |          | tile around colums, so that it hides the                       |                 |                      |        |       |         |
|               |                |                       |          | split in the tile  |                 |                      |        |       |         |
| 47            | 3/15/2018      | Report writing workrm | 129      | OK   |                 |                      |        | FCM   | 15-Mar  |
| 48            | 3/15/2018      | Report writing        | 130      | OK   |                 |                      |        | FCM   | 15-Mar  |
| 49            | 3/15/2018      | Storage               | 131      | OK   |                 |                      |        | FCM   | 15-Mar  |
| 50            | 3/15/2018      | Sgts Squad D          | 132      | Patch holes in wall near TV                                    |                 |                      |        |       |         |
| <del>51</del> | 12/12/2017     | Sgts Squad D          | 132      | No door stop   | SGC             | Item stricken/RG     | 26-Mar |       |         |
| 52            | 3/15/2018      | Sgts Squad F          | 133      | Patch holes in wall near TV                                    |                 |                      |        |       |         |
| 53            | 3/15/2018      | Sgts Squad E          | 134      | Patch holes in wall near TV                                    |                 |                      |        |       |         |
| 54            | 3/15/2018      | Corridor              | 135      | Damaged square of carpet (outside #138)                        |                 | Completed            |        | FCM   | 26-Mar  |
|               |                |                       |          | to be replaced   |                 |                      |        |       |         |
| 55            | 3/15/2018      | Lieutenant            | 136      | OK   |                 |                      |        |       | 15-Mar  |
| 56            | 3/15/2018      | Copy/break rm         | 137      | OK   |                 |                      |        |       | 15-Mar  |
| 57            | 3/15/2018      | Lieutenant            | 138      | OK   |                 |                      |        | l .   | 15-Mar  |
| 58            | 3/15/2018      | Lieutenant            | 139      | OK   |                 |                      |        |       | 15-Mar  |
| 59            | 3/15/2018      | Deputy Dist<br>Cmdr   | 140      | OK   |                 |                      |        | FCM   | 15-Mar  |
| 60            | 3/15/2018      | Open office           | 141      | OK   |                 |                      |        | FCM   | 15-Mar  |
| 61            | 3/15/2018      | Conference rm         | 142      | Remove textured wallpaper; paint grey -                        |                 | Item stricken        |        | FCM   | 26-Mar  |
|               |                |                       |          | LAD to select color (throughout)                               |                 |                      |        |       |         |
| 62            | 3/15/2018      | Captain               | 143      | HVAC has slight rattle; needs adjustment                       |                 | Needs change order   | 26-Mar |       |         |
| 63            | 3/15/2018      | Captain               | 143      | Move blower over one square                                    |                 | to complete b/c duct |        |       |         |
| 64            | 3/15/2018      | Lieutenant            | 144      | OK   |                 |                      |        | FCM   | 15-Mar  |
| 65            | 3/15/2018      | Sergeant              | 145      | OK   |                 |                      |        | FCM   | 15-Mar  |
| 66            | 3/15/2018      | Lieutenant            | 146      | OK   |                 |                      |        | FCM   | 15-Mar  |
| 67            | 3/15/2018      | Lieutenant            | 147      | Caulk/glue on sidelight (hallway side) needs to be cleaned off |                 | Completed            |        | FCM   | 26-Mar  |

|               |           |                         |                | valk-through of floor 2, 2018-03-29  |      |                            |        |     |          |
|---------------|-----------|-------------------------|----------------|--|------|----------------------------|--------|-----|----------|
|               | Date      | Bldg Area               | Rm #           | Description  | Resp | Comments/date              |        |     | off/date |
| 68            | 3/15/2018 | Public Safety<br>Techs  | 148            | OK   |      |                            |        | FCM | 15-Mar   |
| 69            | 3/15/2018 | Armory                  | 149            | Sprinklerhead (outside entrance to room) is missing a flange                         |      | Noted                      | 26-Mar |     |          |
| 70            | 3/15/2018 | Armory                  | 149            | Stainless steel counters scratched   |      | Need to be polished/buffed | 26-Mar |     |          |
| 71            | 3/15/2018 | Restroom outside armory | 150            | Need transition strips   |      | Noted                      | 26-Mar |     |          |
| 72            | 3/15/2018 | Restroom outside armory | 151            | Need transition strips   |      | Noted                      | 26-Mar |     |          |
| 73            | 3/15/2018 | Communications          | 152            | Threshold needs transition strip   |      | Noted                      | 26-Mar |     |          |
| 74            | 3/15/2018 | Service Corridor        | 153            | OK   |      |                            |        | FCM | 15-Mar   |
| 75            | 3/15/2018 | Mechanical              | 154            | OK   |      |                            |        | FCM | 15-Mar   |
| 76            | 3/15/2018 | Demark                  | 155            | OK   |      |                            |        | FCM | 15-Mar   |
| 77            | 3/15/2018 | Electrical              | 156            | Ductwork - needs packing of opening between steel and concrete                       |      | Noted                      | 26-Mar |     |          |
| 78            | 1/3/2018  | Electrical              | 156            | Provide electrical raceway identification on conduits not utilizing colored conduits | FLBE | Noted                      | 26-Mar |     |          |
| 79            | 3/15/2018 | B&G                     | 157            | OK   |      |                            |        | FCM | 15-Mar   |
| 80            | 3/15/2018 | Janitor                 | 159            | OK   |      |                            |        | FCM | 15-Mar   |
| 81            | 3/15/2018 | Monitor room            | 160            | Need transition strips   |      | Noted                      | 26-Mar |     |          |
| 82            | 3/15/2018 | Vestibule               | 161            | OK   |      |                            |        | FCM | 15-Mar   |
| 83            | 3/15/2018 | Juvenile rm 1           | 162            | Walls need to be painted   |      | Completed                  |        | FCM | 26-Mar   |
| 84            | 3/15/2018 | Bag & tag               | 163            | Paint on door jamb   |      | Completed                  |        | FCM | 26-Mar   |
| <del>85</del> | 1/3/2018  | Bag & tag               | <del>163</del> | Repair excessive dip in floor as you enter-<br>room from terrazzo corridor           | CCA  | Item stricken              |        | FCM | 26-Mar   |
| 86            | 3/15/2018 | Juvenile rm 2           | 164            | OK   |      |                            |        | FCM | 15-Mar   |
| 87            | 3/15/2018 | Evidence processing     | 165            | OK   |      |                            |        | FCM | 15-Mar   |
| 88            | 3/15/2018 | Secure vestibule        | 166            | Bolt on the gun safe at the sallyport needs to be cut flush                          |      |                            |        |     |          |
| 89            | 3/15/2018 | Suspect<br>Processing   | 167            | Being redone   |      |                            |        |     |          |

| Condition | is as not | ed during FCM          | partial w | valk-through of floor 2, 2018-03-29                                  |                |                   |        |       |         |
|-----------|-----------|------------------------|-----------|--|----------------|-------------------|--------|-------|---------|
| Item Date | :         | Bldg Area              | Rm #      | Description  | Resp           | Comments/date     |        | Signo | ff/date |
| 90 1/3/2  | 2018      | Suspect                | 167       | Checker plates to be installed with                                  | William        | Check detail; may | 26-Mar |       |         |
|           |           | Processing             |           | countersunk flash fasteners - reinstall                              |                | not need to be    |        |       |         |
|           |           |                        |           |  |                | countersunk/RG    |        |       |         |
| 91 3/15/  | /2018     | Restroom               | 168       | OK   |                |                   |        | FCM   | 15-Mar  |
| 92 3/15/  | /2018     | EDP1                   | 169       | OK   |                |                   |        | FCM   | 15-Mar  |
| 93 3/15/  | /2018     | Interview              | 170       | Need transition strips   |                |                   |        |       |         |
| 94 3/15/  | /2018     | EDP2                   | 171       | OK   |                |                   |        | FCM   | 15-Mar  |
| 95 3/15/  | /2018     | Vestibule              | 172       | OK   |                |                   |        | FCM   | 15-Mar  |
| 96 3/15/  | /2018     | Stairwell              | 173       | OK   |                |                   |        | FCM   | 15-Mar  |
| 97 3/15/  | /2018     | Sallyport              | 174       | Door needs to be adjusted  |                | North door /RG    | 26-Mar |       |         |
| 98 3/15/  | /2018     | Exit from support bldg | 175       | Coal tar surface ok?   |                |                   |        |       |         |
| 99 3/15/  | /2018     | Support bldg           | 175       | Doors need adjustment - can see daylight/feel outside air at bottom  |                |                   |        |       |         |
| 100 3/15/ | /2018     | Support bldg           | 175       | Epoxy and scratches on floors  |                |                   |        |       |         |
| 101 3/15/ | /2018     | Support bldg           | 175       | Exterior door needs paint  |                |                   |        |       |         |
| 102 3/15/ | /2018     | Bulk storage           | 176       | OK   |                |                   |        | FCM   | 15-Mar  |
| 103 3/15/ | /2018     | Patrol bikes           | 177       | Paint outer door frame (near top)                                    |                |                   |        |       |         |
| 104 3/15/ | /2018     | K-9                    | 178       | OK   |                |                   |        | FCM   | 15-Mar  |
| 105 3/15/ | /2018     | Storage                | 179       | OK   |                |                   |        | FCM   | 15-Mar  |
| 106 3/15/ | /2018     | Sprinkler              | 181       | Full plate - exterior  |                |                   |        |       |         |
| 107 3/15/ | /2018     | Sprinkler              | 181       | Missing a switchbox  |                |                   |        |       |         |
| 108 3/15/ | /2018     | Sprinkler              | 181       | Reset damper   |                |                   |        |       |         |
| 109 3/15/ | /2018     | Sprinkler              | 181       | Weatherstripping to exterior door                                    |                |                   |        |       |         |
| 110 3/15/ | /2018     | Vestibule              | 200       | As noted below   |                |                   |        |       |         |
| 111 1/3/2 | 2018      | Vestibule              | 200       | Adjust weather stripping around doors                                | Design Glazing |                   |        |       |         |
| 112 1/3/2 | 2018      | Vestibule              | 200       | Both sets of doors are dragging and                                  | Design Glazing |                   |        |       |         |
|           |           |                        |           | sticking on each other - adjust doors to                             |                |                   |        |       |         |
|           |           |                        |           | seat properly in frame and work                                      |                |                   |        |       |         |
|           |           |                        |           | independently from adjoining door                                    |                |                   |        |       |         |
| 113 1/3/2 | 2018      | Vestibule              | 200       | Paint exterior door where bondo has occurred if paint does not match | Design Glazing |                   |        |       |         |
|           |           |                        |           | replacement door   |                |                   |        |       |         |

| Cond | ditions as not | ed during FCM p  | artial w | valk-through of floor 2, 2018-03-29         |                |                    |        |       |         |
|------|----------------|------------------|----------|---|----------------|--------------------|--------|-------|---------|
| Item | Date           | Bldg Area        | Rm#      | Description                                 | Resp           | Comments/date      |        | Signo | ff/date |
| 114  | 1/3/2018       | Vestibule        | 200      | Repaint columns                             | SGC            |                    |        |       |         |
| 115  | 12/12/2017     | Vestibule        | 200      | Need to replace felt on side of metal doors | Design Glazing |                    |        |       |         |
|      |                |                  |          | where they meet each other to seal out the  |                |                    |        |       |         |
|      |                |                  |          | cold air                                    |                |                    |        |       |         |
| 116  | 3/15/2018      | Lobby            | 201      | Arms on door closers need to be identical   |                | Completed          |        | FCM   | 26-Mar  |
| 117  | 3/15/2018      | Lobby            | 201      | Bubbling where end of X bars meet           | SGC            | Completed          |        | FCM   | 26-Mar  |
|      |                |                  |          | ceiling, left side (facing front)/drywall   |                |                    |        |       |         |
| 118  | 3/15/2018      | Lobby            | 201      | Cleaning of glazed areas (throughout)       |                |                    |        |       |         |
| 119  | 1/3/2018       | Lobby            | 201      | Install light fixtures H1 & H2 lights       | FLBE           | Completed          |        | FCM   | 29-Mar  |
|      | 1/3/2018       | Lobby            | 201      | Provide switch for display case light       | FLBE           | Check detail/RG    |        |       |         |
| 121  | 12/18/2017     | <del>Lobby</del> | 201      | Top of crossbars in vault of lobby ceiling  | SGC            | Duplicate of item  |        | FCM   | 26-Mar  |
|      |                |                  |          | sloppy, needs sanding/touchup               |                | #117               |        |       |         |
| 122  | 12/12/2017     | <del>Lobby</del> | 201      | Sharp edge on display                       | SGC            | Item stricken      |        | FCM   | 26-Mar  |
| 123  | 12/11/2017     | Lobby            | 201      | Drywall mud around top of crossbards in     | SGC            | Duplicate of item  |        | FCM   | 26-Mar  |
|      |                |                  |          | vaulted ceiling of lobby is sloppy, needs   |                | #117               |        |       |         |
|      |                |                  |          | <del>work</del>                             |                |                    |        |       |         |
| 124  | 1/3/2018       | Lobby men's      | 202      | Label access doors                          | ACME           | Completed          |        | FCM   | 26-Mar  |
| 125  | 3/15/2018      | Vestibule        | 203      | OK  |                |                    |        |       | 15-Mar  |
| 126  | 3/15/2018      | IA waiting       | 204      | OK  |                |                    |        | FCM   | 15-Mar  |
| 127  | 3/15/2018      | IA conf rm       | 206      | Remove textured wallpaper; paint grey -     |                | In progress; paper | 26-Mar |       |         |
|      |                |                  |          | LAD to select color                         |                | has been           |        |       |         |
| 128  | 12/12/2017     | IA conf rm       | 206      | Space in corner cabinet, repair required    | DES            |                    |        |       |         |
| 129  | 12/18/2017     | Copy rm          | 208      | Column needs prep, paint                    | SGC            | Completed          |        | FCM   | 29-Mar  |
| 130  | 1/3/2018       | IA break rm      | 209      | Provide proper FCO for sheet vinyl          | CCA            |                    |        |       |         |
|      | 3/15/2018      | Internal Affairs | 210      | OK  |                |                    |        |       | 15-Mar  |
|      | 3/15/2018      | IA office        | 211      | OK  |                |                    |        |       | 15-Mar  |
| 133  | 3/15/2018      | Admin Support    | 212      | OK  |                |                    |        | FCM   | 15-Mar  |
|      |                | Asst             |          |   |                |                    |        |       |         |
|      | 3/15/2018      | Storage          | 213      | OK  |                |                    |        | FCM   | 15-Mar  |
| 135  | 3/15/2018      | Women's rm       | 214      | Floor needs cleaning; 3/29, noted gouge     |                | Noted/see photo    | 29-Mar |       |         |
|      |                |                  |          | in floor in front of toilet                 |                |                    |        |       |         |
|      | 3/15/2018      | Women's rm       | 214      | Hole in door near lever needs plug          |                | Completed          |        |       | 29-Mar  |
| 137  | 1/3/2018       | Women's rm       | 214      | Provide label for access door               | ACME           | Completed          |        | FCM   | 29-Mar  |

| Cond | ditions as not | ed during FCM p        | artial w | valk-through of floor 2, 2018-03-29                         |           |  |        |       |         |
|------|----------------|------------------------|----------|---|-----------|--|--------|-------|---------|
| Item | Date           | Bldg Area              |          | Description   | Resp      | Comments/date                                      |        | Signo | ff/date |
| 138  | 1/3/2018       | Women's rm             | 214      | Remove grout from tile face at door                         | I-Tiles   | Noted/see photo                                    | 29-Mar |       |         |
|      |                |                        |          | location and throughout space                               |           |  |        |       |         |
|      | 3/15/2018      | Men's rm               | 215      | OK  |           |  |        |       | 15-Mar  |
|      | 3/15/2018      | Corridor               | 216      | OK  |           |  |        |       | 15-Mar  |
| 141  | 3/15/2018      | Stair                  | 217      | OK  |           |  |        | FCM   | 15-Mar  |
| 142  | 12/12/2017     | Data closet            | 218      | Wall paint incomplete                                       | Paintworx |  |        |       |         |
| 143  | 1/3/2018       | Electrical             | 219      | Cavity between exterior wall and door needs to be filled    | SGC       | Completed  |        | FCM   | 29-Mar  |
| 144  | 1/3/2018       | Electrical             | 219      | Housing of DSS-4A is not seated near equipment label        | ACME/FLBE |  |        |       |         |
| 145  | 3/15/2018      | Janitor closet         | 220      | Replace drain cover and clean out drain                     |           | Room locked  | 29-Mar |       |         |
| 146  | 1/3/2018       | Janitor closet         | 220      | Noise from above ceiling                                    | ACME      | Item stricken/RG                                   | 26-Mar |       |         |
| 147  | 1/3/2018       | Janitor closet         | 220      | Repaint storm line  | Paintworx | Room locked  | 29-Mar |       |         |
| 148  | 3/15/2018      | Executive toilet       | 221      | OK  |           |  |        | FCM   | 15-Mar  |
| 149  | 3/15/2018      | Chief's corridor       | 222      | Corner guards   |           | Noted  | 29-Mar |       |         |
| 150  | 12/12/2017     | Chief's corridor       | 222      | Corner edge of floor molding not correct, should be beveled | SGC       |  |        |       |         |
| 151  | 3/15/2018      | Deputy Chief           | 223      | OK  |           |  |        | FCM   | 15-Mar  |
| 152  | 3/15/2018      | Chief                  | 224      | OK  |           |  |        | FCM   | 15-Mar  |
|      | 3/15/2018      | Admin Support<br>Coord | 225      | OK  |           |  |        | FCM   | 15-Mar  |
| 154  | 3/15/2018      | Chief Aide             | 226      | OK  |           |  |        | FCM   | 15-Mar  |
| 155  | 3/15/2018      | Chief's coffee area    | 227      | OK  |           |  |        | FCM   | 15-Mar  |
| 156  | 3/15/2018      | Copy room              | 228      | Surface scuff marks; need sealant or caulk                  |           | Completed  |        | FCM   | 29-Mar  |
|      | 1/3/2018       | Copy room              | 228      | Install transition strip at door threshold                  | CCA       | Completed  |        | FCM   | 29-Mar  |
|      | 12/18/2017     | Copy room              | 228      | Gouge in caulk next to door                                 | K-Plus    | 1  |        |       |         |
| 159  | 3/15/2018      | Conference             | 229      | Remove textured wallpaper; paint grey                       |           | Per RG - in progress;<br>paper has been<br>removed | 29-Mar |       |         |
| 160  | 1/3/2018       | Conference             | 229      | Provide IR extender   | FLBE/ACME |  |        |       |         |
| 161  | 12/18/2017     | Assistant Chief        | 230      | Corner on right needs repair -cracked                       | SGC       |  |        |       |         |

| Cond | ditions as not | ed during FCM p  | artial v | valk-through of floor 2, 2018-03-29         |            |               |        |     |         |
|------|----------------|------------------|----------|---|------------|---------------|--------|-----|---------|
| Item | Date           | Bldg Area        | Rm#      | Description                                 | Resp       | Comments/date |        |     | ff/date |
| 162  | 3/15/2018      | Admin Support    | 231      | OK  |            |               |        | FCM | 15-Mar  |
|      |                | Coord            |          |   |            |               |        |     |         |
|      | 3/15/2018      | Assistant Chief  | 232      | OK  |            |               |        |     | 15-Mar  |
| 164  | 3/15/2018      | File area        | 233      | OK  |            |               |        |     | 15-Mar  |
| 165  | 3/15/2018      | Admin Support    | 234      | OK  |            |               |        | FCM | 15-Mar  |
|      |                | Asst             |          |   |            |               |        |     |         |
| 166  | 3/15/2018      | Reception        | 235      | OK  |            |               |        | FCM | 15-Mar  |
| 167  | 12/18/2017     | Chief's Office   | 236      | Door to 222 needs trim paint, (removal      | Paintworx  | Completed     |        | FCM | 29-Mar  |
|      |                | waiting area     |          | of) excess caulk                            |            |               |        |     |         |
| 168  | 12/18/2017     | Chief's Office   | 236      | Overspray on storefront                     | Paintworx  | Completed     |        | FCM | 29-Mar  |
|      |                | waiting area     |          |   |            |               |        |     |         |
| 169  | 12/18/2017     | Chief's Office   | 236      | Wall paint needed around reception desk     | Paintworx  | Completed     |        | FCM | 29-Mar  |
|      |                | waiting area     |          |   |            |               |        |     |         |
| 170  | 3/15/2018      | Corridor         | 237      | OK  |            |               |        | FCM | 15-Mar  |
| 171  | 3/15/2018      | PIO suite        | 238      | OK  |            |               |        | FCM | 15-Mar  |
| 172  | 3/15/2018      | PIO office       | 239      | OK  |            |               |        | FCM | 15-Mar  |
| 173  | 3/15/2018      | Elevator equipt  | 240      | OK  |            |               |        | FCM | 15-Mar  |
| 174  | 3/15/2018      | Stair 2          | 241      | OK  |            |               |        | FCM | 15-Mar  |
| 175  | 3/15/2018      | Corridor         | 242      | OK  |            |               |        | FCM | 15-Mar  |
| 176  | 1/3/2018       | Front desk       | 243      | Remove glue from carpet tile                | CCA        |               |        |     |         |
| 177  | 3/15/2018      | Vestibule        | 244      | Crimp in door striping near hinge - cut out |            | Completed     |        | FCM | 29-Mar  |
|      |                |                  |          | and sand                                    |            |               |        |     |         |
| 178  | 3/15/2018      | Report taking    | 245      | OK  |            |               |        | FCM | 15-Mar  |
| 179  | 3/15/2018      | Lobby women's    | 246      | OK  |            |               |        | FCM | 15-Mar  |
|      |                | bath             |          |   |            |               |        |     |         |
| 180  | 3/15/2018      | FTSD             | 247      | OK  |            |               |        | FCM | 15-Mar  |
|      |                | Conference rm    |          |   |            |               |        |     |         |
| 181  | 3/15/2018      | Corridor         | 248      | As noted below                              |            |               |        |     |         |
| 182  | 1/3/2018       | Corridor         | 248      | Complete AV & security                      | FLBE/Owner |               |        |     |         |
|      | 1/3/2018       | Corridor         | 248      | Repair dent in light at stairwell           | FLBE       |               |        |     |         |
|      | 3/15/2018      | Chair storage rm | 249      | OK  |            |               |        | FCM | 15-Mar  |
| 185  | 3/15/2018      | Training room    | 250      | Install blank plates in data drops          |            | Noted         | 29-Mar |     |         |

|                |            |                        |                | valk-through of floor 2, 2018-03-29   | D         | C   |        | C:  | CC / 1 - 4 - |
|----------------|------------|------------------------|----------------|---|-----------|---|--------|-----|--------------|
|                | Date       | Bldg Area              | 1              | Description   | Resp      | Comments/date   | 1      |     | off/date     |
| <del>186</del> | 1/3/2018   | Training room          | <del>250</del> | Investigate noise coming from grille near-<br>249                           | ACME      | Item stricken/RG  |        | FCM | 26-Mar       |
| 187            | 1/3/2018   | Training room          | 250            | Provide 5 gang stainless steel plates for                                   | FLBE      | Noted   | 29-Mar |     |              |
| 188            | 1/3/2018   | Training room          | <del>250</del> | Verify proper mech operation; currently excessive noise in space            | ACME      | Item stricken/RG  |        | FCM | 26-Mar       |
| 189            | 3/15/2018  | Vestibule              | 251            | OK  |           |   |        | FCM | 15-Mar       |
|                | 3/15/2018  | Storage rm 4           | 253            | OK  |           |   |        | FCM | 15-Mar       |
|                | 1/3/2018   | AV Storage             | 254            | Repair dent in light fixture  | FLBE      | Room locked/inaccessible                                    | 29-Mar |     |              |
| 192            | 1/3/2018   | Kitchen                | 255            | Repair or replace cabinet door above sink - currently scratched near handle | DES       | Completed   |        | FCM | 29-Mar       |
|                | 1/3/2018   | Chief's storage        | <del>256</del> | Fan loud  | ACME      | Item stricken/RG  |        | FCM | 26-Mar       |
| <del>194</del> | 12/12/2017 | Chief's storage        | <del>256</del> | Fan very loud   | ACME      | Item stricken/RG  |        | FCM | 26-Mar       |
|                | 3/15/2018  | Planning               | 257            | OK  |           |   |        | FCM | 15-Mar       |
| 196            | 3/15/2018  | Assistant Chief        | 258            | OK  |           |   |        | FCM | 15-Mar       |
| 197            | 3/15/2018  | Admin Support<br>Coord | 259            | OK  |           |   |        | FCM | 15-Mar       |
| 198            | 3/15/2018  | Division Chief         | 260            | OK  |           |   |        | FCM | 15-Mar       |
| 199            | 3/15/2018  | Janitor                | 261            | OK  |           |   |        | FCM | 15-Mar       |
| 200            | 3/15/2018  | Women's rm             | 262            | Doorsill needs transition strip   |           | Noted   | 29-Mar |     |              |
| 201            | 3/15/2018  | Women's rm             | 262            | handicap stall needs stopper on wall<br>behind door                         |           |   |        |     |              |
| 202            | 1/3/2018   | Women's rm             | 262            | Remove paint from toilet partitions   | Paintworx | Scratches on door - see photo                               | 29-Mar |     |              |
| 203            | 12/18/2017 | Women's rm             | 262            | Wall where partition attaches needs to be redone (head rail)                | SGC       | Completed   |        | FCM | 29-Mar       |
| 204            | 12/12/2017 | Women's rm             | 262            | Threshold is needed under door  | SGC       | Item<br>stricken/duplicate                                  |        | FCM | 29-Mar       |
| 205            | 3/15/2018  | Men's rm               | 263            | Doorsill needs transition strip   |           | Noted   | 29-Mar |     |              |
|                | 12/18/2017 | Open office            | 264            | Window frames are scratched - need to be painted                            | Paintworx | Noted - see photo;<br>also noted in<br>adjoining space #293 | 29-Mar |     |              |

| Cond | ditions as not | ed during FCM pa      | artial v       | valk-through of floor 2, 2018-03-29         |                |                      |        |       |         |
|------|----------------|-----------------------|----------------|---|----------------|----------------------|--------|-------|---------|
| Item | Date           | Bldg Area             | Rm #           | Description                                 | Resp           | Comments/date        |        | Signo | ff/date |
| 207  | 3/15/2018      | Security equipt       | 265            | Flooring at entrance bubbling, needs        |                | Noted                | 29-Mar |       |         |
|      |                | rm                    |                | repair                                      |                |                      |        |       |         |
| 208  | 1/3/2018       | Security equipt       | 265            | Install transition strip at door threshold  | CCA            | Noted                | 29-Mar |       |         |
| 200  | 1 /2 /2010     | rm                    | 265            | D : 1 1 11                                  | CCA            | NT , 1               | 20.14  |       |         |
| 209  | 1/3/2018       | Security equipt<br>rm | 265            | Repair gyp board walls                      | CCA            | Noted                | 29-Mar |       |         |
| 210  | 1/3/2018       | Security equipt       | <del>265</del> | Rework flooring (material underneath        | CCA            | Stricken - duplicate |        | FCM   | 29-Mar  |
|      |                | <del>rm</del>         |                | <del>floor surface)</del>                   |                | of item #207         |        |       |         |
| 211  | 3/15/2018      | ITMB                  | 266            | Blank plates in drops (throughout)          |                |                      |        |       |         |
| 212  | 1/3/2018       | ITMB                  | 266            | Install doors at electric closet per change | SGC            | Per RG - pending     | 26-Mar |       |         |
|      |                |                       |                | order                                       |                |                      |        |       |         |
| 213  | 1/3/2018       | ITMB                  | <del>266</del> | Investigate noise coming from grille        | ACME           | Item stricken        |        | FCM   | 29-Mar  |
| 214  | 1/3/2018       | ITMB                  | 266            | Repair damage to door frame 272 and 273     | All Phase      | Completed            |        | FCM   | 29-Mar  |
|      |                |                       |                | at door and side light                      |                |                      |        |       |         |
| 215  | 1/3/2018       | ITMB                  | 266            | Repair damaged door frame at 270 at door    | All Phase      |                      |        | FCM   | 29-Mar  |
|      |                |                       |                | & sidelight                                 |                |                      |        |       |         |
| 216  | 1/3/2018       | ITMB                  | 266            | Repair damaged door frame at 271 at door    | All Phase      |                      |        | FCM   | 29-Mar  |
|      |                |                       |                | & sidelight                                 |                |                      |        |       |         |
| 217  | 1/3/2018       | ITMB                  | 266            | Replace or repair door frame 276            | SGC/All Phase  |                      |        | FCM   | 29-Mar  |
| 218  | 12/18/2017     | ITMB                  | 266            | Corners need corner guards                  | All Phase      |                      |        |       |         |
| 219  | 12/18/2017     | ITMB                  | 266            | Dirty wall covering                         | Paintworx      |                      |        |       |         |
| 220  | 12/18/2017     | ITMB                  | 266            | Window frame needs caulk                    | SGC            |                      |        |       |         |
| 221  | 3/15/2018      | ITMB workroom         | 267            | OK  |                |                      |        | FCM   | 15-Mar  |
| 222  | 3/15/2018      | Lieutenant            | 268            | OK  |                |                      |        | FCM   | 15-Mar  |
| 223  | 3/15/2018      | Systems               | 270            | Window screws don't match; paint for        |                | Completed            |        | FCM   | 29-Mar  |
|      |                | Developer             |                | uniformity                                  |                |                      |        |       |         |
| 224  | 12/12/2017     | Systems               | 270            | Missing screws on interior window frames    | Design Glazing | Completed            |        | FCM   | 29-Mar  |
|      |                | Developer             |                |   |                |                      |        |       |         |
| 225  | 3/15/2018      | Lt/MIS                | 271            | Window screws don't match; paint for        |                | Completed            |        | FCM   | 29-Mar  |
|      |                | Coordinator           |                | uniformity                                  |                |                      |        |       |         |
| 226  | 3/15/2018      | MF Analyst            | 272            | Window screws don't match; paint for        |                | Completed            |        | FCM   | 29-Mar  |
|      |                |                       |                | uniformity                                  |                | •                    |        |       |         |
| 227  | 1/3/2018       | MF Analyst            | 272            | Inner core of diffuser out of square        | ACME           |                      |        |       |         |

| Con  | ditions as not | ed during FCM p   | artial v       | valk-through of floor 2, 2018-03-29  |               |  |        |       |         |
|------|----------------|-------------------|----------------|--|---------------|--|--------|-------|---------|
| Item | Date           | Bldg Area         | Rm#            | Description  | Resp          | Comments/date  |        | Signo | ff/date |
| 228  | 1/3/2018       | MF Analyst        | 272            | Prep and repaint door and window frame   | Paintworx     | Completed  |        | FCM   | 29-Mar  |
| 229  | 3/15/2018      | Admin Analyst     | 273            | Window screws don't match; paint for uniformity                                    |               | Completed  |        | FCM   | 29-Mar  |
| 230  | 1/3/2018       | Comm/Telecom<br>m | 274            | Provide ID for all Allen Bradley starter switches in space                         | FLBE          | Noted  | 29-Mar |       |         |
| 231  | 1/3/2018       | Comm/Telecom<br>m | 274            | Remove foil tape from filter grille  | ACME          |  |        |       |         |
|      | 3/15/2018      | Admin Specialist  | 275            | See comments - info only   |               | Dent in overhead<br>systems furniture<br>(PM gets this)                                |        |       |         |
| 233  | 1/3/2018       | Admin Specialist  | <del>275</del> | Investigate noise coming from grille   | ACME          | Item stricken/RG   |        | FCM   | 26-Mar  |
| 234  | 12/12/2017     | Admin Analyst     | 275            | Damaged and missing ceiling tiles  | All Phase     | Completed  |        | FCM   | 29-Mar  |
| 235  | 3/15/2018      | Copy room 3       | 276            | Caulk/glue bootprints on floor - clean   |               | Completed  |        | FCM   | 29-Mar  |
| 236  | 12/12/2017     | Copy room 3       | 276            | Tile floor needs cleaning  | Cleanmaster   | Cleaned; however,<br>there are now gouges<br>and scratches in floor<br>tile. See photo | I .    |       |         |
| 237  | 12/18/2017     | Storage           | 277            | Scratched door   | SGC           | Noted  | 29-Mar |       |         |
| 238  | 1/3/2018       | Corridor          | 278            | Repair scratches in elevator frame and   | SGC           |  |        |       |         |
| 239  | 1/3/2018       | Stair 3           | 279            | Install threshold at door leading to roof; excessive gap                           | SGC/All Phase |  |        |       |         |
| 240  | 1/3/2018       | Stair 3           | 279            | Provide caulking at perimeter of door frame to roof; prep and paint frame and door | SGC           |  |        |       |         |
| 241  | 12/12/2017     | Stair 3           | 279            | Large gap at bottom of door leading to roof  | SGC           | Per RG - material ordered  | 26-Mar |       |         |
| 242  | 3/15/2018      | Elevator equipt   | 280            | OK   |               |  |        | FCM   | 15-Mar  |
|      | 3/15/2018      | Interview suite   | 281            | Column outside this room needs to be sanded and bonded                             |               |  |        |       |         |
| 244  | 3/15/2018      | Interview         | 282            | Missing threshold drops  |               | Noted  | 29-Mar |       |         |
|      | 3/15/2018      | Interview         | 283            | Missing threshold drops  |               | Noted  | 29-Mar |       |         |
|      | 1/3/2018       | Interview         | 283            | Confirm need for sound seals on door frame   | Owner         | Item stricken/RG   |        | FCM   | 26-Mar  |

| Conc           | ditions as not | ed during FCM p | artial v       | valk-through of floor 2, 2018-03-29         |           |                      |        |       |         |
|----------------|----------------|-----------------|----------------|---|-----------|----------------------|--------|-------|---------|
| Item           | Date           | Bldg Area       | Rm#            | Description                                 | Resp      | Comments/date        |        | Signo | ff/date |
| 247            | 1/3/2018       | Interview       | <del>283</del> | Fan loud                                    |           | Item stricken/RG     |        | FCM   | 26-Mar  |
| 248            | 3/15/2018      | Interview       | 284            | Missing threshold drops                     |           | Noted                | 29-Mar |       |         |
| 249            | 3/15/2018      | Interview       | 284            | Pilot light outside room does not energize  |           | Noted                | 29-Mar |       |         |
| <del>250</del> | 1/3/2018       | Interview       | <del>284</del> | Fan loud                                    | ACME      | Item stricken/RG     |        | FCM   | 26-Mar  |
| 251            | 3/15/2018      | Interview       | 285            | Missing threshold drops                     |           | Noted                | 29-Mar |       |         |
| 252            | 1/3/2018       | Interview       | 285            | All items on Owner list still apply         |           |                      |        |       |         |
| 253            | 1/3/2018       | Interview       | <del>285</del> | Fan loud                                    | ACME      | Item stricken/RG     |        | FCM   | 26-Mar  |
|                | 12/18/2017     | Interview       | 285            | Seams in wall covering visible; excess glue | Paintworx | Noted                | 29-Mar |       |         |
| 255            | 3/15/2018      | Restroom        | 286            | Trap primer                                 |           | There is now glue on | 29-Mar |       |         |
|                |                |                 |                |   |           | floor which needs to |        |       |         |
|                |                |                 |                |   |           | be removed           |        |       |         |
| 256            | 3/15/2018      | Monitor room    | 287            | Threshold and plates                        |           | Noted                | 29-Mar |       |         |
| <del>257</del> | 3/15/2018      | Copy room       | <del>288</del> | Stopper on wall behind refrigerator door    |           | Item stricken        |        | FCM   | 29-Mar  |
| 258            | 12/18/2017     | Copy room       | 288            | Dent in wall behind door                    | All Phase | Completed            |        | FCM   | 29-Mar  |
| 259            | 3/15/2018      | CID supervisor  | 289            | OK  |           |                      |        | FCM   | 15-Mar  |
| 260            | 3/15/2018      | CID supervisor  | 290            | OK  |           |                      |        | FCM   | 15-Mar  |
| 261            | 3/15/2018      | CID supervisor  | 291            | OK  |           |                      |        | FCM   | 15-Mar  |
| 262            | 3/15/2018      | CID supervisor  | 292            | OK  |           |                      |        | FCM   | 15-Mar  |
| 263            | 3/15/2018      | Detectives      | 293            | Window scratches, see item 206 for          |           | Noted - see photo    | 29-Mar |       |         |
|                |                |                 |                | comments on adjoining space                 |           |                      |        |       |         |
| 264            | 3/15/2018      | CID conf rm     | 294            | Cracked plate on wall needs to be replaced  |           | Completed            |        | FCM   | 29-Mar  |
| 265            | 3/15/2018      | CID conf rm     | 294            | Window frame needs                          |           | Noted                | 29-Mar |       |         |
|                |                |                 |                | sanding/painting/caulking                   |           |                      |        |       |         |
| 266            | 1/3/2018       | CID conf rm     | 294            | Install carpet in floor access panel recess | CCA       | Completed/RG         |        | FCM   | 26-Mar  |
| 267            | 1/3/2018       | CID conf rm     | <del>294</del> | Install markable surface on gyp board       | Paintworx | Item stricken/RG     |        | FCM   | 26-Mar  |
|                |                |                 |                | columns                                     |           |                      |        |       |         |
| 268            | 1/3/2018       | CID conf rm     | 294            | Wall plate upside down                      | FLBE      |                      |        |       |         |
| 269            | 3/15/2018      | Electrical      | 295            | OK  |           |                      |        | FCM   | 15-Mar  |
|                | 3/15/2018      | General item    | GEN            | Check door handles - some play in all       |           |                      |        |       |         |
|                | 1/3/2018       | General item    | GEN            | At all exposed steel columns on this        | All       |                      |        |       |         |
|                |                |                 |                | project, properly prepare columns for       |           |                      |        |       |         |
|                |                |                 |                | finish paint                                |           |                      |        |       |         |

| Conc | ditions as not | ted during FCM | partial w | alk-through of floor 2, 2018-03-29           |                  |                        |        |       |         |
|------|----------------|----------------|-----------|--|------------------|------------------------|--------|-------|---------|
| Item | Date           | Bldg Area      | Rm #      | Description                                  | Resp             | Comments/date          |        | Signo | ff/date |
| 272  | 1/3/2018       | General item   | GEN       | Provide ARC flash hazard warning labels      | FLBE             |                        |        |       |         |
|      |                |                |           | on all panelboards and disconnects; ensure   |                  |                        |        |       |         |
|      |                |                |           | the label provides the following             |                  |                        |        |       |         |
|      |                |                |           | information taken from the arc-flash         |                  |                        |        |       |         |
|      |                |                |           | hazard analysis: location, nominal voltage,  |                  |                        |        |       |         |
|      |                |                |           | flash protection boundary, hazard risk       |                  |                        |        |       |         |
|      |                |                |           | category, incident energy, working           |                  |                        |        |       |         |
|      |                |                |           | distance, engineering report number,         |                  |                        |        |       |         |
|      |                |                |           | revision number, and issue date.             |                  |                        |        |       |         |
| 273  | 1/3/2018       | General item   | GEN       |  | DES              |                        |        |       |         |
| 274  | 1/3/2018       | General item   | GEN       | Provide electrical raceway identification on | FLBE             |                        |        |       |         |
|      |                |                |           | conduits not utilizing colored conduits      |                  |                        |        |       |         |
| 275  | 1/3/2018       | General item   | GEN       | Repaint structural columns inside toilet     | Paintworx/K-Plus | Completed/RG           |        | FCM   | 26-Mar  |
|      |                |                |           | locations including repairs to divots and    |                  | _                      |        |       |         |
|      |                |                |           | scratches; caulk either side of column.      |                  |                        |        |       |         |
| 276  | 1/3/2018       | General item   | GEN       | Rework finish on column including            | Paintworx        | Completed/RG           |        | FCM   | 26-Mar  |
|      |                |                |           | patching scratches and divots, sand and      |                  | _                      |        |       |         |
|      |                |                |           | repaint where necessary                      |                  |                        |        |       |         |
| 277  | 3/15/2018      | General item   | GEN       | Crimp in door striping near hinge - cut out  |                  | Door to 203            | 29-Mar |       |         |
|      |                |                |           | and sand (throughout)                        |                  | complete; left side of |        |       |         |
|      |                |                |           |  |                  | door to 244            |        |       |         |
| 278  | 3/26/2018      | General item   | GEN       | All stainless steel counters/work surfaces   |                  |                        |        |       |         |
|      |                |                |           | on level 1 have multiple scratches; need to  |                  |                        |        |       |         |
|      |                |                |           | be buffed.                                   |                  |                        |        |       |         |
| 289  | 3/26/2018      | General item   | GEN       | Elevator doors - film needs to be stripped   |                  |                        |        |       |         |
|      |                |                |           | and doors cleaned                            |                  |                        |        |       |         |



## RINKER DESIGN ASSOCIATES, P.C.

Engineering • Surveying • Land Planning Transportation • Right of Way • Environmental

### **Punch List Site Visit**

Date: December 29, 2017

Attended by: Sharon Dusza, Tim Freeland: RDA, Gary Morrison, PWC Buildings & Grounds

Job Name/Number: Prince William County Central District Police Station 13175-001

Prepared by: Sharon Dusza, RDA; Ashby Thompson, RDA

#### **Punchlist Items:**

Itemized below are deficiencies for all site work located outside of the highway response course that we found during our site visit on December 29, 2017.

#### General:

Parge all lift holes at curb inlets.

Remove large stones and fine grade, reseed in grassed areas.

Parking Spaces not properly spaced at 9'. Contractor to survey or provide documentation of parking space dimensions for all parking spaces on site.

Repaint all chipping/peeling paint.

Repair/replace gouges/chips in curb & gutter.

Replace concrete where cracking.

Clean gravel, straw, trash, debris from site

Verify that all pole lights work

Cracked curb.



20171229\_132855.jpg

### **Punchlist**

Project Name: Central District Police Station

On 1-11-2018 and 1-25-2018 an Exterior; Roof and Support Building Punchlist Inspection of the Central District Police Station project located in Prince William County, Virginia was performed. The following is a list of items found. Failure to include any items on this list does not alter the responsibility of the Contractor to complete all of the work in accordance with the Contract Documents.

| Item#     | Date Noted | Bldg Area       | Room #    | Type  | Issue   | Status             |
|-----------|------------|-----------------|-----------|-------|---|--------------------|
| itemin ii | Date Notes | Diag / ii cu    | 110011111 | 1,700 | Redo granular at all tar seams throughout entire roof - granular are of the wrong color     |                    |
| 1         | 1/11/2018  | General Item    | NA        | Gen   | (gray) at various locations and is lightly applied at all locations                         | Defer to Architect |
|           | 1/11/2010  | Generalitem     | 14/-4     | GCII  | At the metal panels excessive gaps in the spline metal within the reveals an numerous       | Defer to Architect |
|           |            |                 |           |       | locations - in particular at corners leaving excessive voids. Make corrections to eliminate |                    |
| 4         | 1/11/2018  | General Item    | NA        | Gen   | these voids   | Complete           |
|           | 1/11/2010  | Generalitem     | 14/-4     | GCII  | Copings - complete crimping at the drip edge - currently the coping has been crimped at     | complete           |
| 5         | 1/11/2018  | General Item    | NA        | Gen   | various locations but is not continuous   | Defer to Architect |
| J         | 1/11/2010  | Generalitem     | 107       | Gen   | Clean all galvanized steel supporting the louvres and provide TU galvanized at rusted       | Deter to Architect |
| 6         | 1/11/2018  | General Item    | NA        | Gen   | locations   | Defer to Architect |
|           | _,,        |                 |           |       | At all metal panels - adjust to provide a uniform reveal between panels at both vertical    |                    |
| 7         | 1/11/2018  | General Item    | NA        | Gen   | and horizontal joints   | Defer to Architect |
| 8         | 1/11/2018  | General Item    | NA        | Gen   | Remove silt from brick  | Defer to Architect |
| 9         | 1/11/2018  | General Item    | NA        | Gen   | Provide threshold at all ext. doors   | Complete           |
| 10        | 1/11/2018  | General Item    | NA        | Gen   | Paint all lintels at windows throughout bldg.   | Defer to Architect |
| 11        | 1/11/2018  | General Item    | NA        | Gen   | All masonry at Security Wall - Clean brick - removing silt                                  | Defer to Architect |
| 12        | 1/11/2018  | General Item    | NA        | Gen   | Remove zip strip and provide caulking at all joints between concrete and masonry            | Defer to Architect |
|           | , ,        |                 |           |       | Cut the gate post on the S, N, E walls center gate down so that cap of post is below the    |                    |
| 13        | 1/11/2018  | General Item    | NA        | Gen   | precast masonry   | Incomplete         |
| 14        | 1/11/2018  | General Item    | NA        | Gen   | Install Snow Guards (Bar Type) at all Metal Roof Locations per Contract.                    | Complete           |
|           | , ,        |                 |           |       | Provide flat steel cover plate at OHCDs through out project where excessive gap exists      |                    |
| 17        | 1/25/2018  | General Item    |           | Gen   | between steel and brick work - paint steel to match lintel                                  | Defer to Architect |
| 18        | 1/25/2018  | General Item    |           | Gen   | Install Snow Guards standing seam roof  | Complete           |
| 19        | 1/25/2018  | General Item    |           | Gen   | Install pedestals+F275  | Defer to Architect |
| 21        | 1/25/2018  | General Item    |           | Gen   | Verify proper operation of all wall hydrants  | Defer to Architect |
| 23        | 1/25/2018  | General Item    |           | Gen   | Soffit metal panels at windows installed in an unworkman like manner                        | Defer to Architect |
| 24        | 1/25/2018  | General Item    |           | Gen   | Crimp coping continuously not just at 5' on center  | Defer to Architect |
| 25        | 1/25/2018  | General Item    |           | Gen   | Provide mortar or caulking at vertical joints in precast                                    | Defer to Architect |
| 26        | 1/25/2018  | General Item    |           | Gen   | Cut down all clean outs flush with grade and verify if concrete pads required               | Defer to Architect |
| 27        | 1/25/2018  | General Item    |           | Gen   | Clean all excessive concrete from concrete curbs and light pole bases                       | Defer to Architect |
| 28        | 1/25/2018  | General Item    |           | Gen   | Ensure standing grass throughout  | Defer to Architect |
| 31        | 1/25/2018  | General Item    |           | Gen   | Paint all lintel steel at window heads  | Complete           |
| 32        | 1/25/2018  | General Item    |           | Gen   | Provide caulking at base of metal panels to brick work currently excessive gap              | Defer to Architect |
|           |            |                 |           |       | Repair all damaged precast at all locations - if repair is detectable by naked eye replace  |                    |
| 33        | 1/25/2018  | General Item    |           | Gen   | precast   | Defer to Architect |
| 35        | 1/11/2018  | Roof N to S End |           |       | Splines at the stair tower have slipped leaving excessive gap exposed structure             | Defer to Architect |
| 41        | 1/11/2018  | Roof N to S End |           |       | Install missing cover at overflow drains - middle of bldg.                                  | Complete           |
|           |            |                 |           |       |   |                    |
| 42        | 1/11/2018  | Roof N to S End |           |       | Install missing flashing seam adjacent to the stink pipe behind the aluminum panel entry    | Complete           |
| 44        | 1/11/2018  | Roof N to S End |           |       | Remove ladder from roof   | Complete           |
| 45        | 1/11/2018  | Roof N to S End |           |       | Provide roof manufactures final certification for roof installation                         | Defer to Architect |
| 46        | 1/11/2018  | Roof N to S End |           |       | Excessive gap in coping - gravel stop - raised entry roofing above the aluminum wall panel  | Defer to Architect |

|       | Ī         |                             |  |                      |
|-------|-----------|-----------------------------|--|----------------------|
| 47    | 1/11/2018 | Roof N to S End             | Remove excessive caulk at coping joints along the E wall                                       | Defer to Architect   |
| 48    | 1/11/2018 | Roof N to S End             | The raised roofing area above the entry are not accessible - review at a later date            | Defer to Architect   |
| 52    | 1/11/2018 | Roof N to S End             | Reveal splines have slipped at the stair tower at the S - make corrections necessary           | Defer to Architect   |
|       |           |                             | Reveals and metal panel at the stair tower at the S, are not uniformed - and vary in width     |                      |
| 53    | 1/11/2018 | Roof N to S End             | size - adjust for uniform reveals  | Defer to Architect   |
| 54    | 1/11/2018 | Roof N to S End             | Provide threshold at access door from bldg, to roof  | Complete             |
| 55    | 1/11/2018 | Roof N to S End             | Rework trim at perimeter of access door to roof and provide caulking as necessary              | Defer to Architect   |
| 56    | 1/11/2018 | Roof N to S End             | Remove chalk lines from metal panels   | Defer to Architect   |
|       |           |                             |  |                      |
| 59    | 1/11/2018 | Roof N to S End             | Provide splash blocks at downspouts at all locations where downspouts dump to roof             | Incomplete           |
|       |           |                             | Make entire roof look like the roofing that has been replaced on the W side of the S stair     |                      |
|       |           |                             | tower - currently the correct granular have been utilized as this location however it is still |                      |
| 61    | 1/11/2018 | Roof N to S End             | missing at the curb seams  | Defer to Architect   |
| 63    | 1/11/2018 | Roof N to S End             | Provide missing metal at reveal at the stair tower at the S end - numerous locations           | Defer to Architect   |
| 64    | 1/11/2018 | Roof N to S End             | Metal at reveals at the stair tower at the S, is discolored - does not match. Replace          | Defer to Architect   |
| 68    | 1/11/2018 | Roof N to S End             | Verify light over access door is operational   | Defer to Architect   |
|       | , ,       | Dumpster Pad and Mech.      |  |                      |
| 69    | 1/11/2018 | Yard                        | Fill 6x6 steel tube columns with concrete and install steel cap at the top of each column      | Defer to Architect   |
|       | , ,       | Dumpster Pad and Mech.      |  |                      |
| 71    | 1/11/2018 | Yard                        | Provide receivers for the cane latch at all gates - provide at closed and open positions       | Complete             |
|       | _,,       | Dumpster Pad and Mech.      |  |                      |
| 74    | 1/11/2018 | Yard                        | Provide caulking at zipped strip expansion at joint between concrete and brick work            | Defer to Architect   |
|       | _,,       | Dumpster Pad and Mech.      |  |                      |
| 76    | 1/11/2018 | Yard                        | Repair damage at gate right hand leaf of dumpster enclosure                                    | Complete             |
| , 0   | 1/11/2010 | Dumpster Pad and Mech.      | ntepair duringe at gate right hand rear or duringster endissare                                | complete             |
| 77    | 1/11/2018 | Yard                        | Verify operation of wall packs   | Defer to Architect   |
| - ' ' | 1/11/2010 | Dumpster Pad and Mech.      | Verny operation of wan packs   | Defer to 7 werniteet |
| 78    | 1/11/2018 | Yard                        | Replace brick at wall pack behind generator - currently excessive gap                          | Complete             |
| 70    | 1/11/2010 | Dumpster Pad and Mech.      | include brick at wan pack bening generator currently excessive gap                             | Complete             |
| 79    | 1/11/2018 | Yard                        | Remove protective tape from stair nosing and clean concrete                                    | Complete             |
| 75    | 1/11/2010 | Dumpster Pad and Mech.      | Nemove protective tape from stail hosing and clean concrete                                    | Complete             |
| 81    | 1/11/2018 | Yard                        | Clean brick adjacent to mech. Room door  | Incomplete           |
| 01    | 1/11/2010 | Dumpster Pad and Mech.      | cican brick adjacent to meen. Noom door  | incomplete           |
| 82    | 1/11/2018 | Yard                        | Clean precast above mech. Room door  | Incomplete           |
| 02    | 1/11/2010 | Dumpster Pad and Mech.      | Replace brick above mech. Room door where core drill has occurred and is now leaving a         | incomplete           |
| 83    | 1/11/2018 | Yard                        | void in the wall   | Complete             |
| 03    | 1/11/2018 | Dumpster Pad and Mech.      | Rework gates to a plumb condition - currently gates are racked in place - in particular gate   |                      |
| 84    | 1/11/2018 | Yard                        | at the S end   | Complete             |
| 04    | 1/11/2018 | Dumpster Pad and Mech.      | at the 3 end   | Complete             |
| 85    | 1/11/2018 | Yard                        | Repair or replace gate that's damaged at the top in front of transformer                       | Complete             |
| 63    | 1/11/2016 | Dumpster Pad and Mech.      | Repair of replace gate that's damaged at the top in nont of transformer                        | Complete             |
| 87    | 1/11/2018 | Yard                        | Verify empty conduit adjacent to retaining wall  | Defer to Architect   |
| 0/    | 1/11/2016 | Dumpster Pad and Mech.      | Verify empty conduit adjacent to retaining waii  | Defer to Architect   |
| 00    | 1/11/2010 | ·                           | Dravide caulking at control joint at the CW corner of curport bldg                             | Defer to Architect   |
| 88    | 1/11/2018 | Yard Dumpster Pad and Mech. | Provide caulking at control joint at the SW corner of support bldg.                            | Delet to Alchitect   |
| 90    | 1/11/2018 | Yard                        | Complete work at the dirt island SW corner of support bldg. and establish grass                | Complete             |
| 90    | 1/11/2016 | Dumpster Pad and Mech.      | Complete work at the unit island 5w comer or support blug, and establish glass                 | Complete             |
| 01    | 1/11/2018 |                             | Raise cleanout within asphalt area on W side of sally port and install cleanout cover          | Complete             |
| 91    | 1/11/2018 | Yard Dumpster Pad and Mech. | maise cleanout within aspiralt area on wisher of sally port and install cleaffout cover        | Complete             |
| 0.3   | 1/11/2010 | ·                           | Drovide electroplate between bldg steel and brief at OUD of cells next                         | Defer to Architect   |
| 93    | 1/11/2018 | Yard Dumpster Pad and Mech. | Provide closure plate between bldg. steel and brick at OHD of sally port                       | Defer to Architect   |
| O.F.  | 1/11/2010 | •                           | Daint gae line gray  | Defer to Architect   |
| 95    | 1/11/2018 | Yard Dumpster Pad and Mech. | Paint gas line gray  | Defer to Architect   |
| 0.0   | 1/11/2010 | •                           |  | D                    |
| 96    | 1/11/2018 | Yard                        | Adjust gas line so it is not touching the handrail   | By gas company       |

| 98  | 1/11/2018   | South Building Elevation | Rework all metal panels above at the canopy above the double doors   | Defer to Architect    | $\neg$           |
|-----|-------------|--------------------------|--|-----------------------|------------------|
| 102 | 1/11/2018   | South Building Elevation | Clean louvre   | Complete              |                  |
| 103 | 1/11/2018   | South Building Elevation | Repaint door signage - fire exit door - do not block - currently painting is blurry  | Complete              |                  |
| 104 | 1/11/2018   | South Building Elevation | Clean all brick work at the end of main bldg.  | Complete              |                  |
| 105 | 1/11/2018   | South Building Elevation | Provide missing lock at sprinkler room door  | Incomplete            |                  |
| 106 | 1/11/2018   | South Building Elevation | Patch and repair brick work where conduit for electric meter penetrates the bldg.  | Complete              |                  |
| 100 | 1/11/2010   | South Building Elevation | Adjust the end cap of the aluminum panel eyebrow canopy at the upper level - currently   | complete              |                  |
| 107 | 1/11/2018   | South Building Elevation | the end cap panel is cockeyed  | Incomplete            |                  |
| 107 | 1/11/2010   | South Building Elevation | the end cup paner is cockeyed  | meompiete             |                  |
| 108 | 1/11/2018   | South Building Elevation | Rework coping on the left hand side of the stair tower where it meets the aluminum panel   | Defer to Architect    |                  |
| 100 | 1/11/2010   | South Building Elevation | Adjust the height of the "haggard" ground box outside of the service corridor - currently it   | Defer to 7 wernteet   |                  |
| 109 | 1/11/2018   | South Building Elevation | is sitting low or below the asphalt surface  | Complete              |                  |
| 110 | 1/11/2018   | South Building Elevation | Clean precast all locations on bldg.   | Defer to Architect    |                  |
| 111 | 1/11/2018   | South Building Elevation | Remove debris from steel lintels and paint steel lintels at all door locations   | Defer to Architect    | _                |
| 111 | 1/11/2010   | South Building Elevation | When reworking canopy above sprinkler room and service corridor, extend canopy tight   | Defer to Architect    |                  |
| 112 | 1/11/2018   | South Building Elevation | to brick on right side to eliminate the 1 1/2" caulk joint   | Complete              |                  |
| 112 | 1/11/2010   | Dumpster Pad and Mech.   | to briok of right side to climinate the 1 1/2 addition.  | complete              |                  |
| 113 | 1/11/2018   | Yard                     | Replace damage to gate at this end of generator enclosure  | Complete              |                  |
| 113 | 1, 11, 2010 | Dumpster Pad and Mech.   | replace damage to gate at any end of generator envisore  | oo.npiete             | =                |
| 114 | 1/11/2018   | Yard                     | Patch overcut asphalt at the removal bollards  | Complete              |                  |
| 117 | 1/11/2010   | Security Fencing at Rear | Tatel overeus asphalt at the removal boliards  | complete              |                  |
| 118 | 1/11/2018   | Yards                    | Verify proper bolt security gates - currently bolts extend up at the driving surface   | Defer to Architect    |                  |
| 110 | 1/11/2010   | Security Fencing at Rear | Verify proper son security gates carrently sons extend up at the arriving sarrace  | Defer to 7 wernteet   |                  |
| 119 | 1/11/2018   | Yards                    | Clean mortar joint at all inside corners of security fencing   | Defer to Architect    |                  |
| 113 | 1/11/2010   | raras                    | Move the lightening protection conduits at the fuel tank storage to the inside of enclosure  | Defer to Architect    |                  |
| 120 | 1/11/2018   | Fuel Tank Storage        | as opposed as it is currently mounted on ext.  | Complete              |                  |
| 121 | 1/11/2018   | Fuel Tank Storage        | Clean all CMU within the fuel tank enclosure   | Complete              |                  |
| 122 | 1/11/2018   | Fuel Tank Storage        | PU masonry within fuel tank enclosure  | Complete              |                  |
| 123 | 1/11/2018   | Fuel Tank Storage        | Remove mud off walls of fuel tank enclosure  | Complete              |                  |
| 125 | 1/11/2018   | Fuel Tank Storage        | Remove overspray of hydro seed at the brick work on E side of fuel tank enclosure  | Incomplete            |                  |
| 120 | 1/11/2010   | Security Fencing at Rear | Transfer of the spray of the state of the st | oompiete              |                  |
| 126 | 1/11/2018   | Yards                    | Remove silt and over seed at all brick piers and chain-link fence locations  | Defer to Architect    |                  |
| 120 | 1/11/2010   | Security Fencing at Rear | Cut all metal post tops at chain-link fence that extends up to the precast to just above the   | Berei te / il emitest |                  |
| 127 | 1/11/2018   | Yards                    | horizontal top rail to ensure post cap are below the precast   | Incomplete            |                  |
|     | _,,         | Security Fencing at Rear |  |                       |                  |
| 128 | 1/11/2018   | Yards                    | Replace damaged brick at pier at the SE corner and the 1st pier on the S end heading N   | Complete              |                  |
|     | , ,         | Security Fencing at Rear |  | '                     |                  |
| 129 | 1/11/2018   | Yards                    | Repair damaged protective coating at gates and post on the E   | Complete              |                  |
|     | . ,         | Security Fencing at Rear | Excessive gap between finish grade and chain-link fencing, 2nd panel to the left of right  | '                     |                  |
| 130 | 1/11/2018   | Yards                    | hand gate  | Incomplete            | will complete by |
|     | . ,         | Security Fencing at Rear | Fence panel 6, 7 8 , 10 on the E security wall have excessive gap between grade and  | '                     |                  |
| 131 | 1/11/2018   | Yards                    | bottom rail of fence   | Incomplete            | will complete by |
|     | . ,         | Security Fencing at Rear | Adjust ALL Chain Link Fences to provide a Maximum 2" between finish grade and fence  | '                     |                  |
| 132 | 1/11/2018   | Yards                    | fabric (323113-3.1.I - page 5)   | Incomplete            | will complete by |
|     | . ,         | Security Fencing at Rear |  | '                     |                  |
| 133 | 1/11/2018   | Yards                    | Remove paint from brick pier on the N - 1st pier from the gate wall  | Defer to Architect    |                  |
|     | , -,        | Security Fencing at Rear | 1  |                       |                  |
| 137 | 1/11/2018   | Yards                    | Provide caulking at joint between concrete and brick pier and brick wall   | Complete              |                  |
|     | , ,         | Security Fencing at Rear |  | '                     |                  |
| 138 | 1/11/2018   | Yards                    | Provide caps at stop posts installed at the end of security gate track   | Incomplete            |                  |
|     | , -,        | Security Fencing at Rear | 1 1 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2  |                       |                  |
| 139 | 1/11/2018   | Yards                    | Remove concrete splatter from man door on the inside and repaint   | Complete              |                  |
|     | , -,        | Security Fencing at Rear |  | <u> </u>              |                  |
| 140 | 1/11/2018   | Yards                    | Repair damaged brick at man door jamb  | Complete              |                  |
|     | _,,0        |                          | 1  |                       |                  |

| Ι Γ        |                        | Security Fencing at Rear  |            |   |                        |
|------------|------------------------|---------------------------|------------|---|------------------------|
| 141        | 1/11/2018              | Yards                     |            | Install door position switch at man door  | Complete               |
| 144        | 1/25/2018              | Support Bldg              |            | Install thresholds at ext. doors  | Complete               |
| 146        | 1/25/2018              | Support Bldg              |            | Caulk door frames to CMU and lintels to CMU   | Complete               |
| 110        | 1,23,2010              | Support Blug              |            | Provide weather stripping at OHCD currently light bleed and top, sides and bottom of            | complete               |
| 148        | 1/25/2018              | Support Bldg              |            | doors   | Complete               |
| 149        | 1/25/2018              | Support Bldg              |            | Verify proper operation of the climovent system   | Defer to Architect     |
| 158        | 1/25/2018              | Support Bldg              |            | Paint all conduit and piping in space   | Incomplete             |
| 159        | 1/25/2018              | Support Bldg              |            | Ensure proper operation of OHDs   | Defer to Architect     |
| 100        | 1,20,2010              | 54P511 5146               |            | Recoat the floor - currently where the floor has been cut for the vehicle sensor is done in     | Deter to / ii etiiteet |
| 160        | 1/25/2018              | Support Bldg              |            | an unworkman like manner and is unacceptable  | Defer to Architect     |
|            | , ,                    | 11 0                      |            | Remove floor drain cover under wash station - currently epoxy paint has covered the             |                        |
| 161        | 1/25/2018              | Support Bldg              |            | access  | Defer to Architect     |
| 162        | 1/25/2018              | Support Bldg              |            | Remove protective film from SF above CD   | Defer to Architect     |
| 164        | 1/25/2018              | Support Bldg              |            | Explain why excessive gap under CD on the N end   | Defer to Architect     |
| 167        | 1/25/2018              | Support Bldg              |            | PU drywall at joint between roof structure and wall prior to painting                           | Complete               |
| 168        | 1/25/2018              | Support Bldg              |            | Verify proper operation of all systems  | Defer to Architect     |
| 170        | 1/25/2018              | Support Bldg              |            | Provide soap CMU at unused gas penetration in wall  | Defer to Architect     |
| 172        | 1/25/2018              | Support Bldg              |            | Extend CJ at CMU adjacent to storage room door 176 to finish floor                              | Defer to Architect     |
| 174        | 1/25/2018              | Support Bldg              |            | Paint all exposed ductwork in space   | Incomplete             |
| 175        | 1/25/2018              | Support Bldg              |            | Extend CJ to finish floor adjacent to the kennel door   | Defer to Architect     |
| 176        | 1/25/2018              | Support Bldg              |            | Paint steel columns all the way to roof structure   | Complete               |
| 177        | 1/25/2018              | Support Bldg              |            | Install control mechanism to the OHCD at the S end  | Defer to Architect     |
| 186        | 1/25/2018              |                           | 179        | Paint exposed conduits at ceiling   | Complete               |
| 190        | 1/25/2018              |                           | 179        | Seal door frame to finish floor   | Complete               |
| 193        | 1/25/2018              |                           | 178        | Sand smooth doorframe and repaint door frame and door   | Complete               |
| 195        | 1/25/2018              |                           | 178        | Remove paint from wall runner at ceiling  | Complete               |
|            |                        |                           |            | Replace gates at kennel - currently gates are too wide causing the hinge side to project        |                        |
| 199        | 1/25/2018              |                           | 178        | out   | Complete               |
|            |                        |                           |            | Verify electrical outlet adjacent to the dog bathing station - currently there is a cover plate |                        |
| 206        | 1/25/2018              |                           | 178        | installed   | Complete               |
| 207        | 1/25/2018              |                           | 178        | Paint CMU under dog bathing station   | Complete               |
| 208        | 1/25/2018              |                           | 178        | Install door stop   | Complete               |
| 212        | 1/25/2018              |                           | 177        | Seal all wall penetrations at CMU prior to painting   | Complete               |
| 217        | 1/25/2018              |                           | 177        | Provide mortar at head joint above wall base on back wall                                       | Defer to Architect     |
| 222        | 1/25/2018              |                           | 177        | Paint conduits  | Complete               |
| 223        | 1/25/2018              |                           | 177        | Provide engraved cover plates at electrical devices and   | Complete               |
|            |                        |                           |            | GC storing materials in this room - additional items may be discovered once GC has              | - 4                    |
| 224        | 1/25/2018              |                           | 177        | vacated space   | Defer to Architect     |
| 226        | 1/25/2018              |                           | 176        | Paint housekeeping pad  | Complete               |
| 228        | 1/25/2018              |                           | 176        | Provide missing CMU at plumbing for the wall hydrant  | Defer to Architect     |
| 231        | 1/25/2018              |                           | 176        | Complete electrical in corner   | Defer to Architect     |
| 232        | 1/25/2018              |                           | 1/6        | Paint conduits  The use health earth a altraniv is fire treated a currently no labels shown     | Complete               |
| 234        | 1/25/2018              |                           | 176<br>176 | Ensure backboard for the altronix is fire treated - currently no labels shown                   | Defer to Architect     |
| 236        | 1/25/2018              |                           |            | Paint saddles at piping   | Complete               |
| 237<br>238 | 1/25/2018<br>1/25/2018 |                           | 176<br>176 | Paint sprinkler piping Paint all thread and Kendorf metal                                       | Complete Complete      |
| 245        | 1/25/2018              | Support Bldg              | 1/0        | Explain why the control sensors at the S end - conduit runs through the fire strobe             | Defer to Architect     |
| 245        | 1/25/2018              | Support Bldg Support Bldg | +          | Verify proper warning strobes at OHDs - currently they are fire strobes                         | Defer to Architect     |
| 248        | 1/25/2018              | S of Support Bldg         | +          | Paint electrical conduit to match adjacent surface  | Complete               |
| 254        | 1/25/2018              | S of Support Bldg         | +          | Wash down brick   | Complete               |
| 256        | 1/25/2018              | S of Support Bldg         | +          | Adjust metal panels reveals currently they are not uniformed                                    | Complete               |
| 257        | 1/25/2018              | S of Support Bldg         | -          | Rework corners at overhang - excessive gaps   | Complete               |
| 259        | 1/25/2018              | E of Support Bldg         | -          | Provide caulking at perimeter of louvre   | Defer to Architect     |
| 261        | 1/25/2018              | E of Support Bldg         | +          | Adjust metal panels reveals currently they are not uniformed                                    | Defer to Architect     |
| ZU1        | 7/ 27/ 2010            | r or anbhorr ping         |            | projust metal panels reveals cultering they are not uniformed                                   | Deter to Attilitett    |

Painted at 8' wall

Painted at 8'

| 262        | 1/25/2018              | E of Support Bldg                        | Rework mortar at top course above flashing and head joints   | Defer to Architect     |
|------------|------------------------|--|--|------------------------|
| 264        | 1/25/2018              | E of Support Bldg                        | Paint conduits to match brick color  | Complete               |
| 204        | 1/23/2010              | L of Support Blug                        | Replace panels at gable overhang: currently 2 joints are vertical, the remainder of joints   | complete               |
| 265        | 1/25/2018              | E of Support Bldg                        | follow slope of roof.  | Defer to Architect     |
| 268        | 1/25/2018              | N of Support Bldg                        | Rework asphalt in area - currently patches are unacceptable  | Defer to Architect     |
| 269        | 1/25/2018              | N of Support Bldg                        | Adjust metal panels reveals currently they are not uniformed   | Defer to Architect     |
| 270        | 1/25/2018              | N of Support Bldg                        | Rework brick work at top course adjacent to the flashing and vertical head joints  | Defer to Architect     |
| 271        | 1/25/2018              | N of Support Bldg                        | Remove unused gas penetration and provide brick  | Defer to Architect     |
|            | 1,20,2010              | ., ., ., ., ., ., ., ., ., ., ., ., ., . | The state of the s | Berei te / Wernteet    |
| 272        | 1/25/2018              | N of Support Bldg                        | Clean underside of canopy - if staining cannot be removed then paint canopy decking  | Defer to Architect     |
| 273        | 1/25/2018              | N of Support Bldg                        | Sand canopy steel and repaint  | Defer to Architect     |
| 274        | 1/25/2018              | N of Support Bldg                        | Paint gas line   | Defer to Architect     |
| 275        | 1/25/2018              | N of Support Bldg                        | Provide caulk joint between steel and brick under canopy   | Complete               |
| 276        | 1/25/2018              | N of Support Bldg                        | Verify gutter at canopy - currently sagging in middle where joints occur   | Incomplete             |
| 277        | 1/25/2018              | N of Support Bldg                        | Paint downspout boots  | Complete               |
| 278        | 1/25/2018              | N of Support Bldg                        | Provide closure steel at jambs of the CD to close off gap between brick and steel  | Defer to Architect     |
| 279        | 1/25/2018              | N of Support Bldg                        | Remove paint from brick behind the man door  | Complete               |
| 280        | 1/25/2018              | N of Support Bldg                        | Clean all brick work   | Complete               |
| 281        | 1/25/2018              | N of Support Bldg                        | Paint conduits at security gates to match brick  | Complete               |
| 282        | 1/25/2018              | N of Support Bldg                        | Paint conduits in platform at security gate motor black to match gate  | Complete               |
| 283        | 1/25/2018              | N of Support Bldg                        | Repaint steel at canopy  | Complete               |
| 286        | 1/25/2018              | N of Support Bldg                        | Seal gaps in gutter of canopy - currently gaps at several locations  | Complete               |
| 288        | 1/25/2018              | N of Support Bldg.                       | Metal at top right of the window is discolored from the remaining metal - replace  | Defer to Architect     |
| 290        | 1/25/2018              | E Elev. Main Bldg                        | Provide closure plate at CD to close gap between brick and steel   | Complete               |
| 295        | 1/25/2018              | E Elev. Main Bldg                        | Provide caulking at perimeter of louvre above man door   | Defer to Architect     |
| 298        | 1/25/2018              | E Elev. Main Bldg                        | Adjust metal panels reveals currently they are not uniformed   | Defer to Architect     |
| 300        | 1/25/2018              | E Elev. Main Bldg                        | Provide weather striping at top of door  | Complete               |
| 303        | 1/25/2018              | E Elev. Main Bldg                        | Paint downspout boot   | Complete               |
| 304        | 1/25/2018              | E Elev. Main Bldg                        | Replace damage brick left hand side of OHD at the bottom   | Defer to Architect     |
| 308        | 1/25/2018              | E Elev. Main Bldg                        | Paint conduit to match brick work at the left hand of main bldg.   | Complete               |
| 309        | 1/25/2018              | E Elev. Main Bldg                        | Adjust metal panels reveals currently they are not uniformed   | Defer to Architect     |
| 311        | 1/25/2018              | E Elev. Main Bldg                        | Seal gaps and holes in decking   | Complete               |
| 313        | 1/25/2018              | E Elev. Main Bldg                        | Sand smooth canopy steel and repaint (Both Canopies)   | Defer to Architect     |
| 315        | 1/25/2018              | E Elev. Main Bldg                        | Explain unused conduit penetrations at bldg.   | Defer to Architect     |
| 316        | 1/25/2018              | E Elev. Main Bldg                        | Provide caulking at perimeter of AL SF   | Complete               |
| 317        | 1/25/2018              | E Elev. Main Bldg                        | Provide caulking at perimeter of louvres in wall   | Defer to Architect     |
| 318        | 1/25/2018              | E Elev. Main Bldg                        | Adjust sun shade fins to all match same angle  | Defer to Architect     |
| 321        | 1/25/2018              | E Elev. Main Bldg                        | Remove protective film from cleanouts in sidewalk  | Defer to Architect     |
| 323        | 1/25/2018              | E Elev. Main Bldg                        | Paint lintels at windows   | Defer to Architect     |
| 325        | 1/25/2018              | E Elev. Main Bldg                        | Excessive gap at right end of soffit CW system adjacent to the overflow  | Defer to Architect     |
| 326        | 1/25/2018              | E Elev. Main Bldg                        | Cut EJ material and provide caulking at all site concrete  | Defer to Architect     |
| 327        | 1/25/2018              | E Elev. Main Bldg                        | Install mortar or caulk at vertical joints at precast per contract   | Defer to Architect     |
| 329        | 1/25/2018              | E Elev. Main Bldg                        | Rework metal panels at first punch Curtain Wall, right side of large CW system  Jambs at punch windows are not perpendicular to the window frame system - they splay   | Defer to Architect     |
| 220        | 1/25/2010              | E Flore Main Dist-                       |  | Defente Anchitect      |
| 330        | 1/25/2018              | E Elev. Main Bldg                        | in and out - correct   | Defer to Architect     |
| 332        | 1/25/2018              | E Elev. Main Bldg                        | Note: All comments for canopies above apply to All canopies on this project.  Explain unused conduit penetrations at bldg cut these conduits back flush and cap at   | Defer to Architect     |
| 222        | 1/25/2019              | E Elev. Main Bldg                        |  | Defer to Architect     |
| 333<br>334 | 1/25/2018              | E Elev. Main Bldg                        | brick  PU mortar at right hand side of break room window jamb  | Complete               |
| _          | 1/25/2018              |  | Damaged metal panel under 3rd window from the N end  | Defer to Architect     |
| 337<br>338 | 1/25/2018              | E Elev. Main Bldg<br>E Elev. Main Bldg   | PU mortar joints in brick work various locations   | Defer to Architect     |
| _          | 1/25/2018<br>1/25/2018 | E Elev. Main Bldg                        |  |                        |
| 339<br>343 | 1/25/2018              | N Elev. Main Bldg                        | Paint conduits in platform at security gate motor black to match gate  Repair or replace damage precast at head of window  | Complete<br>Incomplete |
| 344        | 1/25/2018              | N Elev. Main Bldg                        | Provide mortar or caulking at vertical joints in precast   | Complete               |
| 346        | 1/25/2018              | N Elev. Main Bldg                        | Damaged metal panels at Stairtower   | Defer to Architect     |
| 5+0        | 7/ 57/ 5010            | N LICV. MIGHT DIUE                       | Damaged metal panels at stantower  | Deter to Attilitett    |

Will be fixed by c

With canopy

| 347 | 1/25/2018 | E Elev. Main Bldg. |     | Repair gap in reveal at 1st punch window from the CW system right hand side ????             | Defer to Architect |
|-----|-----------|--------------------|-----|--|--------------------|
| 349 | 1/25/2018 | N Elev. Main Bldg. |     | Replace cracked concrete at bottom of stairs   | Incomplete         |
| 350 | 1/25/2018 | N Elev. Main Bldg. |     | Install missing device at metals panels at stairwell currently open electrical               | Defer to Architect |
| 352 | 1/25/2018 | N Elev. Main Bldg. |     | Provide caulking at perimeter of punch window at NW corner                                   | Complete           |
| 354 | 1/25/2018 | N Elev. Main Bldg. |     | Paint lintel at window heads (Typical at all Lintel locations on this project)               | Complete           |
| 356 | 1/25/2018 | N Elev. Main Bldg. |     | Extend CJ to grade between window and stairwell  | Complete           |
| 357 | 1/25/2018 | N Elev. Main Bldg. |     | Cut and remove unused conduit in corner adjacent to stairwell                                | Complete           |
|     |           |                    |     | Cut down conduits to grade and provide cleanout cap and verify if concrete is required at    |                    |
| 358 | 1/25/2018 | E Elev. Main Bldg  |     | these locaitons  | Complete           |
| 361 | 1/25/2018 | E Elev. Main Bldg  |     | Excessive gap at left end window   | Complete           |
| 362 | 1/25/2018 | E Elev. Main Bldg  |     | Excessive gap at first alcove left hand on left side   | Complete           |
| 363 | 1/25/2018 | E Elev. Main Bldg  |     | Caulk joint between soffit and brick pilasters   | Complete           |
| 365 | 1/25/2018 | E Elev. Main Bldg  |     | Adjust sun shading to point at same angle at all locations                                   | Defer to Architect |
| 366 | 1/25/2018 | E Elev. Main Bldg  |     | Rework metal at top of window frames across the front  | Defer to Architect |
| 367 | 1/25/2018 | E Elev. Main Bldg  |     | Metal work under windows not pluumb and level - rework                                       | Defer to Architect |
| 368 | 1/25/2018 | E Elev. Main Bldg  |     | Excessive gap between metal panel and window frame throughout                                | Defer to Architect |
| 372 | 1/25/2018 | E Elev. Main Bldg  |     | Rework joint between precast sill and brick work   | Defer to Architect |
| 373 | 1/25/2018 | E Elev. Main Bldg  |     | Clean lambs tongue overflow on left hand side of entry                                       | Complete           |
| 375 | 1/25/2018 | E Elev. Main Bldg  |     | Explain pipe penetration below the wall hydrant left hand side of entry                      | Defer to Architect |
| 376 | 1/25/2018 | E Elev. Main Bldg  |     | Rework metal panels at entry at soffit currently significant slopes is unacceptable          | Defer to Architect |
| 378 | 1/25/2018 | E Elev. Main Bldg  |     | Rework entry canopy currently significant bow on right side                                  | Defer to Architect |
| 379 | 1/25/2018 | E Elev. Main Bldg  |     | Rework all end caps at all eyebrow metal panel installation                                  | Defer to Architect |
| 380 | 1/25/2018 | E Elev. Main Bldg  |     | Provide continous crimp at coping  | Defer to Architect |
| 381 | 1/25/2018 | E Elev. Main Bldg  |     | Rework metal at entry where canopy meets metal panels  | Defer to Architect |
| 382 | 1/25/2018 | E Elev. Main Bldg  |     | Adjust metal panels reveals currently they are not uniformed                                 | Defer to Architect |
| 383 | 1/25/2018 | E Elev. Main Bldg  |     | Redo blue reveal at vertical metal panels  | Defer to Architect |
| 384 | 1/25/2018 | E Elev. Main Bldg  |     | Re insall precast at right hand side of vertical blue metal panels                           | Defer to Architect |
|     |           |                    |     | Rework precast installation at top of pilasters currently projectiong excessively over brick |                    |
| 385 | 1/25/2018 | E Elev. Main Bldg  |     | work   | Defer to Architect |
| 386 | 1/25/2018 | E Elev. Main Bldg  |     | Provide caulking between CW system and brick work- all joint locations                       | Defer to Architect |
| 395 | 1/25/2018 | E Elev. Main Bldg  |     | Caulk joint at end of steel lintel where it meets the brick work                             | Complete           |
| 396 | 1/25/2018 | E Elev. Main Bldg  |     | Caulk joint between lintel and brick pilasters   | Complete           |
| 401 | 1/25/2018 | E Elev. Main Bldg  |     | Damaged metal panels at variuos locaitons - replace panels                                   | Defer to Architect |
| 402 | 1/25/2018 | E Elev. Main Bldg  |     | Rework spline at metal panels  | Defer to Architect |
| 403 | 1/25/2018 | E Elev. Main Bldg  |     | Adjust metal panels reveals currently they are not uniformed                                 | Defer to Architect |
| 405 | 1/25/2018 | E Elev. Main Bldg  |     | Repaint gas line gray and adjust so as not to touch metal handrail                           | Defer to Architect |
| 406 | 1/25/2018 | E Elev. Main Bldg  |     | Rework overhang at the S end - at end of overhang  | Defer to Architect |
| 407 | 1/25/2018 | E Elev. Main Bldg  |     | Provide caulking at perimeter of all window frames   | Complete           |
| 408 | 1/25/2018 | Gen                |     | Clean all precast removing silt from precast - numerous locations                            | Defer to Architect |
| 410 | 1/25/2018 | E Elev. Main Bldg  |     | Rework metal drip edge under precast at front plaza walls                                    | Defer to Architect |
| 411 | 1/25/2018 | E Elev. Main Bldg  |     | Clean brick work at plaza walls  | Incomplete         |
| 412 | 1/25/2018 | E Elev. Main Bldg  |     | Replace damaged precsast where electriciaan installed electrical devices at plaza            | Complete           |
| 413 | 1/25/2018 | Gen                |     | Install missing caulking at joints in precast  | Defer to Architect |
| 415 | 1/25/2018 | E Elev. Main Bldg  |     | Rework overhang metal - currently bowed significantly above entry door                       | Defer to Architect |
| 416 | 1/25/2018 | Front Plaza        |     | Remove exposed CMU at the bottom of the stairs at the front plaza and install brick          | Complete           |
| 418 | 1/25/2018 | Elevators          |     | Not inspected inoperable.  | Defer to Architect |
|     |           |                    |     | Ensure overcurrent protective devices settings have been made by authorized service          |                    |
| 419 | 1/25/2018 | General            | GEN | representative.  | Complete           |
|     |           |                    |     | D : 1 ADOC   1   1   1   1   1   1   1   1   1   |                    |
|     |           |                    |     | Provide ARC Flash Hazard warning labels on all panelboards and disconnects ensure the        |                    |
|     |           |                    |     | label provides the following information taken from the arc-flash hazard analysis.           |                    |
|     |           |                    |     | Location, nominal voltage, Flash protection boundary, hazard risk category, incident         |                    |
| 420 | 1/25/2018 | General            |     | energy, working distance, engineering report number-revision number and issue date.          | Complete           |
| 421 | 1/25/2018 | General            | GEN | Complete all Cx activities / demonstrations required.  | Complete           |

| 425 | 1/25/2018   | General |           | GEN  | Provide electrical raceway identification on conduits not utilizing colorized conduit.   | Defer to Architect          |                   |
|-----|-------------|---------|-----------|------|--|-----------------------------|-------------------|
| 123 | 1/23/2010   | General |           | OLIV | Provide engraved laminate tags for all electrical equipment. EMON DMON meters, ATS,  | Defer to 7 il criticet      |                   |
| 426 | 1/25/2018   | General |           | GEN  | Transformers, disconnects, etc.  | Complete                    |                   |
| 427 | 1/25/2018   | General |           | GEN  | Complete TAB   | Complete                    |                   |
| 428 | 1/25/2018   | General |           | GEN  | Complete HVAC water treatment analysis   | Complete                    |                   |
| 429 | 1/25/2018   | General |           | GEN  | Complete and confirm water sterilization of domestic water is complete.  | Complete                    |                   |
| 430 | 1/25/2018   | General |           | GEN  | Provide engraved laminate tags for concealed electrical equipment  | N/A                         |                   |
| 433 | 1/25/2018   | General | Site      | GLIV | FDC is not chrome as specified.  | Incomplete                  | Confirm           |
| 433 | 1/23/2010   |         | Site      |      | Exterior receptacles have the incorrect while in use cover. Replace all with Die Cast  | incomplete                  | Commi             |
| 434 | 1/25/2018   |         | Site      |      | Aluminum as specified and approved.  | Complete                    |                   |
| 434 | 1/25/2018   |         | Site      |      | Remove tape and confirm operation of sump pump drain. Provide splash block.  | Complete                    |                   |
| 430 | 1/23/2016   |         | Site      |      | Remove tape and commit operation of sump pump drain. Provide splash block.   | Complete                    |                   |
| 427 | 1 /25 /2010 |         | C:+a      |      | Demonstrated of height of the state of the side of the side of the state of the sta | Camanlata                   |                   |
| 437 | 1/25/2018   |         | Site      |      | Remove all conduits/piping around permitted of building utilized for temporary services.  Electrical handholes to be flush with ground.  | Complete Defer to Architect |                   |
| 438 | 1/25/2018   |         | Site      |      |  |                             |                   |
| 441 | 1/25/2018   |         | Site      |      | Several Light poles are not plug. Shim and correct.  | Defer to Architect          |                   |
| 442 | 1/25/2018   |         | Site      |      | Light pole base skirts are not sitting flush to concrete.  | Defer to Architect          | $\dashv$          |
| 443 | 1/25/2018   |         | Site      |      | Remove light pole bolt cut ends from grass.  Weatherized enclosures receptacle covers shall be stainless, with engraved panelboard   | Defer to Architect          | $\dashv$          |
|     | . / /       |         |           |      |  |                             |                   |
| 444 | 1/25/2018   |         | Site      |      | and circuit.   | N/A                         | Labels can be ins |
| 445 | 1/25/2018   |         | Site      |      | Bolt skirt missing from southern 4 way light pole.   | Incomplete                  | FLBE ordered      |
| 448 | 1/25/2018   |         | Site      |      | repaved drive lisle to remove noticeable patches.  | On Separate List            |                   |
| 449 | 1/25/2018   |         | Site      |      | Paint gas line   | Defer to Architect          |                   |
| 450 | 1/25/2018   |         | Site      |      | Polish downspout boots   | Complete                    |                   |
| 451 | 1/25/2018   |         | Site      |      | paint all exposed electrical conduit same color as structure.  | Complete                    |                   |
| 452 | 1/25/2018   |         | Site      |      | Plug un used conduits  | Complete                    |                   |
| 453 | 1/25/2018   |         | Site      |      | Lightning conductor exposed and unattached near bike rack. Ground/complete.  | Defer to Architect          |                   |
| 454 | 1/25/2018   |         | Site      |      | Site light near fuel station. Half of the distribution array is not functioning.   | Defer to Architect          |                   |
|     |             |         | Support   |      |  |                             |                   |
| 455 | 1/25/2018   |         | Bldg. Bay |      | Engraved Laminate tags for disconnects, etc.   | N/A                         |                   |
|     |             |         | Support   |      |  |                             |                   |
| 456 | 1/25/2018   |         | Bldg. Bay |      | Paint all exposed mechanical piping and ductwork.  | Complete                    |                   |
|     |             |         | Support   |      |  |                             |                   |
| 457 | 1/25/2018   |         | Bldg. Bay |      | Remove all tape / rust and concrete from drains and restore factory finish.  | Complete                    |                   |
|     |             |         | Support   |      |  |                             |                   |
| 462 | 1/25/2018   |         | Bldg. Bay |      | Replace burned out overhead lighting   | Incomplete                  |                   |
|     |             |         | Support   |      | Provide engraved panelboard and circuit on all receptacles. This included overhead   |                             |                   |
| 463 | 1/25/2018   |         | Bldg. Bay |      | receptacles.   | N/A                         |                   |
|     |             |         | Support   |      |  |                             | $\neg$            |
| 465 | 1/25/2018   |         | Bldg. Bay |      | Grout all sleeves to CMU and pack annular space  | Defer to Architect          |                   |
|     |             |         | Support   |      |  |                             |                   |
| 466 | 1/25/2018   |         | Bldg. Bay |      | Receptacle under keypad not provided with while in use cover   | Incomplete                  | Confirm           |
|     | · · ·       |         | Support   |      |  |                             | 7                 |
| 467 | 1/25/2018   |         | Bldg. Bay |      | why has 1/2" conduit been utilized? Specs call for a minimum of 3/4" conduit.  | Defer to Architect          |                   |
| 469 | 1/25/2018   |         | 179       |      | Grout all sleeves to CMU and pack annular space  | Defer to Architect          | ┪                 |
| 471 | 1/25/2018   |         | 179       |      | Label J box covers   | Incomplete                  | ┪                 |
| 473 | 1/25/2018   |         | 178       |      | Receptacle not provided under k-9 bath   | Complete                    | ┪                 |
| 474 | 1/25/2018   |         | 178       |      | Receptacle under k-9 bath to have while in use cover   | Complete                    | ┪                 |
| 476 | 1/25/2018   |         | 178       |      | Unused coach rod plates left on CMU remove/ patch holes.   | Defer to Architect          | ┪                 |
| 477 | 1/25/2018   |         | 178       |      | Provide escutcheons where pipes penetrate ceiling  | Complete                    | ╡                 |
| 477 | 1/25/2018   |         | 178       |      | Light switch is to be with Occ. Sensor.  | Complete                    | ╡                 |
| 483 | 1/25/2018   |         | 177       |      | Provide extension handles on all valves.   | Defer to Architect          | $\dashv$          |
| 485 | 1/25/2018   |         | 177       |      | Fully apply color identification on conduits.  | Incomplete                  | $\dashv$          |
| 487 |             |         | 176       |      | Rework and request reinspection.   | <u> </u>                    | $\dashv$          |
| 40/ | 1/25/2018   |         | 1/0       |      | Inework and request remspection.   | Defer to Architect          |                   |

|     |           |           | Panel UP3 - Circuit arrangement does not match contract documents. Typed panelboard                                   |                         |
|-----|-----------|-----------|---|-------------------------|
|     |           |           | schedule not provided on card stock within sleeve, Provide ARC flash Warning label as                                 |                         |
|     |           |           | required. Spare breakers not left in on position. Panel is not accepted in current state.                             |                         |
| 488 | 1/25/2018 | 176       | Rework and request reinspection.  | Complete                |
|     |           |           | Plywood does not appear to be fire rated. Additionally plywood if fire treated labels have                            |                         |
| 489 | 1/25/2018 | 176       | been painted over.  | Defer to Architect      |
| 491 | 1/25/2018 | 176       | Provide nylon bushings on conduits.   | Incomplete              |
| 492 | 1/25/2018 | 176       | Complete wiring / piping and replace face shell   | Defer to Architect      |
| 493 | 1/25/2018 | 176       | Mechanical insulation is to cover all specialties.  | Defer to Architect      |
|     |           | Ext Sally | Lightning conductor has been installed exposed. Concealed conductor and conduit inside                                |                         |
| 494 | 1/25/2018 | port      | building.   | Defer to Architect      |
|     |           | Ext Fuel  | Lightning protection not concealed inside enclosure. This area was not submitted for                                  |                         |
| 495 | 1/25/2018 | Station   | approval of routing. Rework cabling to not drape across stone work.   | Defer to Architect      |
|     |           | Generator |   |                         |
| 496 | 1/25/2018 | yard      | Provide engraved laminate tag on disconnects  | N/A                     |
|     |           | Generator |   |                         |
| 498 | 1/25/2018 | yard      | Galv coat all cut ends of unistrut  | Complete                |
|     |           | Generator |   |                         |
| 499 | 1/25/2018 | yard      | Patch hole in brick at sally port   | Complete                |
|     |           |           | Panel H3 - Circuit arrangement does not match contract documents. Typed panelboard                                    |                         |
|     |           |           | schedule not provided on card stock within sleeve, Provide ARC flash Warning label as                                 |                         |
|     |           |           | required. Spare breakers not left in on position. Panel is not accepted in current state.                             |                         |
| 500 | 1/25/2018 | 180       | Rework and request reinspection.  Panel HM3 - Circuit arrangement does not match contract documents. Typed panelboard | Could not get into room |
|     |           |           |   |                         |
|     |           |           | schedule not provided on card stock within sleeve, Provide ARC flash Warning label as                                 |                         |
|     |           |           | required. Spare breakers not left in on position. Panel is not accepted in current state.                             |                         |
| 501 | 1/25/2018 | 180       | Rework and request reinspection.  | Could not get into room |
|     |           |           | Panel XH3 - Circuit arrangement does not match contract documents. Typed panelboard                                   |                         |
|     |           |           | schedule not provided on card stock within sleeve, Provide ARC flash Warning label as                                 |                         |
|     |           |           | required. Spare breakers not left in on position. Panel is not accepted in current state.                             |                         |
| 502 | 1/25/2018 | 180       | Rework and request reinspection.  | Could not get into room |
|     |           |           | Panel 2MLA - Circuit arrangement does not match contract documents. Typed panelboard                                  |                         |
|     |           |           | schedule not provided on card stock within sleeve, Provide ARC flash Warning label as                                 |                         |
|     |           |           | required. Spare breakers not left in on position. Panel is not accepted in current state.                             |                         |
| 503 | 1/25/2018 | 180       | Rework and request reinspection.  | Could not get into room |
| F04 | 1/25/2010 | 100       | Lobol all lighting contactors   | Cauld not got into      |
| 504 | 1/25/2018 | 180       | Label all lighting contactors   | Could not get into room |
| 505 | 1/25/2018 | 180       | Clean spilt system and pan  | Could not get into room |
|     | , , -     |           |   |                         |

|     |             |            | T   |                         |
|-----|-------------|------------|---|-------------------------|
| 506 | 1/25/2018   | 180        | Seal all conduits   | Could not get into room |
| 507 | 1/25/2018   | 180        | Paint gas piping  | Could not get into room |
| 307 | 1/23/2018   | 100        | r anti gas pipnig   | Could not get into room |
| 508 | 1/25/2018   | 180        | Provide new ductwork section where holes has been cut.                                      | Could not get into room |
| 300 | 1/23/2010   | 100        | Panel L3 - Circuit arrangement does not match contract documents. Typed panelboard          | could not get into room |
|     |             |            | schedule not provided on card stock within sleeve, Provide ARC flash Warning label as       |                         |
|     |             |            | required. Spare breakers not left in on position. Panel is not accepted in current state.   |                         |
| 509 | 1/25/2018   | 180        | Rework and request reinspection.  | Could not get into room |
|     | _,,         |            | Panel EL3 - Circuit "1" tripped, Circuit arrangement does not match contract documents.     | 8                       |
|     |             |            | Typed panelboard schedule not provided on card stock within sleeve, Provide ARC flash       |                         |
|     |             |            | Warning label as required. Spare breakers not left in on position. Panel is not accepted in |                         |
| 510 | 1/25/2018   | 180        | current state. Rework and request reinspection.   | Could not get into room |
|     |             |            |   |                         |
|     |             |            | Panel ML3 - Provide engraved laminate tag, Proper common trip breaker not provided          |                         |
|     |             |            | wire providing trip not acceptable. Circuit arrangement does not match contract             |                         |
|     |             |            | documents. Typed panelboard schedule not provided on card stock within sleeve, Provide      |                         |
|     |             |            | ARC flash Warning label as required. Spare breakers not left in on position. Panel is not   |                         |
| 511 | 1/25/2018   | 180        | accepted in current state. Rework and request reinspection.                                 | Could not get into room |
|     |             |            |   |                         |
| 512 | 1/25/2018   | 180        | Clean air compressor  | Could not get into room |
|     |             |            |   |                         |
| 513 | 1/25/2018   | 180        | Complete BAS work   | Could not get into room |
|     |             |            |   |                         |
| 514 | 1/25/2018   | 180        | Paint exposed compressor piping   | Could not get into room |
| 515 | 1/25/2018   | 180        | Light switch is to be with Occ. Sensor.   | Could not get into room |
| 516 | 1/25/2018   | Generator  | Remove items from generator   | Could not get into room |
| 517 | 1/25/2018   | Generator  | Panel board cover left open   | Complete                |
| 519 | 1/25/2018   | Generator  | Light burned out in generator   | Complete                |
| 520 | 1/25/2018   | Generator  | Remove fuel soaked rags from fuel overfill.   | Defer to Architect      |
| 521 | 1/25/2018   | Generator  | Clean interior surfaces   | Complete                |
| 521 | 1/25/2018   | Fuel Kiosk | Provide final coats of paint on conduits and wire raceways                                  | Complete                |
| JLL | 1/ 23/ 2010 | I del Mosk | Provide correct while in use receptacle cover and provide engraved cover with               | compicte                |
| 524 | 1/25/2018   | Roof       | panelboard and circuit.   | N/A                     |
| 527 | 1/25/2018   | Roof       | Provide engraved laminate tags on disconnects.  | Incomplete              |
| 533 | 1/25/2018   | Roof       | Provide domes for all roof drains   | Complete                |
| 534 | 1/25/2018   | RTU-1      | Damage to energy wheel media RTU-1  | Defer to Architect      |
| 535 | 1/25/2018   | RTU-1      | Return all interior surfaces to factory condition.  | Defer to Architect      |
| 536 | 1/25/2018   | RTU-1      | All specialties to be insulated   | Defer to Architect      |
| 537 | 1/25/2018   | RTU-1      | Comb all damage from pre-heat coil  | Defer to Architect      |
| 538 | 1/25/2018   | RTU-2      |   | Defer to Architect      |
| 539 | 1/25/2018   | RTU-2      | Return all interior surfaces to factory condition.  | Defer to Architect      |
| 540 | 1/25/2018   | RTU-2      | All specialties to be insulated   | Defer to Architect      |
| 541 | 1/25/2018   | RTU-2      | Comb all damage from pre-heat coil  | Defer to Architect      |
| 241 | 1/ 23/ 2010 | 1/10-2     | Comb an damage from pre-freat con   | Defet to Armitect       |
|     |             | + +        |   |                         |
|     | +           |            |   |                         |
|     |             |            | MEP Comments  |                         |
|     |             | <u> </u>   | INICI COMMENS   |                         |

Labels can be ins

# Prince William County Department of Transportation DOT Accounting Request for Payment

### Information Required to Obtain Contractor Payment Form for a Project

| Name of Project -                |
|----------------------------------|
| Project Number –                 |
| Name of Contractor -             |
| Contract No                      |
| PO Number -                      |
| Contract Date -                  |
| Original Contract Amount -       |
| Retainage to be Held Yes or No - |
| Retainage %                      |
|                                  |

Please return to Sandra Lewis as soon as Contract has been approved.

# PRINCE WILLIAM COUNTY DEPARTMENT OF TRANSPORTATION CONTRACTOR 'S REQUEST FOR PAYMENT PROJECT NAME

### **Contractor Name**

| CONTRACT NO.                                 | PO#  |                       | Project    | #         |
|--|--|-----------------------|------------|-----------|
| CONTRACT DATE                                | INVOICE D                                    | ATE                   |            |           |
| REQUEST FOR PAYMENT NO                       | o  | _                     |            |           |
| SUBMISSION OF (CHECK ON                      | IE)  |                       |            |           |
| PROGR  | RESS PAYMENT<br>LICATION FOR PAYMENT SHALL I | BE FOR RETAINAGE ONLY | _SEMI-FINA | L PAYMENT |
| ORIGINAL CONTRACT AMOU                       | JNT  |                       |            |           |
| CHANGE ORDERS                                |  |                       | -          |           |
| ADJUSTED CONTRACT AMO                        | UNT INCLUDING CHANGE                         | ORDERS                |            |           |
| (1) ORIGINAL WORK EARNE                      | D LESS PREVIOUS STORE                        | D MATERIALS           |            |           |
| (2) CHANGE ORDER WORK                        | EARNED                                       |                       | -          |           |
| (3) PRICE ADJUSTMENT "AS                     | PHALT"                                       |                       | -          | <u>-</u>  |
| (4) PRICE ADJUSTMENT "ST                     | EEL GUARD RAIL"                              |                       |            | <u>-</u>  |
| (5a) STORED MATERIALS                        | PREVIOUS REQUEST                             |                       | _          |           |
| (5b ) ADDITIONAL MATERI                      | ALS ON HAND THIS REQ                         | -                     | _          |           |
| (5c) REMOVED MATERIAL                        | S ON HAND THIS REQ                           |                       | _          |           |
| (5d) BALANCE MATERIAL                        | S ON HAND (5a+5b-5c)                         | \$ -                  | _          |           |
| (5) TOTAL AMOUNT MATERIALS EARNED & STORED - |  |                       |            |           |
| (6) TOTAL AMOUNT EARNED (1+2+3+4+5)          |  |                       | \$         | <u>-</u>  |
| (7) TOTAL AMOUNT PREVIOU                     | USLY INVOICED                                |                       |            |           |
| (8) TOTAL AMOUNT DUE CO                      | NTRACTOR THIS INVOICE (                      | (6-7)                 | \$         | <u>-</u>  |
| Approved by: Contractor                      |  |                       |            | *srl      |
| DATE   | Signed                                       |                       |            |           |
| Approved by: Prince William County           |  |                       |            |           |
| DATE   | Signed                                       |                       |            |           |

# PRINCE WILLIAM COUNTY DEPARTMENT OF TRANSPORTATION CONTRACTOR 'S REQUEST FOR PAYMENT WITH RETAINAGE

(Name of Project) (Contractor's Name

| CONTRACT NO.  | PO#                                  | Project #     |             |  |
|---|--------------------------------------|---------------|-------------|--|
| CONTRACT DATE   | INVOICE DATE                         |               | _           |  |
| REQUEST FOR PAYMENT NO.                                   |                                      |               |             |  |
| SUBMISSION OF (CHECK ONE)                                 |                                      |               |             |  |
| PROGRESS PAYMENTE: SUBMISSION OF FINAL APPLICATION FOR PA |                                      | SEMI-FINAL PA | YMENT       |  |
| ORIGINAL CONTRACT AMOUNT                                  |                                      |               |             |  |
| CHANGE ORDERS   |                                      |               |             |  |
| ADJUSTED CONTRACT AMOUNT INCLUD                           | ING CHANGE ORDERS                    | \$ -          |             |  |
| (1) ORIGINAL WORK EARNED LESS PREV                        | IOUS STORED MATERIALS                |               |             |  |
| (2) CHANGE ORDER WORK EARNED                              |                                      |               |             |  |
| (3) PRICE ADJUSTMENT "ASPHALT"                            |                                      |               |             |  |
| (4) PRICE ADJUSTMENT "STEEL GUARD I                       | RAIL"                                |               | <u> </u>    |  |
| (5a) STORED MATERIALS PREVIOUS R                          | EQUEST                               | _             |             |  |
| (5b ) ADDITIONAL MATERIALS ON HAN                         | D THIS REQ                           | _             |             |  |
| (5c ) REMOVED MATERIALS ON HAND 1                         | THIS REQ -                           | _             |             |  |
| (5d ) BALANCE MATERIALS ON HAND (                         | 5a+5b-5c)                            | _             |             |  |
| (5) TOTAL AMOUNT MATERIALS EARNED                         | & STORED                             | _             |             |  |
| (6) TOTAL AMOUNT EARNED (1+2+3+4+5)                       |                                      | \$ -          | _           |  |
| (7) RETAINAGE WITHHELD YEAR-TO-DAT                        | E (line 6*5%)                        | \$ -          |             |  |
| (8) TOTAL RETAINAGE WITHHELD THRU LAST REQUEST            |                                      |               |             |  |
| (9) RETAINAGE WITHHELD CURRENT REC                        | \$ -                                 | <u></u>       |             |  |
| (10) TOTAL AMOUNT PREVIOUSLY INVOICE                      | CED                                  |               | <u></u>     |  |
| (11) TOTAL AMOUNT DUE CONTRACTOR                          | THIS INVOICE (6-7)-10                | \$ -          | _           |  |
| Note: Submission of Final Application for I               | Payment shall be for Retainage only. |               | <del></del> |  |
| Approved by: Contractor                                   |                                      |               | *srl        |  |
| DATE  | Signed                               |               |             |  |
| Approved by: Prince William County                        |                                      |               |             |  |
| DATE  | Signed                               |               |             |  |



# Right-of-Way Acquisition Report Compensation Approval Form

| TRACKING No.        | SUBMITTED   |                 |             |                 |
|---------------------|-------------|-----------------|-------------|-----------------|
| Project:            |             |                 |             |                 |
| Recipient: Location | n:          |                 |             |                 |
| Compensation for:   | Fee Simple  | Easement I      | Damages     | Relocation      |
| Approximate Sq F    | ootage:     | Appraisal Amou  | nt: \$      |                 |
| Amount of Compe     | ensation:   | Object:         |             |                 |
|                     | Appı        | roval Signature | Date        | <b>Due Date</b> |
| County Attorney:    | ,           |                 |             | **/**/**        |
| Director of Finance | e:          |                 |             | **/**/**        |
| Budget Director:    |             |                 |             | **/**/**        |
|                     | Final       | Approval        | Date        | Due Date        |
| Director of Transp  | ortation:   |                 |             | **/**/**        |
| ACXO >\$300,000     |             |                 | <u>**/*</u> | */**            |
| County Executive    | > \$300,000 |                 |             | **/**/**        |

# Prince William County Transportation Department Settlement Check List

In an effort to expedite your settlement as quickly as possible, please provide the following information and mail to Prince William County Department of Transportation, 5 County Complex Court, Suite 290, Prince William, VA 22192, Attn: Scott Hatten Mailstop DS990. If you have questions please contact Mr. Scott Hatten at: 703-792-6257 or shatten@pwcgov.org

| Hatten at: 703-792-6257 or shatten @pwcgov.org                                       | 90. If you have questions please contact Mr. Scott |  |
|--|--|--|
|  | hurches<br>te all which apply:                     |  |
| Parties Authorized To Sign (place additional signers of                              |  |  |
| Name:  | Title:   |  |
| End  | closed   |  |
| ☐ Completed Mortgage Information Sheet ☐   | Signed W- 9  |  |
| ☐ Corporate Resolution authorizing sale of land/ease                                 | ements/ROW to Prince William County                |  |
| ☐ Corporate Resolution designating authorized sign                                   | er for corporate land transactions                 |  |
| ☐ Copies of all Petitions/Orders of Designating Trustees                             |  |  |
| ☐ Board Minutes approving resolutions (if applicable                                 | e)   |  |
| ☐ Signed/notarized Deed  | Signed/notarized Agreement                         |  |
| ☐ Signed Utility easements (Verizon, NOVEC, Dominion, Comcast, Washington Gas, etc.) |  |  |
| ☐ Signed Right-Of-Entry Agreements   | Copy of current title policy                       |  |
| How would you like to conduct settlement: By Fed-E.                                  | x In-person  |  |
| To whom and where the documents should be sent: Na                                   | ame  |  |
| Title: Phone:  | Fax:   |  |
| Address:   |  |  |
| City, State, Zip   | Email:   |  |
|  |  |  |

# Prince William County Transportation Department Settlement Check List

In an effort to expedite your settlement as quickly as possible, please provide the following information and mail to Prince William County Department of Transportation, 5 County Complex Court, Suite 290, Prince William, VA 22192, Attn: Scott Hatten, Mailstop DS990. If you have questions please contact Mr. Scott Hatten at: 703-792-6257 or shatten@pwcgov.org

|  | Corporations   |  |  |
|--|--|--|--|
| Parties Authorized To Sign:  | mplete all which apply:                                      |  |  |
| Name:  | Title:   |  |  |
| Name:  |  |  |  |
| Name:  | Title:   |  |  |
| Name:  | Title:   |  |  |
| <u>I</u>   | Enclosed   |  |  |
| Completed Mortgage Information Sheet   | ☐ Signed W- 9  |  |  |
| ☐ Copy of Articles of Incorporation,   | ☐ Copy of SCC certificate in good standing                   |  |  |
| Current Operating Agreement and all amenda   | nents, if none Certification there is no Operating Agreement |  |  |
| Corporate Resolution authorizing sale of land  | /easements/ROW to Prince William County                      |  |  |
| ☐ Corporate Resolution designating authorized signer for corporate land transactions |  |  |  |
| ☐ Board Minutes approving resolutions (if appli                                      | icable)  |  |  |
| ☐ Signed/notarized Deed  | ☐ Signed/notarized Agreement                                 |  |  |
| ☐ Signed Utility easements (Verizon, NOVEC,  | Dominion, Comcast, Washington Gas, etc.)                     |  |  |
| ☐ Signed Right-Of-Entry Agreements   | ☐ Copy of current title policy                               |  |  |
| How would you like to conduct settlement: By Fe                                      | ed-Ex In-person  |  |  |
|  | t: Name  |  |  |
|  | one: Fax:  |  |  |
|  |  |  |  |
|  | Email:   |  |  |

# Prince William County Transportation Department Settlement Check List

In an effort to expedite your settlement as quickly as possible, please provide the following information and mail to Prince William County Department of Transportation, 5 County Complex Court, Suite 290, Prince William, VA 22192, Attn: Scott Hatten, Mailstop DS990. If you have questions please contact Mr. Scott Hatten at: 703–792–6257 or <a href="mailto:shatten@pwcgov.org">shatten@pwcgov.org</a>

|  | For Property Owners   |  |
|--|---|--|
| Please   | e complete all which apply – if applicable:                     |  |
| Name   | ::Name:   |  |
| Addre  | ess: city, state, zip:  |  |
| Phone  | e: Office: Cell:  |  |
| Conta  | ct Email:   |  |
|  | Enclosed  |  |
| Completed Mortgage Information Sheet (copy of statement)                             |   |  |
| □ s  | Signed W-9  |  |
| ☐ Are you planning to refinance soon ? Yes No  |   |  |
|  | New lender contact information                                  |  |
| ☐ Signed/notarized Agreement ☐ Signed Right-Of-Entry Agreements                      |   |  |
| ☐ Signed Utility easements (Verizon, NOVEC, Dominion, Comcast, Washington Gas, etc.) |   |  |
| □ P  | Power -of-Attorney/ Court Orders appointing Trustee             |  |
| ☐ S  | student Loans paid off: Yes No                                  |  |
| <u> </u>   | 0. If represented by Counsel – Name, Address, Phone, Fax, Email |  |
|  |   |  |



| Date |   |   |  |
|------|---|---|--|
| TO:  |   | name County Executive   |  |
| FROM | <b>1</b> :  | title   |  |
| RE:  |   | Approval of Selection Committee for the Purpose of Interviewing, Evaluating, and Selecting Consulting Services for <u>name of project</u>   |  |
| I.   | Background: in chronological order is as follows: |   |  |
|      | A.  | <u>project name -</u> short description.  |  |
|      | B.  | Budget – Funds are  |  |
|      | C.  | <u>Request for Proposals</u> – A Request for Proposals (RFP) has been prepared to solicit proposals from consultants for NAME OF PROJECT.   |  |
|      | D.  | Selection Committee Approval – The County Executive must approve the Selection Committee whose function is to interview, evaluate, and select a design consultant in accordance with County Purchasing Regulations. |  |
| II.  | <u>Curre</u>                                      | nt Situation is as follows:   |  |
|      | A.  | <u>Proposal Due Date</u> – Proposals from consultants are due   |  |
|      | B.  | <u>Selection Committee Recommendation</u> – The recommended committee members to interview, evaluate, and select the most applicable candidates are as follows:   |  |

| Date<br>Page 2 |               |  |
|----------------|---------------|--|
|                |               | <ol> <li>Name &amp; title</li> <li>Name &amp; title</li> <li>Name &amp; title</li> <li>Name &amp; title</li> </ol>   |
|                | C.            | <u>Selection Committee Approval</u> – This Selection Committee requires the approval of the County Executive in accordance with Prince William County Purchasing Regulations.  |
| III.           | purpo<br>PROJ | nmendation is that the Selection Committee identified above be approved for the se of interviewing, evaluating, and selecting a design consultant for the NAME OF ECT. A check in the appropriate box and a signature on the line at the bottom of this provides approval of the recommendation. |
|                |               | Approved   |
|                |               | Disapproved  |

of

Date

, Purchasing Manager Cc:

County Executive

### SOLICITATION INFORMATION FORM FOR CONSTRUCTION PROJECTS

### SUBMITTED BY:

### DATE SUBMITTED:

This form must accompany the following 100% final completed and approved electronic documents. Submit the above documents to Contract Specialist as word/excel files. Ensure each file reflects in lower left corner of each page a document creation or origination date.

- Contract Special Provisions (CSP)
- Special Provisions / Copied Note (VSP)
- Schedule of Unit Prices

### **GENERAL**

The following information is requested to assist the Contract Specialist in preparing your construction solicitation. Failure to provide a detailed response to the questions herein may result in delay in the Contract Specialist completing the final solicitation document and/or rejection of your requisition to proceed with review of your solicitation.

Please furnish the following information if applicable, to your project:

- 1. Name of Project (name indicated in CIP and as shown on the plans)
- 2. Full description of Work and overview of project (Include location/address)

Provide generalized background, important details and related project information

| 3.  | Detail how project is funded (state/county/federal, etc.) Note: Federal and State funded projects <u>have different front-end documents</u> than projects funded 100% by PWC   |
|-----|--|
| 4.  | Provide COA number.  |
| 5.  | Provide date of approval of plans (no solicitation will be advertised without <b><u>final</u> approved plans</b> – no exceptions).   |
| 6.  | Provide Name/phone number of contact person for contracting Department.  |
| 7.  | Provide a "suggested schedule" of activities for advertising, pre-bid conference, opening bids, and award. In an effort to determine award date by BOCS, it is recommended Engineer review the BOCS Agenda meeting schedule dates including, the date for Close of Agenda date for preparation of Staff Report and the Agenda Dispatch date. |
| 8.  | Provide Prince William County employees' name/phone number whom Purchasing will coordinate solicitation front-end document preparation and address technical question  |
| 9.  | Provide Name/phone number of contact person of Engineer firm (Designer)  |
| 10. | Provide Design Engineering consultants 'construction estimate (attached excel Schedule of Unit Prices from Design Consultant)  |
| 11. | Indicate amount Bidders must pay to CD ROM bidding documents & Plans.  |
| 12. | Indicate Number calendar days or the specific date for construction contractor to complete the work.   |
| 13. | Specify or provide details regarding (PWC or Consultant) providing construction over-sight/on-site construction activities.  |
| 14. | Indicate who will provide construction inspections/testing services  |
| 15. | Describe additional related details  |

Form Completed By: \_\_\_\_\_ Date: \_\_\_\_

# SOLICITATION INFORMATION FORM FOR RFP PROFESSIONAL ENGINEERING SERVICES

| SUBN        | MITTED BY:   |
|-------------|--|
| DATE        | E SUBMITTED:   |
| <u>GENE</u> | RAL_   |
| RFP so      | llowing information is requested to assist the Contract Specialist in preparing your elicitation. Failure to provide a detailed response to the questions herein may result y in the Contract Specialist completing the final solicitation document and/or on of your requisition to proceed with review of your solicitation. |
| Please      | furnish the following information if applicable, to your project:  |
| 1.          | Name of Project (name indicated in CIP and as shown on the plans)  |
| 2.          | Brief description and overview of project (Include location/address)   |
| 3.          | Describe how project is funded (state/county/federal, etc.) Provide OCA number.  |
| 4.          | Provide generalized background, important details and related project information.   |
| 5.          | Does solicitation require prior to advertisement review/approval by any governmental agency (VDOT/FHWA)? Is so state governmental agency. Provide names of approval agencies i.e. VDOT. Include contact person name and number   |
| 6.          | Submit/attach a copy of any/all jurisdictional agreements, including   |

**VDOT/FHWA grants** 

| ency approval for  |
|--|
| mber whom  |
| RFP due date,<br>n effort to determine<br>e BOCS Agenda<br>da date for |
|  |
|  |
|  |



# **Prince William County, Department of Transportation**

# **Special Event Checklist Information**

| Type of Event  |  |
|--|--|
| Date of Event (including time of event)  |  |
| Project Description  |  |
| Location of Event  |  |
| Is there is a street sign in the background for photo opportunity?   |  |
| Event Format:  |  |
| <ul> <li>Do you need chairs?</li> <li>Do you need audio speakers?</li> <li>Do you need a podium?</li> <li>Do you need a stage?</li> <li>Do you need a tent?</li> <li>Do you need a refreshment table?</li> </ul> |  |
| Speaker(s) for Event   |  |
| Guests for the Event (those who should receive an invitation for the event)  |  |
| Dignitaries who need to be recognized  • If yes, who?  |  |
| Refreshments needed for the event?  • If yes, what kind of refreshments?   |  |
| Directions to Event  |  |
| Is an event program needed?  • If yes, what is the schedule?   |  |
| Do you need nametags for the event?  • If yes, who needs nametags?   |  |

# PRINCE WILLIAM COUNTY TASK ORDER

| TASK ORDER NO.   | TASK OF  | RDER DATE   |   |
|--|--|---|---|
| <b>MODIFICATION NO.</b> (If note indicate the change, e.g. 001, 002)   | naking a change to an  | existing Task Order, insert a mo  | dification number                               |
| CONTRACT NAME  | CONTRA   | CT NO.  |   |
| PROJECT NAME   | PROJEC'  | ΓNO.  |   |
| PWC REPRESENTATIVE   | , (Contact/I<br>/ (Dept./Div<br>/ (Phone/Em                    | ·)  |   |
| VENDOR /CONTRACTOR  Precedence of Documents  | (Business Name)<br>(Address)<br>(Contact/Title)<br>/ (Phone/Em | ail)  |   |
| In the event of inconsistencies amon   | ng documents, the fo   | ollowing shall take precedence  | ··  |
| 1. Contract Number be 2. PWC Purchase Order/Task  , , , ,  Task Order Amount Total Task Order Amount, not to ex  Period of Performance Vendor/Contractor shall begin performance Scope of Work shall be completed to the second order.  Scope of Work In accordance with the Provisions of the second order. | ,  xceed - \$ without within within calend                     | out prior written County appro<br>calendar days from receipt<br>ar days <i>or</i> by (a <i>specific</i> | oval.<br>of a Purchase Order.<br><i>date</i> ). |
| Vendor/Contractor shall provide: (S document, e.g. Deliverables, Deliverab   | Specify or attac   | ch a detailed Scope of Work inclu   | •   |
| USING DEPARTMENT HEAD OMANAGER'S SIGNATURE AND   |  | VENDOR/CONTRA<br>AND DATE   | CTOR'S SIGNATURE                                |
| Signature  | Date   | Signature   | Date  |
| Print Name and Title   |  | Print Name and Titl   | e   |
| PURCHASING MANAGER'S SI<br>AND DATE  | IGNATURE   |   |   |
| Signature  | Data   |   |   |

(Task Orders exceeding \$15,000 must be signed by the Using Department Head and the Vendor, and the original hard copy must be sent to Purchasing for the Purchasing Manager's signature.)

**Adam Manne, Purchasing Manager** 

# VIRGINIA DEPARTMENT OF TRANSPORTATION MANASSAS RESIDENCY

# **Check List for PWC Bond Acceptance Documents**

| Projec | et:   |
|--------|---|
|        | <b>Record Plats</b> – All plats must be recorded and show the deed book, page number and date, or the instrument number.  |
|        | <b>Legal Instruments</b> - quit claim deeds, vacated easements, turnaround easements, etc. All documents must be recorded and show the deed book, page number and date, or the instrument number.   |
|        | <b>Construction Plans</b> - Compact disc containing "full scale" as-built plans on TIFF files.  |
|        | <b>Typical Section</b> - Chart with typical section and right-of-way information.   |
|        | Composite – (1) copy of a project sketch showing changes to primary and secondary system of highways including additions, abandonment's and discontinuances with corresponding mileage for each segment.                                    |
|        | <b>Draft Resolution –</b> (1) copy of the B.O.S. draft resolution.  |
|        | Land Use Permit Applications / Utilities – Applications submitted from all companies with utilities in R/W. Applications must include (2) copies of a plan sheet or sketch with locations of utilities highlighted.                         |
|        | <b>Land Use Permit Applications / P.W.C.</b> – Applications submitted from P.W.C. for landscaping, sidewalks not maintained by VDOT, etc. Applications must include (2) copies of plans. Landscaping plans must be pre-approved by V.D.O.T. |
|        | Maintenance Agreements – Agreements for extrinsic structures (dams, tunnels, etc.), concrete driveways in ditch sections, VDOT snow removal access, etc.  |

Notes: 1. All information must be legible.
2. If an item is not required, indicate N/A in the appropriate check box.



# Request for Taxpayer Identification Number and Certification

Give Form to the requester. Do not send to the IRS.

| intoma   | 111010                  | And Col vice  |                      |                        |                    |                   |                    |  |                 |           |
|--|-------------------------|---|----------------------|------------------------|--------------------|-------------------|--------------------|--|-----------------|-----------|
|  | 1 1                     | Name (as shown on your income tax return). Name is required on this line; do not leave this line blank.   |                      |                        |                    | ,                 |                    |  |                 |           |
| page 2.  | <b>2</b> E              | Business name/disregarded entity name, if different from above  |                      |                        |                    |                   |                    |  |                 |           |
| o s  | 3 (                     | Check appropriate box for federal tax classification; check only <b>one</b> of the following seven boxes:  Individual/sole proprietor or C C Corporation S Corporation Partnership single-member LLC  Limited liability company. Enter the tax classification (C=C corporation, S=S corporation, P=partners)  |                      | ust/estate             | cert               | ain ent           | tities,<br>is on p | codes a<br>not ind<br>page 3)<br>ode (if a | lividual<br>):  |           |
| r ig   |                         | Note. For a single-member LLC that is disregarded, do not check LLC; check the appropriate box in   | '' -                 | above fo               | , Exe              | mptior            | from               | FATCA                                      | —<br>A repo     | rting     |
| Print or type  |                         | the tax classification of the single-member owner.  | i uic iiic           | above 10               |                    | le (if ar         | ny) _              |  |                 |           |
| P. P.  |                         | Other (see instructions) ►  |                      |                        | (Аррі              | ies to acc        | ounts m            | naintained                                 | outside         | the U.S.) |
| či   | 5 A                     | Address (number, street, and apt. or suite no.)   | Reques               | ter's nam              | ne and a           | ddress            | (optio             | onal)                                      |                 |           |
| See <b>Spe</b>   | 6 0                     | City, state, and ZIP code   |                      |                        |                    |                   |                    |  |                 |           |
|  | 7 L                     | ist account number(s) here (optional)   |                      |                        |                    |                   |                    |  |                 |           |
| Par  | tΙ                      | Taxpayer Identification Number (TIN)  |                      |                        |                    |                   |                    |  |                 |           |
|  |                         | TIN in the appropriate box. The TIN provided must match the name given on line 1 to av  |                      | Social                 | security           | numb              | er                 |  |                 |           |
|  |                         | thholding. For individuals, this is generally your social security number (SSN). However, folien, sole proprietor, or disregarded entity, see the Part I instructions on page 3. For other  |                      |                        |                    |                   |                    |  |                 |           |
| entities, it is your employer identification number (EIN). If you do not have a number, see <i>How to get a</i>                                    |                         |   |                      |                        |                    |                   |                    |  |                 |           |
| TIN o  | n pa                    | ge 3.   |                      | or                     |                    |                   |                    |  |                 |           |
| <b>Note.</b> If the account is in more than one name, see the instructions for line 1 and the chart on page 4 guidelines on whose number to enter. |                         | 4 for   | Employ               | er iden                | tificati           | on nu             | mber               |  |                 |           |
|  |                         |   |                      | _                      |                    |                   |                    |  |                 |           |
|  |                         |   |                      |                        |                    |                   |                    |  |                 |           |
| Par  |                         | Certification   |                      |                        |                    |                   |                    |  |                 |           |
|  | •                       | nalties of perjury, I certify that:   |                      |                        |                    |                   |                    |  |                 |           |
| 1. In  | e nu                    | mber shown on this form is my correct taxpayer identification number (or I am waiting for   | a numb               | per to be              | sissuec            | to m              | e); an             | id   |                 |           |
| Se   | rvice                   | ot subject to backup withholding because: (a) I am exempt from backup withholding, or (b<br>(IRS) that I am subject to backup withholding as a result of a failure to report all interest<br>per subject to backup withholding; and   |                      |                        |                    |                   |                    |  |                 |           |
| 3. I a   | m a l                   | U.S. citizen or other U.S. person (defined below); and  |                      |                        |                    |                   |                    |  |                 |           |
| 4. The   | e FAT                   | TCA code(s) entered on this form (if any) indicating that I am exempt from FATCA reporting  | ng is cor            | rect.                  |                    |                   |                    |  |                 |           |
| becau<br>intere<br>gener   | ise y<br>st pa<br>ally, | ion instructions. You must cross out item 2 above if you have been notified by the IRS the ou have failed to report all interest and dividends on your tax return. For real estate translaid, acquisition or abandonment of secured property, cancellation of debt, contributions to payments other than interest and dividends, you are not required to sign the certification is on page 3. | actions,<br>o an inc | item 2 d<br>lividual r | does no<br>etireme | ot app<br>ent arr | ly. Fo             | or mor<br>ment                             | tgage<br>(IRA), | and       |
| Sign<br>Here   |                         | Signature of U.S. person ► Da   | ate ▶                |                        |                    |                   |                    |  |                 |           |
|  |                         | p   |                      |                        |                    |                   |                    |  |                 |           |

# **General Instructions**

Section references are to the Internal Revenue Code unless otherwise noted.

**Future developments.** Information about developments affecting Form W-9 (such as legislation enacted after we release it) is at www.irs.gov/fw9.

## **Purpose of Form**

An individual or entity (Form W-9 requester) who is required to file an information return with the IRS must obtain your correct taxpayer identification number (TIN) which may be your social security number (SSN), individual taxpayer identification number (ITIN), adoption taxpayer identification number (ATIN), or employer identification number (EIN), to report on an information return the amount paid to you, or other amount reportable on an information return. Examples of information returns include, but are not limited to, the following:

- Form 1099-INT (interest earned or paid)
- Form 1099-DIV (dividends, including those from stocks or mutual funds)
- Form 1099-MISC (various types of income, prizes, awards, or gross proceeds)
- Form 1099-B (stock or mutual fund sales and certain other transactions by brokers)
- Form 1099-S (proceeds from real estate transactions)
- Form 1099-K (merchant card and third party network transactions)

- Form 1098 (home mortgage interest), 1098-E (student loan interest), 1098-T (tuition)
- Form 1099-C (canceled debt)
- Form 1099-A (acquisition or abandonment of secured property)

Use Form W-9 only if you are a U.S. person (including a resident alien), to provide your correct TIN.

If you do not return Form W-9 to the requester with a TIN, you might be subject to backup withholding. See What is backup withholding? on page 2.

By signing the filled-out form, you:

- 1. Certify that the TIN you are giving is correct (or you are waiting for a number to be issued),
  - 2. Certify that you are not subject to backup withholding, or
- 3. Claim exemption from backup withholding if you are a U.S. exempt payee. If applicable, you are also certifying that as a U.S. person, your allocable share of any partnership income from a U.S. trade or business is not subject to the withholding tax on foreign partners' share of effectively connected income, and
- 4. Certify that FATCA code(s) entered on this form (if any) indicating that you are exempt from the FATCA reporting, is correct. See *What is FATCA reporting?* on page 2 for further information.

Form W-9 (Rev. 12-2014) Page **2** 

**Note.** If you are a U.S. person and a requester gives you a form other than Form W-9 to request your TIN, you must use the requester's form if it is substantially similar to this Form W-9.

**Definition of a U.S. person.** For federal tax purposes, you are considered a U.S. person if you are:

- An individual who is a U.S. citizen or U.S. resident alien;
- A partnership, corporation, company, or association created or organized in the United States or under the laws of the United States;
- · An estate (other than a foreign estate); or
- A domestic trust (as defined in Regulations section 301.7701-7).

Special rules for partnerships. Partnerships that conduct a trade or business in the United States are generally required to pay a withholding tax under section 1446 on any foreign partners' share of effectively connected taxable income from such business. Further, in certain cases where a Form W-9 has not been received, the rules under section 1446 require a partnership to presume that a partner is a foreign person, and pay the section 1446 withholding tax. Therefore, if you are a U.S. person that is a partner in a partnership conducting a trade or business in the United States, provide Form W-9 to the partnership to establish your U.S. status and avoid section 1446 withholding on your share of partnership income.

In the cases below, the following person must give Form W-9 to the partnership for purposes of establishing its U.S. status and avoiding withholding on its allocable share of net income from the partnership conducting a trade or business in the United States:

- In the case of a disregarded entity with a U.S. owner, the U.S. owner of the disregarded entity and not the entity;
- In the case of a grantor trust with a U.S. grantor or other U.S. owner, generally, the U.S. grantor or other U.S. owner of the grantor trust and not the trust; and
- In the case of a U.S. trust (other than a grantor trust), the U.S. trust (other than a grantor trust) and not the beneficiaries of the trust.

**Foreign person.** If you are a foreign person or the U.S. branch of a foreign bank that has elected to be treated as a U.S. person, do not use Form W-9. Instead, use the appropriate Form W-8 or Form 8233 (see Publication 515, Withholding of Tax on Nonresident Aliens and Foreign Entities).

Nonresident alien who becomes a resident alien. Generally, only a nonresident alien individual may use the terms of a tax treaty to reduce or eliminate U.S. tax on certain types of income. However, most tax treaties contain a provision known as a "saving clause." Exceptions specified in the saving clause may permit an exemption from tax to continue for certain types of income even after the payee has otherwise become a U.S. resident alien for tax purposes.

If you are a U.S. resident alien who is relying on an exception contained in the saving clause of a tax treaty to claim an exemption from U.S. tax on certain types of income, you must attach a statement to Form W-9 that specifies the following five items:

- 1. The treaty country. Generally, this must be the same treaty under which you claimed exemption from tax as a nonresident alien.
  - 2. The treaty article addressing the income.
- 3. The article number (or location) in the tax treaty that contains the saving clause and its exceptions.
  - 4. The type and amount of income that qualifies for the exemption from tax.
- 5. Sufficient facts to justify the exemption from tax under the terms of the treaty article.

**Example.** Article 20 of the U.S.-China income tax treaty allows an exemption from tax for scholarship income received by a Chinese student temporarily present in the United States. Under U.S. law, this student will become a resident alien for tax purposes if his or her stay in the United States exceeds 5 calendar years. However, paragraph 2 of the first Protocol to the U.S.-China treaty (dated April 30, 1984) allows the provisions of Article 20 to continue to apply even after the Chinese student becomes a resident alien of the United States. A Chinese student who qualifies for this exception (under paragraph 2 of the first protocol) and is relying on this exception to claim an exemption from tax on his or her scholarship or fellowship income would attach to Form W-9 a statement that includes the information described above to support that exemption.

If you are a nonresident alien or a foreign entity, give the requester the appropriate completed Form W-8 or Form 8233.

### **Backup Withholding**

What is backup withholding? Persons making certain payments to you must under certain conditions withhold and pay to the IRS 28% of such payments. This is called "backup withholding." Payments that may be subject to backup withholding include interest, tax-exempt interest, dividends, broker and barter exchange transactions, rents, royalties, nonemployee pay, payments made in settlement of payment card and third party network transactions, and certain payments from fishing boat operators. Real estate transactions are not subject to backup withholding.

You will not be subject to backup withholding on payments you receive if you give the requester your correct TIN, make the proper certifications, and report all your taxable interest and dividends on your tax return.

## Payments you receive will be subject to backup withholding if:

- 1. You do not furnish your TIN to the requester,
- 2. You do not certify your TIN when required (see the Part II instructions on page 3 for details),  $\,$

- 3. The IRS tells the requester that you furnished an incorrect TIN.
- 4. The IRS tells you that you are subject to backup withholding because you did not report all your interest and dividends on your tax return (for reportable interest and dividends only), or
- 5. You do not certify to the requester that you are not subject to backup withholding under 4 above (for reportable interest and dividend accounts opened after 1983 only).

Certain payees and payments are exempt from backup withholding. See *Exempt payee code* on page 3 and the separate Instructions for the Requester of Form W-9 for more information.

Also see Special rules for partnerships above.

# What is FATCA reporting?

The Foreign Account Tax Compliance Act (FATCA) requires a participating foreign financial institution to report all United States account holders that are specified United States persons. Certain payees are exempt from FATCA reporting. See Exemption from FATCA reporting code on page 3 and the Instructions for the Requester of Form W-9 for more information.

### **Updating Your Information**

You must provide updated information to any person to whom you claimed to be an exempt payee if you are no longer an exempt payee and anticipate receiving reportable payments in the future from this person. For example, you may need to provide updated information if you are a C corporation that elects to be an S corporation, or if you no longer are tax exempt. In addition, you must furnish a new Form W-9 if the name or TIN changes for the account; for example, if the grantor of a grantor trust dies.

### **Penalties**

Failure to furnish TIN. If you fail to furnish your correct TIN to a requester, you are subject to a penalty of \$50 for each such failure unless your failure is due to reasonable cause and not to willful neglect.

Civil penalty for false information with respect to withholding. If you make a false statement with no reasonable basis that results in no backup withholding, you are subject to a \$500 penalty.

Criminal penalty for falsifying information. Willfully falsifying certifications or affirmations may subject you to criminal penalties including fines and/or imprisonment.

**Misuse of TINs.** If the requester discloses or uses TINs in violation of federal law, the requester may be subject to civil and criminal penalties.

# **Specific Instructions**

### Line 1

You must enter one of the following on this line; **do not** leave this line blank. The name should match the name on your tax return.

If this Form W-9 is for a joint account, list first, and then circle, the name of the person or entity whose number you entered in Part I of Form W-9.

a. Individual. Generally, enter the name shown on your tax return. If you have changed your last name without informing the Social Security Administration (SSA) of the name change, enter your first name, the last name as shown on your social security card, and your new last name.

**Note. ITIN applicant:** Enter your individual name as it was entered on your Form W-7 application, line 1a. This should also be the same as the name you entered on the Form 1040/1040A/1040EZ you filed with your application.

- b. **Sole proprietor or single-member LLC.** Enter your individual name as shown on your 1040/1040A/1040EZ on line 1. You may enter your business, trade, or "doing business as" (DBA) name on line 2.
- c. Partnership, LLC that is not a single-member LLC, C Corporation, or S Corporation. Enter the entity's name as shown on the entity's tax return on line 1 and any business, trade, or DBA name on line 2.
- d. Other entities. Enter your name as shown on required U.S. federal tax documents on line 1. This name should match the name shown on the charter or other legal document creating the entity. You may enter any business, trade, or DBA name on line 2.
- e. **Disregarded entity.** For U.S. federal tax purposes, an entity that is disregarded as an entity separate from its owner is treated as a "disregarded entity." See Regulations section 301.7701-2(c)(2)(iii). Enter the owner's name on line 1. The name of the entity entered on line 1 should never be a disregarded entity. The name on line 1 should be the name shown on the income tax return on which the income should be reported. For example, if a foreign LLC that is treated as a disregarded entity for U.S. federal tax purposes has a single owner that is a U.S. person, the U.S. owner's name is required to be provided on line 1. If the direct owner of the entity is also a disregarded entity, enter the first owner that is not disregarded for federal tax purposes. Enter the disregarded entity's name on line 2, "Business name/disregarded entity name." If the owner of the disregarded entity is a foreign person, the owner must complete an appropriate Form W-8 instead of a Form W-9. This is the case even if the foreign person has a U.S. TIN.

Form W-9 (Rev. 12-2014) Page **3** 

#### Line 2

If you have a business name, trade name, DBA name, or disregarded entity name, you may enter it on line 2.

#### Line 3

Check the appropriate box in line 3 for the U.S. federal tax classification of the person whose name is entered on line 1. Check only one box in line 3.

Limited Liability Company (LLC). If the name on line 1 is an LLC treated as a partnership for U.S. federal tax purposes, check the "Limited Liability Company" box and enter "P" in the space provided. If the LLC has filed Form 8832 or 2553 to be taxed as a corporation, check the "Limited Liability Company" box and in the space provided enter "C" for C corporation or "S" for S corporation. If it is a single-member LLC that is a disregarded entity, do not check the "Limited Liability Company" box; instead check the first box in line 3 "Individual/sole proprietor or single-member LLC."

#### Line 4, Exemptions

If you are exempt from backup withholding and/or FATCA reporting, enter in the appropriate space in line 4 any code(s) that may apply to you.

#### Exempt payee code.

- Generally, individuals (including sole proprietors) are not exempt from backup withholding.
- Except as provided below, corporations are exempt from backup withholding for certain payments, including interest and dividends.
- Corporations are not exempt from backup withholding for payments made in settlement of payment card or third party network transactions.
- Corporations are not exempt from backup withholding with respect to attorneys' fees or gross proceeds paid to attorneys, and corporations that provide medical or health care services are not exempt with respect to payments reportable on Form 1099-MISC.

The following codes identify payees that are exempt from backup withholding. Enter the appropriate code in the space in line 4.

- 1-An organization exempt from tax under section 501(a), any IRA, or a custodial account under section 403(b)(7) if the account satisfies the requirements of section 401(f)(2)
  - 2-The United States or any of its agencies or instrumentalities
- $3-\!A$  state, the District of Columbia, a U.S. commonwealth or possession, or any of their political subdivisions or instrumentalities
- $4-\!\mbox{A}$  foreign government or any of its political subdivisions, agencies, or instrumentalities
  - 5-A corporation
- 6—A dealer in securities or commodities required to register in the United States, the District of Columbia, or a U.S. commonwealth or possession
- $7\!-\!\text{A}$  futures commission merchant registered with the Commodity Futures Trading Commission
  - 8-A real estate investment trust
- 9-An entity registered at all times during the tax year under the Investment Company Act of 1940
  - 10-A common trust fund operated by a bank under section 584(a)
  - 11-A financial institution
- 12-A middleman known in the investment community as a nominee or custodian
  - 13-A trust exempt from tax under section 664 or described in section 4947

The following chart shows types of payments that may be exempt from backup withholding. The chart applies to the exempt payees listed above, 1 through 13.

| IF the payment is for  | THEN the payment is exempt for  |
|--|---|
| Interest and dividend payments   | All exempt payees except for 7  |
| Broker transactions  | Exempt payees 1 through 4 and 6 through 11 and all C corporations. S corporations must not enter an exempt payee code because they are exempt only for sales of noncovered securities acquired prior to 2012. |
| Barter exchange transactions and patronage dividends                                   | Exempt payees 1 through 4   |
| Payments over \$600 required to be reported and direct sales over \$5,000 <sup>1</sup> | Generally, exempt payees 1 through 5 <sup>2</sup>   |
| Payments made in settlement of payment card or third party network transactions        | Exempt payees 1 through 4   |

<sup>&</sup>lt;sup>1</sup>See Form 1099-MISC, Miscellaneous Income, and its instructions.

<sup>2</sup> However, the following payments made to a corporation and reportable on Form 1099-MISC are not exempt from backup withholding: medical and health care payments, attorneys' fees, gross proceeds paid to an attorney reportable under section 6045(f), and payments for services paid by a federal executive agency.

Exemption from FATCA reporting code. The following codes identify payees that are exempt from reporting under FATCA. These codes apply to persons submitting this form for accounts maintained outside of the United States by certain foreign financial institutions. Therefore, if you are only submitting this form for an account you hold in the United States, you may leave this field blank. Consult with the person requesting this form if you are uncertain if the financial institution is subject to these requirements. A requester may indicate that a code is not required by providing you with a Form W-9 with "Not Applicable" (or any similar indication) written or printed on the line for a FATCA exemption code.

- A—An organization exempt from tax under section 501(a) or any individual retirement plan as defined in section 7701(a)(37)
- B-The United States or any of its agencies or instrumentalities
- C-A state, the District of Columbia, a U.S. commonwealth or possession, or any of their political subdivisions or instrumentalities
- D—A corporation the stock of which is regularly traded on one or more established securities markets, as described in Regulations section 1.1472-1(c)(1)(i)
- E—A corporation that is a member of the same expanded affiliated group as a corporation described in Regulations section 1.1472-1(c)(1)(i)
- F—A dealer in securities, commodities, or derivative financial instruments (including notional principal contracts, futures, forwards, and options) that is registered as such under the laws of the United States or any state
  - G—A real estate investment trust
- H—A regulated investment company as defined in section 851 or an entity registered at all times during the tax year under the Investment Company Act of
- I-A common trust fund as defined in section 584(a)
- J-A bank as defined in section 581
- K-A broker
- L-A trust exempt from tax under section 664 or described in section 4947(a)(1)
- M-A tax exempt trust under a section 403(b) plan or section 457(g) plan

**Note.** You may wish to consult with the financial institution requesting this form to determine whether the FATCA code and/or exempt payee code should be completed.

#### Line 5

Enter your address (number, street, and apartment or suite number). This is where the requester of this Form W-9 will mail your information returns.

### Line 6

Enter your city, state, and ZIP code.

## Part I. Taxpayer Identification Number (TIN)

Enter your TIN in the appropriate box. If you are a resident alien and you do not have and are not eligible to get an SSN, your TIN is your IRS individual taxpayer identification number (ITIN). Enter it in the social security number box. If you do not have an ITIN, see *How to get a TIN* below.

If you are a sole proprietor and you have an EIN, you may enter either your SSN or EIN. However, the IRS prefers that you use your SSN.

If you are a single-member LLC that is disregarded as an entity separate from its owner (see *Limited Liability Company (LLC)* on this page), enter the owner's SSN (or EIN, if the owner has one). Do not enter the disregarded entity's EIN. If the LLC is classified as a corporation or partnership, enter the entity's EIN.

**Note.** See the chart on page 4 for further clarification of name and TIN combinations.

How to get a TIN. If you do not have a TIN, apply for one immediately. To apply for an SSN, get Form SS-5, Application for a Social Security Card, from your local SSA office or get this form online at <a href="https://www.ssa.gov">www.ssa.gov</a>. You may also get this form by calling 1-800-772-1213. Use Form W-7, Application for IRS Individual Taxpayer Identification Number, to apply for an ITIN, or Form SS-4, Application for Employer Identification Number, to apply for an EIN. You can apply for an EIN online by accessing the IRS website at <a href="https://www.irs.gov/businesses">www.irs.gov/businesses</a> and clicking on Employer Identification Number (EIN) under Starting a Business. You can get Forms W-7 and SS-4 from the IRS by visiting IRS.gov or by calling 1-800-TAX-FORM (1-800-829-3676).

If you are asked to complete Form W-9 but do not have a TIN, apply for a TIN and write "Applied For" in the space for the TIN, sign and date the form, and give it to the requester. For interest and dividend payments, and certain payments made with respect to readily tradable instruments, generally you will have 60 days to get a TIN and give it to the requester before you are subject to backup withholding on payments. The 60-day rule does not apply to other types of payments. You will be subject to backup withholding on all such payments until you provide your TIN to the requester.

**Note.** Entering "Applied For" means that you have already applied for a TIN or that you intend to apply for one soon.

Caution: A disregarded U.S. entity that has a foreign owner must use the appropriate Form W-8.

Form W-9 (Rev. 12-2014) Page 4

## Part II. Certification

To establish to the withholding agent that you are a U.S. person, or resident alien, sign Form W-9. You may be requested to sign by the withholding agent even if items 1, 4, or 5 below indicate otherwise.

For a joint account, only the person whose TIN is shown in Part I should sign (when required). In the case of a disregarded entity, the person identified on line 1 must sign. Exempt payees, see Exempt payee code earlier.

Signature requirements. Complete the certification as indicated in items 1 through 5 below

- 1. Interest, dividend, and barter exchange accounts opened before 1984 and broker accounts considered active during 1983. You must give your correct TIN, but you do not have to sign the certification.
- 2. Interest, dividend, broker, and barter exchange accounts opened after 1983 and broker accounts considered inactive during 1983. You must sign the certification or backup withholding will apply. If you are subject to backup withholding and you are merely providing your correct TIN to the requester, you must cross out item 2 in the certification before signing the form.
- 3. Real estate transactions. You must sign the certification. You may cross out item 2 of the certification
- 4. Other payments. You must give your correct TIN, but you do not have to sign the certification unless you have been notified that you have previously given an incorrect TIN. "Other payments" include payments made in the course of the requester's trade or business for rents, royalties, goods (other than bills for merchandise), medical and health care services (including payments to corporations), payments to a nonemployee for services, payments made in settlement of payment card and third party network transactions, payments to certain fishing boat crew members and fishermen, and gross proceeds paid to attorneys (including payments to corporations).
- 5. Mortgage interest paid by you, acquisition or abandonment of secured property, cancellation of debt, qualified tuition program payments (under section 529), IRA, Coverdell ESA, Archer MSA or HSA contributions or distributions, and pension distributions. You must give your correct TIN, but you do not have to sign the certification.

# What Name and Number To Give the Requester

| For this type of account:  | Give name and SSN of:   |
|--|---|
| I. Individual     Two or more individuals (joint account)  | The individual The actual owner of the account or, if combined funds, the first individual on the account |
| <ol><li>Custodian account of a minor<br/>(Uniform Gift to Minors Act)</li></ol>  | The minor <sup>2</sup>  |
| a. The usual revocable savings trust (grantor is also trustee)     b. So-called trust account that is not a legal or valid trust under state law   | The grantor-trustee¹  The actual owner¹   |
| <ol><li>Sole proprietorship or disregarded<br/>entity owned by an individual</li></ol>   | The owner <sup>3</sup>  |
| 6. Grantor trust filing under Optional<br>Form 1099 Filing Method 1 (see<br>Regulations section 1.671-4(b)(2)(i)<br>(A))   | The grantor*  |
| For this type of account:  | Give name and EIN of:   |
| 7. Disregarded entity not owned by an individual   | The owner   |
| 8. A valid trust, estate, or pension trust   | Legal entity⁴   |
| Corporation or LLC electing<br>corporate status on Form 8832 or<br>Form 2553   | The corporation   |
| 10. Association, club, religious, charitable, educational, or other tax-exempt organization  | The organization  |
| 11. Partnership or multi-member LLC  | The partnership   |
| 12. A broker or registered nominee   | The broker or nominee   |
| 13. Account with the Department of<br>Agriculture in the name of a public<br>entity (such as a state or local<br>government, school district, or<br>prison) that receives agricultural<br>program payments | The public entity   |
| 14. Grantor trust filing under the Form<br>1041 Filing Method or the Optional<br>Form 1099 Filing Method 2 (see<br>Regulations section 1.671-4(b)(2)(i)<br>(B))  | The trust   |

List first and circle the name of the person whose number you furnish. If only one person on a joint account has an SSN, that person's number must be furnished.

You must show your individual name and you may also enter your business or DBA name on the "Business name/disregarded entity" name line. You may use either your SSN or EIN (if you have one), but the IRS encourages you to use your SSN.

List first and circle the name of the trust, estate, or pension trust. (Do not furnish the TIN of the personal representative or trustee unless the legal entity itself is not designated in the account title.) Also see Special rules for partnerships on page 2. \*Note. Grantor also must provide a Form W-9 to trustee of trust.

Note. If no name is circled when more than one name is listed, the number will be considered to be that of the first name listed.

## **Secure Your Tax Records from Identity Theft**

Identity theft occurs when someone uses your personal information such as your name, SSN, or other identifying information, without your permission, to commit fraud or other crimes. An identity thief may use your SSN to get a job or may file a tax return using your SSN to receive a refund.

To reduce your risk:

- · Protect your SSN,
- Ensure your employer is protecting your SSN, and
- Be careful when choosing a tax preparer.

If your tax records are affected by identity theft and you receive a notice from the IRS, respond right away to the name and phone number printed on the IRS notice or letter.

If your tax records are not currently affected by identity theft but you think you are at risk due to a lost or stolen purse or wallet, questionable credit card activity or credit report, contact the IRS Identity Theft Hotline at 1-800-908-4490 or submit Form 14039

For more information, see Publication 4535, Identity Theft Prevention and Victim

Victims of identity theft who are experiencing economic harm or a system problem, or are seeking help in resolving tax problems that have not been resolved through normal channels, may be eligible for Taxpayer Advocate Service (TAS) assistance. You can reach TAS by calling the TAS toll-free case intake line at 1-877-777-4778 or TTY/TDD 1-800-829-4059.

Protect yourself from suspicious emails or phishing schemes. Phishing is the creation and use of email and websites designed to mimic legitimate business emails and websites. The most common act is sending an email to a user falsely claiming to be an established legitimate enterprise in an attempt to scam the user into surrendering private information that will be used for identity theft.

The IRS does not initiate contacts with taxpayers via emails. Also, the IRS does not request personal detailed information through email or ask taxpayers for the PIN numbers, passwords, or similar secret access information for their credit card, bank, or other financial accounts.

If you receive an unsolicited email claiming to be from the IRS, forward this message to phishing@irs.gov. You may also report misuse of the IRS name, logo, or other IRS property to the Treasury Inspector General for Tax Administration (TIGTA) at 1-800-366-4484. You can forward suspicious emails to the Federal Trade Commission at: spam@uce.gov or contact them at www.ftc.gov/idtheft or 1-877-IDTHEFT (1-877-438-4338).

Visit IRS.gov to learn more about identity theft and how to reduce your risk.

# **Privacy Act Notice**

Section 6109 of the Internal Revenue Code requires you to provide your correct TIN to persons (including federal agencies) who are required to file information returns with the IRS to report interest, dividends, or certain other income paid to you; mortgage interest you paid; the acquisition or abandonment of secured property; the cancellation of debt; or contributions you made to an IRA, Archer MSA, or HSA. The person collecting this form uses the information on the form to file information returns with the IRS, reporting the above information. Routine uses of this information include giving it to the Department of Justice for civil and criminal litigation and to cities, states, the District of Columbia, and U.S. commonwealths and possessions for use in administering their laws. The information also may be disclosed to other countries under a treaty, to federal and state agencies to enforce civil and criminal laws, or to federal law enforcement and intelligence agencies to combat terrorism. You must provide your TIN whether or not you are required to file a tax return. Under section 3406, payers must generally withhold a percentage of taxable interest, dividend, and certain other payments to a payee who does not give a TIN to the payer. Certain penalties may also apply for providing false or fraudulent information.

Circle the minor's name and furnish the minor's SSN.

# WIRE TRANSFER NOTIFICATION

| TRANSFER TO:   | DATE PREPARED   |
|--|---|
| NAME AMOUNT  | PREPARED BY   |
| FOR REPETITIVE WIRES:  | APPROVED  |
| PRIN/  |   |
| OR   | EFFECTIVE DAY AND DATE OF WIRE (ENSURE BANK BUSINESS DAY) |
| NON-REPETITIVE BENEFICIARY ACCOUNT:  | BENEFICIARY BANK:   |
| ACCOUNT NAME   |   |
| ACCOUNT NUMBER   | ABA NUMBER  |
|  | ADDRESS   |
| ORIGINATOR(S):   |   |
|  | CITY/STATE  |
| PWC<br>NAME(S)   | FOR DISBURSEMENTS USE ONLY:                               |
| DESCRIPTIVE INFORMATION TEXT 1   | PROCESSED BY  |
| TEXT 2   | AUTHORIZATION   |
| :CONFIRMATION VERIFIED TO BANK POSTING AND DATE  | N: NUMBER DATE TIME                                       |
| The state of the s | THE THE   |

# **Work Request Form**

Please do not use special characters like '&'. These may cause the form to give errors.

| Short Description:                  |       |   |
|-------------------------------------|-------|---|
| Date/time of Submission:            | Date  |   |
| <b>Requestor Name:</b>              |       |   |
| Requestor's Phone #:                |       |   |
| <b>Requesting Agency:</b>           |       |   |
| <b>Onsite Point of Contact:</b>     |       |   |
| Phone #:                            |       |   |
| Address for work:                   |       |   |
| Building #:                         |       |   |
| City:                               |       |   |
| Zipcode:                            |       |   |
| Description of Requested Work:      |       |   |
|                                     | 4     | Ъ |
| <b>Requested Completion Date:</b>   | Date  |   |
| (10 working days for standard reque | ests) |   |
| IDT Code(if applicable):            |       |   |
| Authorized By:                      |       |   |





# Prince William County Department of Transportation Work Zone Safety Assistance

| Date:        |                                       |   |
|--------------|---------------------------------------|---|
| Shift:       | Day/Night (Circle One)                | - |
| Police Offic | cer's Name (Print)                    |   |
| Badge #      |                                       |   |
| PWC DOT      | Supervisor/ Representative (Print)    |   |
| Project Nar  | me                                    |   |
| Project Nur  | mber                                  |   |
| Location W   | /orked                                |   |
| Hours Worl   | ked( From-To) Include am/pm           |   |
| Total Hours  | s                                     |   |
| Notes I      | Example - Job cancelled after arrival |   |
|              |                                       |   |
|              |                                       |   |
|              |                                       |   |
| Police Offic | cers Signature                        |   |
| PWC DOT      | Supervisor/Representative Signature   |   |
| PWC DOT C    | Construction Chief Signature          |   |
|              |                                       |   |

Copy of completed Time Sheet will be sent to Katherine Gaskins and DOT Accounting By DOT Supervisor

| Materials Name  | References           |
|---|----------------------|
| Agreement   | 2.6.5                |
| Appraisal   | 2.6.1, 2.6.5         |
| Automated forms in ASCEND                                 | 2.1.6                |
| Binder of all warranties from contractor                  | 2.4.3                |
| BOCS Item for Public Hearing                              | 2.2.2                |
| BOCS Resolution   | 2.6.8, 2.8.1         |
| BOCS Staff Report and Resolution                          | 2.2.4, 2.2.5, 2.2.14 |
| Bond Acceptance documents                                 | 2.4.4                |
| Budget (General Fund) forms                               | 2.4.10               |
| Building permit   | 2.2.19               |
| Building Program  | 2.2.1                |
| CIP forms   | 2.4.10               |
| Commissioning Report                                      | 2.3.7                |
| Construction documents                                    | 2.2.18               |
| Construction Drawing                                      | 2.6.5                |
| Construction plan   | 2.6.4                |
| Consultant's proposal                                     | 2.2.11               |
| Contract  | 2.2.16               |
| Contract Modification                                     | 2.2.5                |
| Copies of invoices and/or internal charges                | 2.3.3, 2.3.4         |
| Daily Tickets   | 2.3.6                |
| Design drawings   | 2.2.13               |
| Drawings by consultants                                   | 2.2.7                |
| Easements   | 2.6.5                |
| EIS   | 2.2.9                |
| FONSI   | 2.2.9                |
| Geotechnical Report                                       | 2.2.1                |
| GPIN parcel listing                                       | 2.6.1, 2.6.4         |
| Intermediate Reports                                      | 2.3.7                |
| Letter from GC to County stating change over in insurance | 2.4.2                |
| Letter to Trustee/Portfolio Manager                       | 2.3.4                |
| Letters to citizens                                       | 2.2.3                |
| Mortgage Information Sheet                                | 2.6.5                |
| NEPA Permit   | 2.2.8, 2.2.9         |
| Offer letter  | 2.6.6                |
| Permit letter   | 2.2.15               |
| Plat  | 2.2.17, 2.6.5        |
| Professional cost estimate                                | 2.2.13               |
| Project cashflow worksheet                                | 2.7.1                |
| Project plans   | 2.6.1                |
| Purchase Order  | 2.6.4                |
| Request for Proposal (RFP)                                | 2.1.1, 2.6.7, 2.7.1  |
| Right of Entry  | 2.6.5                |
| ROD   | 2.2.9                |
| Scope of Work (SOW)                                       | 2.1.5                |
| Site plan application                                     | 2.2.15               |
| Solicitation document                                     | 2.1.6                |
| Summary of expenses                                       | 2.3.4                |
| Supplemental instruction                                  | 2.3.8                |
| Task Order  | 2.2.11, 2.2.16       |



# Rev. 6/1/2019 Capital Projects Materials

Section 3.6

| Title Report               | 2.6.5                  |
|----------------------------|------------------------|
| Titles                     | 2.2.17                 |
| Transmittals               | 2.2.4, 2.2.6, 2.2.8,   |
|                            | 2.2.9, 2.2.14, 2.2.15, |
|                            | 2.2.19, 2.3.9, 2.4.4,  |
|                            | 2.5.1                  |
| UFI                        | 2.5.1                  |
| Utility Service Work Order | 2.2.11                 |
| VDOT                       | 2.2.8, 2.2.14          |
| Vendor contract list       | 2.6.2, 2.6.4           |





**Project Administrators Handbook** 

| / | 1/2019  | KENISIOH LISU  | Section 2     |
|---|---------|--|---------------|
|   | Section | Section Title  | Revision Date |
|   | 1       | Process Matrix   | 2/20/2015     |
|   | 2.1.1   | Kick-off   | 6/1/2019      |
|   | 2.1.2   | Planning Commission  | 2/20/2015     |
|   | 2.1.3   | Architectural Review Board   | 2/20/2015     |
|   | 2.1.4   | Appoint Selection Committee  | 6/1/2019      |
|   | 2.1.5   | Design Scope of Work   | 6/1/2019      |
|   | 2.1.6   | Requests for Proposal (RFP)  | 6/1/2019      |
|   | 2.2.1   | Programming  | 2/20/2015     |
|   | 2.2.2   | Public Hearings  | 6/1/2019      |
|   | 2.2.3   | Public Information Meeting   | 6/1/2019      |
|   | 2.2.4   | Alternative Analysis   | 6/1/2019      |
|   | 2.2.5   | Contract Modifications   | 6/1/2019      |
|   | 2.2.6   | Design Field Inspection  | 2/20/2015     |
|   | 2.2.7   | Schematics   | 6/1/2019      |
|   | 2.2.8   | Environmental Impact Studies   | 6/1/2019      |
|   | 2.2.9   | Environmental Permitting   | 6/1/2019      |
|   | 2.2.10  | Procure Interior Design  | 6/1/2019      |
|   | 2.2.11  | Task Order   | 6/1/2019      |
|   | 2.2.12  | Interiors  | 2/20/2015     |
|   | 2.2.13  | Design Development (Buildings & Parks)   | 2/20/2015     |
|   | 2.2.14  | Design Development (Roads)   | 6/1/2019      |
|   | 2.2.15  | Site Permitting  | 2/20/2015     |
|   | 2.2.16  | Survey   | 6/1/2019      |
|   | 2.2.17  | Plat Preparation   | 6/1/2019      |
|   | 2.2.18  | Construction Documents   | 6/1/2019      |
|   | 2.2.19  | Building Permit Review and Permitting  | 2/20/2015     |
|   | 2.2.20  | Invoices   | 6/1/2019      |
|   | 2.3.1   | Invitation for Bid (IFB)   | 6/1/2019      |
|   | 2.3.2   | Change Order   | 6/1/2019      |
|   | 2.3.3   | Request for Payment  | 6/1/2019      |
|   | 2.3.4   | Draw Downs for Bond or Lease-Funded Projects                                       | 6/1/2019      |
|   | 2.3.5   | Withholding and Releasing Retainage  | 6/1/2019      |
|   | 2.3.5-B | Withholding and Releasing Retainage (Design-Build)                                 | 2/20/2015     |
|   | 2.3.6   | Inspection   | 6/1/2019      |
|   | 2.3.7   | Commissioning  | 2/20/2015     |
|   | 2.3.8   | Construct (Buildings and Parks)  | 2/20/2015     |
|   | 2.3.9   | Construct (Roads)  | 6/1/2019      |
|   | 2.3.10  | Punchlist Walk Through (Buildings)   | 6/1/2019      |
|   | 2.3.11  | Punchlist Walk Through (Roads)   | 6/1/2019      |
|   | 2.3.12  | Construction Information on Social Media   | 6/1/2019      |
|   | 2.3.13  | Procure & Install Furniture & Equipment  | 2/20/2015     |
|   | 2.3.14  | Procure & Install OIT Data and Telecom Wiring                                      | 2/20/2015     |
|   | 2.3.15  | Internal Forces Road Construction  | 2/20/2015     |
|   | 2.3.16  | Design-Build Two Phase Selection RFQ and RFP                                       | 6/1/2019      |
|   | 2.3.17  | Active Construction Projects Lane Shifts or Lane Closure Public Notification Proce |               |
|   | 2.4.1   | Final Occupancy  | 6/1/2019      |
|   | 2.4.2   | Acquire Insurance  | 2/20/2015     |
|   | 2.4.2   | ·  |               |
|   |         | Warranty Period  | 6/1/2019      |
|   | 2.4.4   | VDOT Street Acceptance   | 2/20/2015     |
|   | 2.4.5   | Special Event/Ribbon Cutting   | 2/20/2015     |
|   | 2.4.6   | Plat Development   | 2/20/2015     |
|   | 2.4.7   | Release of Liens   | 2/20/2015     |
|   | 2.4.8   | Accounting Close-Out   | 6/1/2019      |
|   | 2.4.9   | VDOT Audit   | 2/20/2015     |
|   |         |  |               |



| 2.4.10 | Transition of Operating Budget                                  | 2/20/2015  |
|--------|---|------------|
| 2.5.1  | Identify Existing Utilities and Conflicts                       | 6/1/2019   |
| 2.5.2  | Negotiate Fee Arrangement                                       | 6/1/2019   |
| 2.5.3  | Acquire Easements   | 2/20/2015  |
| 2.5.4  | Upgrades (Betterments)  | 6/1/2019   |
| 2.5.5  | Request/Authorize Work  | 2/20/2015  |
| 2.5.6  | Dispose of Old Material   | 2/20/2015  |
| 2.5.7  | Relocation of Utilities   | 2/20/2015  |
| 2.6.1  | Land Acquisition Overview                                       | 2/20/2015  |
| 2.6.2  | Title Search  | 2/20/2015  |
| 2.6.3  | Receive Plat  | 2/20/2015  |
| 2.6.4  | Secure Appraisal  | 2/20/2015  |
| 2.6.5  | Make the Offer  | 2/20/2015  |
| 2.6.6  | Negotiate   | 2/20/2015  |
| 2.6.7  | Settlement  | 2/20/2015  |
| 2.6.8  | Condemnation  | 6/1/2019   |
| 2.6.9  | Court Proceeding  | 6/1/2019   |
| 2.7.1  | Determining Debt Sale Amount and Timing                         | 2/20/2015  |
| 2.7.2  | Bond/Lease Sale   | 6/1/2019   |
| 2.7.3  | Arbitrage Process   | 6/1/2019   |
| 2.7.4  | Post-Sale Debt Maintenance                                      | 6/1/2019   |
| 2.7.5  | Budget Transfer   | 6/1/2019   |
| 2.7.6  | Internal Payment for Development Service Fees (Journal Entries) | 6/1/2019   |
| 2.8.1  | Board Agenda  | 6/1/2019   |
| 2.8.2  | Life Cycle Management   | 2/20/2015  |
| 3.1    | Glossary  | 6/1/2019   |
| 3.2    | Abbreviations   | 6/1/2019   |
| 3.3.1  | Office of Executive Management                                  | 2/20/2015  |
| 3.3.2  | Department of Finance   | 2/5/2008   |
| 3.3.3  | Department of Public Works                                      | 2/20/2015  |
| 3.3.4  | Department of Transportation                                    | 6/1/2019   |
| 3.3.5  | Park Grounds, Facility and Support Services                     | 2/20/2015  |
| 3.4    | External Contacts   | 6/1/2019   |
| 3.5    | Capital Project Forms   | 6/1/2019   |
| 3.6    | Materials   | 6/1/2019   |
| 4      | Revision List   | 6/1/2019   |
|        |   | 0, -, -010 |

